

JS8C

The Branner Geological Library



LELAND STANFORD JUNIOR UNIVERSITY

THE COAL QUESTION



THE
COAL QUESTION

*An Inquiry Concerning the Progress of the
Nation, and the Probable Exhaustion
of our Coal-mines*

BY THE LATE
W. STANLEY JEVONS, M.A., LL.D., F.R.S.

EDITED BY
A. W. FLUX, M.A.

SOMETIME FELLOW OF ST. JOHN'S COLLEGE, CAMBRIDGE
WILLIAM DOW PROFESSOR OF POLITICAL ECONOMY IN MCGILL UNIVERSITY, MONTREAL
FORMERLY STANLEY JEVONS PROFESSOR AND CORDEN LECTURER IN THE
OWENS COLLEGE, MANCHESTER

THIRD EDITION, REVISED

London
MACMILLAN AND CO., LIMITED
NEW YORK: THE MACMILLAN COMPANY

1906

All rights reserved

St

Non progredi est regredi.

210210

"The progressive state is in reality the cheerful and the hearty state to all the different orders of the society ; the stationary is dull ; the declining melancholy."

ADAM SMITH

First Edition, 1865

Second Edition, Revised, 1866

Third Edition, Revised, 1906


Preservation '88

CONTENTS

	PAGE
EXPLANATION OF PLATES	vii
PREFACE TO THE THIRD EDITION	ix
PREFACE TO THE SECOND EDITION	xxix
CHAPTER I	
INTRODUCTION AND OUTLINE	I
CHAPTER II	
OPINIONS OF PREVIOUS WRITERS	15
CHAPTER III	
GEOLOGICAL ASPECTS OF THE QUESTION	40
CHAPTER IV	
OF THE COST OF COAL MINING	56
CHAPTER V	
OF THE PRICE OF COAL	79
CHAPTER VI	
OF BRITISH INVENTION	100
CHAPTER VII	
OF THE ECONOMY OF FUEL	137
CHAPTER VIII	
OF SUPPOSED SUBSTITUTES FOR COAL	158

CHAPTER IX	
OF THE NATURAL LAW OF SOCIAL GROWTH	PAGE 191
CHAPTER X	
OF THE GROWTH AND MIGRATIONS OF OUR POPULATION .	202
CHAPTER XI	
OF THE CHANGE AND PROGRESS OF OUR INDUSTRY . . .	233
CHAPTER XII	
OF OUR CONSUMPTION OF COAL	261
CHAPTER XIII	
OF THE EXPORT AND IMPORT OF COAL	285
CHAPTER XIV	
OF THE COMPARATIVE COAL RESOURCES OF DIFFERENT COUNTRIES	320
CHAPTER XV	
OF THE IRON TRADE	368
CHAPTER XVI	
PROBLEM OF THE TRADING BODIES	410
CHAPTER XVII	
OF TAXES AND THE NATIONAL DEBT	437
CHAPTER XVIII	
CONCLUDING REFLECTIONS	454
INDEX	461

PLATE I.



EXPLANATION OF PLATES

PLATE I of the frontispiece reproduces Jevons' original frontispiece with the following changes :—

i. The curves of population and of imports are carried on to later dates than in the original.

ii. The progress of the vend of coal from Newcastle is traced at decennial intervals between 1800 and 1861. The following data, derived from the authority quoted by Jevons (p. 262), for years preceding 1845, and, for subsequent years, from the *Transactions of the North of England Institute of Mining Engineers*, vol. xii, 1862-3, p. 169 (see also vol. xv, p. 257), show the total vend at intervals of ten years.

VEND OF COAL FROM NEWCASTLE (see also p. 262)

Year	Tons	Year	Tons
1810	2,834,326	1840	5,587,384
1820	3,403,225	1850	8,471,685
1830	3,630,303	1861	10,527,581 ¹

¹ Including 162,934 tons sent by rail.

iii. The curve showing what the output would become if it continued to increase at the rate determined by Jevons (p. 272) is supplemented by a similar curve showing the results of a continued growth at the rate experienced for the last quarter of a century (pp. 281-2). As with the former, so with the latter, the results show that the rate on which the curve is calculated cannot be continued for a long period.


Plate II is drawn to a logarithmic scale, so that progress at a uniform rate is represented by a straight line sloping upwards across the page. The figures for foreign countries, for and after 1868, are taken from the annual volumes of *Mineral Statistics for the United States*. For earlier years various sources have been employed, chiefly the Report of the Argyll Commission. For the United States the returns previous to 1880 are less complete than those for later years. In the earlier years the

anthracite returns represent sales, not output. The figures for the first few years of the diagram are based on tables published by the U.S. Geological Survey, and on the census return for 1860.

To bring the line relating to the world's output within the limits of the page, it has been made to represent one-tenth of the entire world's output. To show the whole of the world's output on the same scale as the output of individual countries included in the diagram, the line would only need to be moved upwards parallel to itself through about $3\frac{1}{8}$ inches. The line representing British exports of coal is based on figures inclusive of bunker coal shipped on foreign-going ships. For the years before 1873 the return of bunkers is lacking, and an allowance based on the tonnage of steam vessels cleared from British ports has been made.

(For tables of production in different countries, *cf.* Chap. xiv, *passim*, especially p. 365. For exports, *cf.* pp. 318-9.)

PLATE II.



This diagram is drawn on a logarithmic scale, so that a uniform rate of increase per cent from year to year is represented by a straight line. A diminishing rate of increase yields a line of decreasing slope, a growing rate one of increasing slope. Lines whose directions are parallel represent equal rates of increase, whatever the absolute amounts represented.

PREFACE TO THE THIRD EDITION

THE extent to which the argument advanced by Jevons, in reference to the exhaustibility of British coal resources, has been misunderstood, is surprising in view of the care which he took to make his position clear. The Royal Commissions appointed in 1866 and in 1901 to investigate the question, in spite of the careful study which each of them gave to the important issues involved, both shared the general misunderstanding. In their reports Jevons is referred to as calculating that the coal consumption of the United Kingdom would reach certain very large amounts in the near future; and, a divergence being shown between actual experience and what is called his prophecy, his argument is discredited. Now Jevons himself, in the text of Chapter xii (p. 274), took pains to point out that the figures set forth (p. 272) are merely a state-

ment of how great the consumption of coal would become if the rate of progress shown at the time at which he wrote were maintained. It is an absolutely fundamental point in his argument that that rate could not long be maintained, and that the general prosperity of the nation must be affected by the inevitable reduction of the rate of increase of coal consumption. Though hesitating to name the date at which the reduction would become marked, he stated clearly that, in his opinion, it could not be as much as a century distant. In view of this, the fact that a decreased rate of growth became manifest within twenty years can hardly be regarded as a disproof of the validity of his arguments.

Some critics have, with great pains, worked out the effects of a progressive rate of diminution of the annual increase in coal output, based on the difference between that annual increase as noted by Jevons and as revealed by the returns for later years. The elaborate tables, printed at length in an appendix to the reports of the recent Royal Commission, in which Mr. R. Price-Williams

gave a revised version of tables presented to the Commission of 1871, afford an example of this. Though calculations on these lines appear to be intended as a refutation of the arguments of Jevons, they embody, in truth, the very error of which their compilers accuse Jevons. They are based on the assumption that the rates of change observed in the recent past will continue unaltered into the distant future. Though, by the exercise of proper care, the reader of these tables can assure himself that they are not intended to embody a prophecy, but merely to represent what is implied by the persistence of existing rates of movement, there is little in the tables themselves, or in the reflections naturally based on a consideration of their results, to compel attention to their hypothetical character. Now Jevons used his tables to show that the rate of growth manifested in them could not be maintained for any long period of time. In this may be seen the superiority of his method over that of his critics.

The experience of the last thirty years shows a rate of progress of the British coal output

nearly unchanged, if we base the comparison, not on single years, but on broader averages. In detail, a decrease of the rate of progress, followed by a recovery, is noted. In view of this, no attempt is made in the text to set forth the results of an assumed progressive rate of decrease in the annual addition to output. It is shown that, even at the average rate of progress manifested in the last quarter of the nineteenth century, the annual output would, by the end of the twentieth century, amount to some 1,500,000,000 tons. Hence Jevons' argument, that a reduced rate of progress must set in before the end of a century from the time at which he wrote, may be repeated. There is no conflict between this view and that set forth in the reports of the recent Royal Commission, in spite of the apparent belief of the Commissioners that the experience of Jevons might serve as a warning to them of what to avoid. That the reduction is inevitable is clear, though it is submitted that the data available do not afford a reliable basis for a calculation of the approximate date when growth of output will cease.

A point to be noted in passing is that the Commission reported that the average rate of increase of output for the last thirty years has been $2\frac{1}{2}$ per cent per annum. This rate results from a comparison of individual years at the beginning and end of the period in question. If we compare the five years 1870-74 with the five years 1900-04, the rate of increase per annum is found to have averaged but $2\frac{1}{3}$ per cent over the interval of thirty years. The difference between the $2\frac{1}{2}$ per cent per annum, reported by the Commission, and the rate of $2\frac{1}{3}$ per cent. determined by the method named is considerable. A rate of progress of $2\frac{1}{2}$ per cent per annum, on the output of 1870-74, would have resulted in an output for the five years 1900-04 exceeding that actually recorded by about 27,000,000 tons yearly. In the computations of the text, and in the frontispiece, the rate of increase taken to represent the facts of the recent past has been 2 per cent per annum (see p. 281), and the second diagram of the frontispiece will make it clear how nearly uniform the average rate has been, and how indecisive as yet are

the indications of a progressive decrease of that rate.

This second diagram brings out also the steadiness of the rates of increase of output in Germany, France, Belgium, and in the world as a whole, as also of British coal exports. In the United States, development has progressed so rapidly in the last decade that the high rate of annual increase in coal production, which had prevailed for a dozen years before, has undergone acceleration. A study of the diagram will show that, in respect to coal output, the United Kingdom took the second place among the nations in 1899. Should the rates of progress recently prevalent be maintained for so long, the diagram further shows that even the second place will only be held during about two decennia.

The most important change in the general situation, so far as relates to the subject of this book, since it was originally written, is the development of the coal resources of Germany. This has necessitated substantial changes in the chapter dealing with the coal resources of different countries, and introduces new considerations into the arguments relating to actual and

prospective foreign competition with British industry. The investigations of the last ten years have done more than anything previously known to demonstrate the solidity of the basis on which the German industrial fabric is reared on its material side. In the text (p. 324 *et seq.*) reference is made to the statements of Herr Oskar Simmersbach on this subject, but the material on which those statements are based is summarised in Mr. Bennett H. Brough's report to the recent Royal Commission, printed in Part XI of the Appendices to the Final Report. It is in collating this information, rather than in calling attention to any considerable mass of newly ascertained facts, that Herr Simmersbach has been led to the remarkable results cited in the text. To anyone who shares the views expressed by Jevons, on the supreme importance of coal in relation to industrial development, the advance of Germany, like that of the United States, will appear to have resulted from the natural conditions of the territory occupied by an energetic and intelligent race, rather than from the conditions created by legislatures.

In looking forward to the future, and in

considering the forecast of the authority cited, namely, that Germany is destined to succeed to the commercial and industrial inheritance of Britain, the great depth at which much of the coal included in his estimates lies cannot be ignored as a factor in the problem. Apart from unproved coalfields, in view of the rates of increase of output which now prevail in the two countries, it would seem probable that the exhaustion of the British deposits will not progress much, if at all, more rapidly, in relation to their total contents, than will be the case with the German coal. Unless the unproved areas are found to yield much larger quantities of good coal, accessible at moderate cost, in Germany than in Great Britain, the rise in the cost of coal due to approaching exhaustion will proceed *pari passu* in the two countries, even if it be not more rapid there than here. In the meantime, however, the growing annual output, and the revelation of the extensive resources of the German coal mines, are matters of the utmost importance to the industrial communities of Great Britain.

Looking beyond these islands to the daughter

states across the seas, the reported coal resources of Canada and Australia suggest the reflection that, even though an increasing cost of power in Britain involve the decay here of the industries on which our country's great preponderance has been based, the mercantile and industrial greatness of the British Empire may not pass away. The future pictured by Jevons on pp. 429 and 430 is one the consideration of which has by so much the greater interest as the conditions on which its advent depends approach nearer to their realisation.

The discussion of possible substitutes for coal as a source of mechanical energy, which occupies Chapter viii, has needed but little change or addition to the exhaustive treatment given it by Jevons. In one direction there does appear to be scope for an addition to his discussion, namely, in reference to water-power used to develop electric energy. Of late years great strides have been taken in the utilisation of waterfalls and streams in this way. So much, in fact, has been done to perfect the appliances used that even the most economical of known methods of generating electricity by the use

of coal in this country fail to reach the low level of cost from favourably situated water-powers in some other countries. In considering the coal resources of various countries, one of the two points to which Jevons directed particular attention was the possibility of "a system of manufacturing industry capable of competing with ours" being supported on such coal resources (p. 327). Clearly, where cheap power can be obtained without the use of coal, the lack of coal is not the only matter to which attention must be directed. An industry competing with ours might develop in a country whose supplies of coal were scanty if its water-powers were sufficiently extensive. The absence from the text of any attempt to estimate the degree in which, in different countries, water-power may supplement or replace coal is due in part to the difficulty of obtaining information really meeting the needs of the case. So far as developments have proceeded up to the present, the position appears rather to resemble that of the majority of countries in respect to coal, to which Jevons applied the words (p. 327): "none are at all capable of competing in quality

or extent with our coalfields. They will prove very useful in furnishing a supply for local industry” The same reasons which permitted Jevons to pass over these coalfields of minor importance must serve as the chief justification for omitting any but a passing mention of the utilisation of water-power in modern times. As regards Great Britain, the evidence laid before the recent Royal Commission showed that the amount of water-power from streams, available for the development of electric energy, is so small as not to affect seriously the question of coal consumption. Other countries may find—are finding—in their water-powers a useful and effective substitute for coal. Thus there is afforded a forcible illustration of the reflection of Jevons (p. 188) that the advantage possessed by Great Britain in her abundant coal-deposits does not extend to other possible sources of power.

Much attention was devoted by the recent Royal Commission to the possibility of effecting economies in the consumption of coal, and it was shown that very large economies are perfectly feasible. In general, however, the

adoption of such economies needs the stimulus of a high price for coal. These economies, too, are open to our competitors equally with ourselves, and thus competition operates to compel their adoption in advance of the high prices consequent on approaching exhaustion.

In considering the history of coal production during the nineteenth century, the tables of Chapter xiv make clear the fact that, not in Great Britain alone, but also in neighbouring Continental countries, the increase of output proceeded with much greater rapidity before 1865 than it has done since about that date. The introduction of the steam-engine in modern industry and transport caused a much more rapid growth in fuel production than sufficed for the maintenance of steam-driven industry when once coal had been established as the general source of power. It follows that the transition, from progress in coal production at the rate of $3\frac{1}{2}$ per cent. per annum to progress at the rate of 2 per cent. per annum, is not necessarily the sign of a reduced degree of general welfare. But, whether the experience of the last quarter of a century be or be not

a beginning of that decline in our manufacturing prosperity to which Jevons looked forward in a longer future, the substitution of a slower rate of progress, or a stationary output, for the actual advance at the rate of 2 per cent. per annum, will necessarily mark a check in our industrial progress. And that check must be experienced in a future not far distant. Should we hasten it by placing obstacles in the way of the expansion of those industries in which coal plays so important a part? Or should we not rather, while pressing as far as possible the advantages which are ours in the present, prepare for those phases of industrial advance which are more suited to a nation unprovided with an abundance of cheap coal?

The more firmly we are convinced of the exhaustible nature of the basis of our present material prosperity, and of the comparatively near approach of the end of the plenty and cheapness on which we have flourished, the more urgent is the consideration of measures aimed at the amelioration of the condition of the future inhabitants of these islands. Jevons strongly urged the speedy reduction of the

National Debt. As the lapse of forty years sees the Debt swollen once more nearly to the dimensions it had in 1865, while the reserves of coal have been reduced substantially in the interval, what was urgent in 1865 is even more urgent to-day. The fact that each generation is apt to find its own burdens quite heavy enough finds illustration in the renewed growth in the National Debt after a long period of reduction. The injustice of handing on to our descendants a country whose fuel resources are seriously impoverished and which is heavily burdened with public debt is sufficiently manifest.

In other ways of meeting our obligations to our successors somewhat more effective progress has been made in the last forty years than in the matter of debt redemption. By the establishment of a system of public education, and by raising the age at which children may be legally employed in industry, something has been done towards meeting those obligations. These measures, urged in the preface to the second edition, have been embodied in legislation. But these achieve-

ments fall far short of what the situation demands. The renewed consideration of the case urged by Jevons should serve to stimulate to further action along the lines indicated by him.

It remains to state the general scheme of revision of the text which has been followed in preparing this new edition. To attempt to rewrite the book, preserving its method and spirit, but taking account of the knowledge accumulated in the forty years since its original issue, was clearly undesirable. To reprint the text as it was, using footnotes and appendices to supply pertinent information of later date than the text, was a possible plan, but one which would have demanded a constant, and often unnecessary, effort on the part of the reader. In selecting a course intermediate between these two, the editor has sought to preserve the text unaltered as far as might conveniently be done, while relieving the reader, as far as possible, from the necessity of the constant vigilance needed to remember that the standpoint is that of forty years ago.

In Chapters ii to ix, a few verbal

alterations, together with some footnotes, and notes at the end of Chapters ii and v, have been judged sufficient for the purpose indicated, while the references to Mr. Vivian's mode of estimating the resources of the South Wales coal area have been omitted from Chapter ii.

In Chapter x and the first part of the following chapter, the tables of population, etc., have been continued to date in the text, rather than break them into two parts, one in the text, the other in footnotes.

Chapter xiii has been changed but slightly, except in one point, namely, the statistical study of freight rates. On pp. 266-71 of the second edition an admirable study of the freight market of forty years ago is given. In view of the revolutionary changes which have occurred in the general and comparative levels of ocean freights, it has been reluctantly omitted from this edition.

In Chapters xiv and xv a considerable amount of reconstruction and some addition was unavoidable. It has been made with as little change of the original text as seemed consistent with a reasonable statement of the

facts now known. Where an opinion, such as that relating to Belgium's possible competition with Great Britain (p. 337), seemed to be such that the later developments might have left the author's view unchanged, the editor has not considered himself at liberty to alter it, even though, in some cases, he may not share it.

The first chapter forms practically the author's preface to the first edition, in which the numbering of chapters began with what became Chapter ii in the second edition. It has, consequently, been left with but trivial changes in phraseology, just as the preface to the second edition has been reprinted without change. In reading both, it must be remembered that the situation dealt with is that presented at the time at which Jevons wrote them.

A second case in which it has been judged advisable to make no attempt to revise the text is that of the latter part of Chapter xi and the whole of Chapter xii, in which the rate of progress of industry and of coal-consumption is treated. More ample informa-

tion than was available to Jevons is now at our disposal, but the data he used are repeated in the text, later figures being set forth in a note at the end of Chapter xii.

The "Problem of the Trading Bodies," treated in Chapter xvi, has also been reproduced without change. As it stands it is easy to take exception to the position assigned to Germany. The nature of the argument is not essentially altered by admitting the industrial development of Germany, as well as of the United States, as a factor of the first importance in the problem. No revision of the argument, so as to fit it to the conditions existing at the present time, could have made up for the loss to the student which would have been involved in discarding Jevons' masterly exposition of the subject.

In like manner the following chapter on "Taxes and the National Debt" has been repeated without modification, while the final chapter needed no other revision than that which it had received at Jevons' own hands.

Additions and changes made in the text by the editor are marked by square brackets, thus

[], except in the case of quite trivial verbal alterations. No such mark has been deemed necessary to distinguish footnotes added to those of the original version. These latter being almost exclusively references, and the references added being rarely to works of a date such as could have appeared in the second edition, confusion between original and added matter is unlikely to arise. The notes given as appendices to some of the chapters needed no mark to distinguish them from the author's text.

In all changes, the purpose in view has been the reproduction of Jevons' book, with the additional information necessary to adapt it for use in reference to the current situation, and with the least change consistent with that general aim.

A copy of the volume, on the margins of which Jevons had begun the work of revision, was found by Mrs. Jevons. Unfortunately this copy contained no indication of any plan of rewriting, the revision being confined to verbal changes, and only extending to Chap. vi pp. 100-104, Chap. viii pp. 158-160, Chap. ix

and Chap. xviii. The changes indicated have, of course, been embodied in this edition. It is a matter for great regret that the author's revision did not extend to those chapters which have undergone most change in the present edition.

The evidence taken by the Royal Commission on Coal Supplies has been of a value which it would be hard to overestimate in the preparation of this edition. To Mr. H. Stanley Jevons, who has kindly read the proofs, and to colleagues who have aided me by directing me to sources of needed information, I desire to express my indebtedness and my gratitude. I trust that the course followed in the arrangement of matter in this edition will commend itself to the numerous admirers of the book and of its author

A. W. FLUX.

January, 1906

PREFACE TO THE SECOND EDITION

I AM desirous of prefixing to the second edition of the following work a few explanations which may tend to prevent misapprehension of its purpose and conclusions.

The expression "exhaustion of our coal mines" states the subject in the briefest form, but is sure to convey erroneous notions to those who do not reflect upon the long series of changes in our industrial condition which must result from the gradual deepening of our coal mines and the increased price of fuel. Many persons perhaps entertain a vague notion that some day our coal seams will be found emptied to the bottom, and swept clean like a coal-cellar. Our fires and furnaces, they think, will then be suddenly extinguished, and cold and darkness will be left to reign over a depopulated country. It is almost needless to say, however, that our

mines are literally inexhaustible. We cannot get to the bottom of them; and though we may some day have to pay dear for fuel, it will never be positively wanting.

I have occasionally spoken in the following pages of "the end," of the "instability of our position," and so forth. When considered in connection with the context, or with expressions and qualifications in other parts of the volume, it will be obvious that I mean not the end or overturn of the nation, but the end of the present progressive condition of the kingdom. If there be a few expressions which go beyond this, I should regard them as speculative only, and should not maintain them as an essential part of the conclusions.

Renewed reflection has convinced me that my main position is only too strong and true. It is simply that we cannot long progress as we are now doing. I give the usual scientific reasons for supposing that coal must confer mighty influence and advantages upon its rich possessor, and I show that we now use much more of this invaluable aid than all other countries put together. But it is impossible we

should long maintain so singular a position ; not only must we meet some limit within our own country, but we must witness the coal produce of other countries approximating to our own, and ultimately passing it.

At a future time, then, we shall have influences acting against us which are now acting strongly with us. We may even then retain no inconsiderable share of the world's trade, but it is impossible that we should go on expanding as we are now doing. Our motion must be reduced to rest, and it is to this change my attention is directed. How long we may exist in a stationary condition I, for one, should never attempt to conjecture. The question here treated regards the length of time that we may go on rising, and the height of prosperity and wealth to which we may attain. Few will doubt, I think, after examining the subject, that we cannot long rise as we are now doing.

Even when the question is thus narrowed I know there will be no want of opponents. Some rather hasty thinkers will at once cut the ground from under me, and say that they never supposed we should long progress as we

are doing, nor do they desire it. I would make two remarks in answer.

Firstly, have they taken time to think what is involved in bringing a great and growing nation to a stand? It is easy to set a boulder rolling on the mountain-side; it is perilous to try to stop it. It is just such an adverse change in the rate of progress of a nation which is galling and perilous. Since we began to develop the general use of coal, about a century ago, we have become accustomed to an almost yearly expansion of trade and employment. Within the last twenty years everything has tended to intensify our prosperity, and the results are seen in the extraordinary facts concerning the prevalence of marriage, which I have explained in pp. 222—225, and to which I should wish to draw special attention. It is not difficult to see, then, that we must either maintain the expansion of our trade and employment, or else witness a sore pressure of population and a great exodus of our people.

The fact is, that many of my opponents simply concede the point I am endeavouring to prove without foreseeing the results, and without,

again, giving any reasons in support of their position.

Secondly, I do not know why this nation should not go on rising to a pitch of greatness as inconceivable now as our present position would have been inconceivable a century ago. I believe that our industrial and political genius and energy, used with honesty, are equal to anything. It is only our gross material resources which are limited. Here is a definite cause why we cannot always advance.

Other opponents bring a more subtle objection. They say that the coal we use affords no measure of our industry. At a future time, instead of exporting coal, or crude iron, we may produce elaborate and artistic commodities depending less on the use of coal than the skill and taste of the workman. This change is one which I anticipated (see p. 429). It would constitute a radical change in our industry. We have no peculiar monopoly in art, and skill, and science as we now have in coal. That by art and handicraft manufactures we might maintain a moderate trade is not to be denied, but all notions of manufacturing and maritime supre-

macy must then be relinquished. Those persons very much mistake the power of coal, and steam, and iron, who think that it is now fully felt and exhibited; it will be almost indefinitely greater in future years than it now is. Science points to this conclusion, and common observation confirms it. These opponents, then, likewise concede what I am trying to show, without feeling how much they concede. They do not seem to know which is the sharp edge of the argument.

A further class of opponents feel the growing power of coal, but repose upon the notion that economy in its use will rescue us. If coal become twice as dear as it is, but our engines are made to produce twice as much result with the same coal, the cost of steam-power will remain as before. These opponents, however, overlook two prime points of the subject. They forget that economy of fuel leads to a great increase of consumption, as shown in the chapter on the subject; and, secondly, they forget that other nations can use improved engines as well as ourselves, so that our comparative position will not be much improved.

It is true that where fuel is cheap it is wasted,

and where it is dear it is economised. The finest engines are those in Cornwall, or in steam-vessels plying in distant parts of the ocean. It is credibly stated, too, that a manufacturer often spends no more in fuel where it is dear than where it is cheap. But persons will commit a great oversight here if they overlook the cost of an improved and complicated engine, which both in its first cost, and its maintenance, is higher than that of a simple one. The question is one of capital against current expenditure. It is well known that nothing so presses upon trade as the necessity for a large capital expenditure; it is so much more risked, so much more to pay interest on, and so much more abstracted from the trading capital. The fact is, that a wasteful engine pays better where coals are cheap than a more perfect but costly engine. Bourne, in his *Treatise on the Steam Engine*, expressly recommends a simple and wasteful engine where coals are cheap.

The state of the matter is as follows:—Where coal is dear, but there are other reasons for requiring motive power, elaborate engines may be profitably used, and may partly reduce the cost of the power.

But if coal be dear in one place and cheap in another, motive power will necessarily be cheaper where coal is cheap, because there the option of using either simple or perfect engines is enjoyed. It is needless to say that any improvement of the engine which does not make it more costly will readily be adopted, especially by an enterprising and ingenious people like the Americans.

I take it, therefore, that if there be any strong cause exclusive of the possession of coal which will tend to keep manufacturers here, economy of fuel and a large employment of capital may neutralise in some degree the increased cost of motive power. But so far as cheap fuel and power is the exciting cause of manufactures, these must pass to where fuel is cheapest, especially when it is in the hands of persons as energetic and ingenious as ourselves.

Finally, I may mention the argument of Mr. Vivian, that the art of coal mining will advance so that coal may be drawn from great depths without any material increase of cost. The very moderate rise of price as yet experienced apparently supports this view, and for my own part I entertain no doubt that a mine might, if

necessary, be driven to the depth of 5,000 feet. The cost at which it must be done, however, is quite another matter. The expenditure on the shaft increases in a far higher ratio than its depth; the influence of this expenditure is more than can be readily estimated, because it is risked in the first instance, and in not a few cases is wholly lost; and not only must the capital itself be repaid, but considerable amounts of compound and simple interest must be met, in order that the undertaking shall be profitable. Were the depth of mines so slight an inconvenience as Mr. Vivian would make it appear, I think we should have more deep mines. It is now forty years since the Monkwearmouth Pit was commenced, and I believe that only one deeper pit has since been undertaken, that at Dukinfield, seventeen years ago. We cannot wonder that there are so few deep pits, when we consider that it required twenty years' labour to complete the Monkwearmouth Pit, in consequence of the serious obstacles encountered (see p. 89). The Dukinfield Deep Pit, begun in June, 1849, was more fortunate, and reached the expected coal at a depth of 2,150 feet in March, 1859.

Having now candidly mentioned and discussed the strongest objections brought against the views stated in the following work, I may fairly ask the reader that he will treat these views with candour, not separating any statement from its qualifications and conditions. I have some reason to complain that this has not been done hitherto. A correspondent of *The Times* and *Mining Journal* has represented it as a consequence of my suppositions that there would, in 1961, be a population of 576 millions of people in this country, a statement wholly without foundation in the following pages.

One journal, the (London) *Examiner*,¹ has so far misrepresented me that the editorial writer, after expressly stating that he has read the book with care, says :—"Professor Jevons shrinks from endorsing the 4,000 feet theory, and stops short at 2,500 ; but why there precisely, rather than anywhere else, he does not tell us. All we can gather from him on the subject is, that when we get to that depth a complete supply of foreign coals will come in from Pennsylvania and elsewhere." If the above be compared with

¹ *Examiner*, May 19th, 1866.

what I have really said on the subjects on p. 57, and in chapter xiii., it will be seen that my statements are represented as the direct opposite of what they are. The whole article is full of almost equal misrepresentations.

I have been surprised to find how far the views expressed in some of the following chapters are merely an explicit statement of those long entertained by men of great eminence. The manner in which Mr. Mill mentioned this work in his remarkable speech on the National Debt¹ was in the highest degree gratifying. I have found, indeed, that most of what I said concerning the National Debt was unconsciously derived from Mr. Mill's own works. I have repeated it unchanged in this edition, with the exception of adding references. The fact is that no writer can approach the subject of Political Economy without falling into the deepest obligations to Mr. Mill, and it is as impossible as it is needless always to specify what we owe to a writer of such great eminence, and such wide-spread influence.

Sir John Herschel has most kindly expressed

¹ *House of Commons*, April 17th, 1866.

a general concurrence in my views, and has even said that this work contained "a mass of considerations, that as I read them seemed an echo of what I have long thought and felt about our present commercial progress."

As regards the supremacy of coal as a source of heat and power, and the impossibility of finding a substitute, I have again only interpreted the opinions of Professor Tyndall. He has kindly allowed me to extract the following from a recent letter with which he favoured me :—

"I see no prospect of any substitute being found for coal, as a source of motive power. We have, it is true, our winds and streams and tides; and we have the beams of the sun. But these are common to all the world. We cannot make head against a nation which, in addition to those sources of power, possesses the power of coal. We may enjoy a multiple of their physical and intellectual energy, and still be unable to hold our own against a people which possesses abundance of coal; and we should have, in my opinion, no chance whatever in a race with a nation which, in addition to abundant coal, has energy and intelligence approximately equal to our own.

“It is no new thing for me to affirm in my public lectures that the destiny of this nation is not in the hands of its statesmen but in those of its coal-owners; and that while the orators of St. Stephen’s are unconscious of the fact, the very lifeblood of this country is flowing away.”

And in the following passage Professor Tyndal has lately summed up the sources of power:—

“Wherever two atoms capable of uniting together by their mutual attractions exist separately, they form a store of potential energy. Thus our woods, forests, and coal-fields on the one hand, and our atmospheric oxygen on the other, constitute a vast store of energy of this kind—vast, but far from infinite. We have, besides our coal-fields, bodies in the metallic condition more or less sparsely distributed in the earth’s crust. These bodies can be oxydised, and hence are, so far as they go, stores of potential energy. But the attractions of the great mass of the earth’s crust are already satisfied, and from them no further energy can possibly be obtained. Ages ago the elementary constituents of our rocks clashed together and produced the motion of heat, which was taken up by the ether and

carried away through stellar space. It is lost for ever as far as we are concerned. In those ages the hot conflict of carbon, oxygen, and calcium produced the chalk and limestone hills which are now cold; and from this carbon, oxygen, and calcium no further energy can be derived. And so it is with almost all the other constituents of the earth's crust. They took their present form in obedience to molecular force; they turned their potential energy into dynamic, and gave it to the universe ages before man appeared upon this planet. For him a residue of power is left, vast truly in relation to the life and wants of an individual, but exceedingly minute in comparison with the earth's primitive store."¹

I learn from Mr. Hunt that his forthcoming report will show the production of coal in the United Kingdom in 1865 to be about ninety-five millions of tons, giving a considerable increase over the great total of 1864.

I would direct the attention of those who think the failure of coal so absurd a notion, and who, perhaps, would add that petroleum can

¹ *Fortnightly Review*, Dec. 31, 1865, p. 143.

take the place of coal when necessary, to the results of an inquiry lately undertaken by Mr. Hunt concerning an increase of supply of cannel coal. He finds, after a minute personal and local inquiry, that the present yearly production of 1,418,176 tons might be raised to 3,172,000 tons should the gas companies demand it and offer a sufficient price. But it appears to be clear that *such a supply could not be maintained for many years*. The Wigan cannel is estimated to last twenty years at the longest. Ten years of the assumed production would exhaust the North Wales cannel, and two authorities, Mr. Binney and Mr. J. J. Landale, agree that the Boghead oil-making coal will not last many years.

It is evident, in short, that the sudden demand for the manufacture of petroleum, added to the steady and rising demand of the gas works, will use up the peculiar and finest beds of oil and gas-making coals in a very brief period.

I have to thank Mr. Robert Hunt not only for his kindness in supplying me with a copy of the unpublished report containing these facts, but also for his readiness in furnishing the latest

available information from the Mining Record Office. The operations of this most useful institution are still crippled, in spite of Mr. Hunt's constant exertions, by the want of proper power. It was established at the suggestion of the British Association, moved by Mr. Thomas Sopwith, to preserve the plans of abandoned mines in order that the future recovery of coal or minerals now left unworked might be facilitated, and the danger from irruptions of water and foul air from forgotten workings be averted. Colliery owners are, indeed, obliged to possess plans of their workings, and to exhibit them to the Government Inspectors of Mines, but they are not obliged to deposit copies in the Mining Record Office, on the ground of non-interference with vested interests. The deposit of plans then being voluntary, very few are received, and almost all are lost or destroyed soon after the closing of the colliery. Such plans, however, are of national importance, like registers of births, deaths, and marriages, or wills and other records. It is obvious that their destruction should be rendered illegal and penal, and that after the closing of a colliery, when the

interference with private interests becomes imaginary, they should be compulsorily deposited in the Mining Record Office. It is more than twenty years since Mr. Sopwith urged these views in his remarkable pamphlet on *The National Importance of preserving Mining Records*.¹ Yet our legislation remains as it was in truly English fashion. This subject, I hope, will now receive proper attention from the Royal Commission which is about to be appointed to inquire into the subject of our coal supply.

My great obligations to Mr. Hull will be clearly seen in several parts of the work.

I am inclined to think that a careful consideration of my arguments will show them to be less speculative and more practical than appears at first sight. I have carefully avoided anything like mere romance and speculation. It would be romance to picture the New Zealander moralising over the ruins of London Bridge, or to imagine the time when England will be a mere name in history. Some day Britain may be known as a second Crete, a sea-born island crowned by

¹ See p. 21 *infra*. The necessary legislation was secured in 1872.

ninety cities. Like the Cretans, we are ruled by laws more divine than human ; we teach the use of metals, and clear the seas of robbers, and exert a mild governance over the coasts and islands. We too, like Crete, may form in remote history but a brief and half-forgotten link in the transmission of the arts from the East towards the West—transmission not without improvement.

But the subject of the following chapters, rightly regarded, seems to me to have an immediate and practical importance. It brings us face to face with duties of the most difficult and weighty character—duties which we have too long deferred and ignored. So long as future generations seemed likely for an indefinite period to be more numerous and comparatively richer than ourselves, there was some excuse for trusting to time for the amelioration of our people. But the moment we begin to see a limit to the increase of our wealth and numbers, we must feel a new responsibility. We must begin to allow that we can do to-day what we cannot so well do to-morrow. It is surely in the moment when prosperity is greatest ; when the revenue is ex-

panding most rapidly and spontaneously ; when employment is abundant for all, and wages rising, and wealth accumulating so that individuals hardly know how to expend it—then it is that an effort can best be made, and perhaps only be made, to raise the character of the people appreciably.

It is a melancholy fact which no Englishman dare deny or attempt to palliate, that the whole structure of our wealth and refined civilisation is built upon a basis of ignorance and pauperism and vice, into the particulars of which we hardly care to inquire. We are not entirely responsible for this. It is the consequence of tendencies which have operated for centuries past. But we are now under a fearful responsibility that, in the full fruition of the wealth and power which free trade and the lavish use of our resources are conferring upon us, we should not omit any practicable remedy. If we allow this period to pass without far more extensive and systematic exertions than we are now making, we shall suffer just retribution.

It is not hard to point out what kind of measures are here referred to. The ignorance, im-

providence, and brutish drunkenness of our lower working classes must be dispelled by a general system of education, which may effect for a future generation what is hopeless for the present generation. One preparatory and indispensable measure, however, is a far more general restriction on the employment of children in manufacture. At present it may almost be said to be profitable to breed little slaves and put them to labour early, so as to get earnings out of them before they have a will of their own. A worse premium upon improvidence and future wretchedness could not be imagined.

Mr. Baker, the Inspector of Factories in South Staffordshire, has given a deplorable account of the way in which women and children are employed in the brick-yards; and in the South Wales ironworks I have myself seen similar scenes, which would be incredible if described. Dr. Morgan holds that our manufacturing population is becoming degenerate; and it must be so unless, as our manufacturing system grows, corresponding restrictions are placed upon the employment of infant labour.

It will be said that we cannot deprive parents

of their children's earnings. If we cannot do it now, we can never do it; and wretched, indeed, must be a kingdom which depends for subsistence upon infant labour. But we can do it to the ultimate advantage of all, and we are bound to do it from regard to the children themselves: and anything which we may lose or spend now in education and loss of labour will be repaid many times over by the increased efficiency of labour in the next generation.

Reflection will show that we ought not to think of interfering with the free use of the material wealth which Providence has placed at our disposal, but that our duties wholly consist in the earnest and wise application of it. We may spend it on the one hand in increased luxury and ostentation and corruption, and we shall be blamed. We may spend it on the other hand in raising the social and moral condition of the people, and in reducing the burdens of future generations. Even if our successors be less happily placed than ourselves they will not then blame us.

To some it might seem that no good can come from contemplating the weakness of our national

position. Discouragement and loss of prestige could alone apparently result. But this is a very superficial view, and the truth, I trust, is far otherwise. Even the habitual contemplation of death injures no man of any strength of mind. It rather nerves him to think and act justly while it is yet day. As a nation we have too much put off for the hour what we ought to have done at once. We are now in the full morning of our national prosperity, and are approaching noon. Yet we have hardly begun to pay the moral and the social debts to millions of our countrymen which we must pay before the evening.

THE COAL QUESTION

THE COAL QUESTION

CHAPTER I

INTRODUCTION AND OUTLINE

DAY by day it becomes more evident that the Coal we happily possess in excellent quality and abundance is the mainspring of modern material civilization. As the source of fire, it is the source at once of mechanical motion and of chemical change. Accordingly it is the chief agent in almost every improvement or discovery in the arts which the present age brings forth. It is to us indispensable for domestic purposes, and it has of late years been found to yield a series of organic substances, which puzzle us by their complexity, please us by their beautiful colours, and serve us by their various utility.

And as the source especially of steam and iron, coal is all powerful. This age has been called the Iron Age, and it is true that iron is the

material of most great novelties. By its strength, endurance, and wide range of qualities, this metal is fitted to be the fulcrum and lever of great works, while steam is the motive power. But coal alone can command in sufficient abundance either the iron or the steam ; and coal, therefore, commands this age—the Age of Coal.

Coal in truth stands not beside, but entirely above, all other commodities. It is the material source of the energy of the country—the universal aid—the factor in everything we do. With coal almost any feat is possible or easy ; without it we are thrown back into the laborious poverty of early times.

With such facts familiarly before us, it can be no matter of surprise that year by year we make larger draughts upon a material of such myriad qualities—of such miraculous powers. But it is at the same time impossible that men of foresight should not turn to compare with some anxiety the masses yearly drawn with the quantities known or supposed to lie within these islands.

Geologists of eminence, acquainted with the contents of our strata, and accustomed, in the study of their great science, to look over long periods of time with judgment and enlighten-

ment, were long ago painfully struck by the essentially limited nature of our main wealth. And though others have been found to reassure the public, roundly asserting that all anticipations of exhaustion are groundless and absurd, and "may be deferred for an indefinite period," yet misgivings have constantly recurred to those really examining the question. The subject acquired new weight when prominently brought forward by Sir W. Armstrong in his Address to the British Association in 1863, at Newcastle, the very birthplace of the coal trade.

This question concerning the duration of our present cheap supplies of coal cannot but excite deep interest and anxiety wherever or whenever it is mentioned: for a little reflection will show that coal is almost the sole necessary basis of our material power, and is that, consequently, which gives efficiency to our moral and intellectual capabilities. England's manufacturing and commercial greatness, at least, is at stake in this question, nor can we be sure that material decay may not involve us in moral and intellectual retrogression. And as there is no part of the civilized world where the life of our true and beneficent Commonwealth can be a matter of indifference, so, above all, to an Englishman

who knows the grand and steadfast course his country has pursued to its present point, its future must be a matter of almost personal solicitude and affection.

The thoughtless and selfish, indeed, who fear any interference with the enjoyment of the present, will be apt to stigmatise all reasoning about the future as absurd and chimerical. But the opinions of such are closely guided by their wishes. It is true that at the best we see dimly into the future, but those who acknowledge their duty to posterity will feel impelled to use their foresight upon what facts and guiding principles we do possess. Though many data are at present wanting or doubtful, our conclusions may be rendered so far probable as to lead to further inquiries upon a subject of such overwhelming importance. And we ought not at least to delay dispersing a set of plausible fallacies about the economy of fuel, and the discovery of substitutes for coal, which at present obscure the critical nature of the question, and are eagerly passed about among those who like to believe that we have an indefinite period of prosperity before us.

The writers who have hitherto discussed this question, being chiefly geologists, have of ne-

cessity treated it casually, and in a one-sided manner. There are several reasons why it should now¹ receive fuller consideration. In the first place, the accomplishment of a Free Trade policy, the repeal of many laws that tended to restrain our industrial progress, and the very unusual clause in the French Treaty which secures a free export of coals for some years to come, are all events tending to an indefinite increase of the consumption of coal. On the other hand, two most useful systems of Government inquiry have lately furnished us with new and accurate information bearing upon the question; the Geological Survey now gives some degree of certainty to our estimates of the coal existing within our reach, while the returns of mineral statistics inform us very exactly of the amount of coal consumed.

Taking advantage of such information, I venture to try and shape out a first rough approximation to the probable progress of our industry and consumption of coal in a system of free industry. We of course deal only with what is

¹ The reader should bear in mind that this work was first published in 1865. The *Introduction and Outline*, forming practically the preface to the First Edition, has been reprinted without any attempt to adapt its phraseology to the facts of forty years later.

probable. It is the duty of a careful writer not to reject facts or circumstances because they are only probable, but to state everything with its due weight of probability. It will be my foremost desire to discriminate certainty and doubt, knowledge and ignorance—to state those data we want, as well as those we have. But I must also draw attention to principles governing this subject, which have rather the certainty of natural laws than the fickleness of statistical numbers.

It will be apparent that the first seven of the following chapters are mainly devoted to the physical data of this question, and are of an introductory character. The remaining chapters, which treat of the social and commercial aspects of the subject, constitute the more essential part of the present inquiry. It is this part of the subject which seems to me to have been too much overlooked by those who have expressed opinions concerning the duration of our coal supplies.

I have endeavoured to present a pretty complete outline of the available information in union with the arguments which the facts suggest. But such is the extent and complexity of the subject that it is impossible to notice all

the bearings of fact upon fact. The chapters, therefore, have rather the character of essays treating of the more important aspects of the question ; and I may here suitably devote a few words to pointing out the particular purpose of each chapter, and the bearings of one upon the other.

I commence by citing the opinions of earlier writers, who have more or less shadowed forth my conclusions ; and I also quote Mr. Hull's estimate of the coal existing in England, and adopt it as the geological datum of my arguments.

In considering the geological aspects of the question, I endeavour to give some notion of the way in which an estimate of the existing coal is made, and of the degree of certainty attaching to it, deferring to the chapter upon Coal Mining the question of the depth to which we can follow seams of coal. It is shown that in all probability there is no precise physical limit of deep mining, but that the growing difficulties of management and extraction of coal in a very deep mine must greatly enhance its price. It is by this rise of price that gradual exhaustion will be manifested, and its deplorable effects occasioned.

I naturally pass to consider whether there

are yet in the cost of coal any present signs of exhaustion; it appears that there has been no recent rise of importance, but that, at the same time, the high price demanded for coals drawn from some of the deepest pits indicates the high price that must in time be demanded for even ordinary coals.

A distinct division of the inquiry, comprising chapters vi. vii. and viii., treats of inventions in regard to the use of coal. It is shown that we owe almost all our arts to continental nations, except those great arts which have been called into use here by the cheapness and excellence of our coal. It is shown that the constant tendency of discovery is to render coal a more and more efficient agent, while there is no probability that when our coal is used up any more powerful substitute will be forthcoming. Nor will the economical use of coal reduce its consumption. On the contrary, economy renders the employment of coal more profitable, and thus the present demand for coal is increased, and the advantage is more strongly thrown upon the side of those who will in the future have the cheapest supplies. As it is in a subsequent chapter on the Export and Import of Coal conclusively shown that we cannot make up for a future want of

coal by importation from other countries, *it will appear that there is no reasonable prospect of any relief from a future want of the main agent of industry. We must lose that which constitutes our peculiar energy.* And considering how greatly our manufactures and navigation depend upon coal, and how vast is our consumption of it compared with that of other nations, it cannot be supposed we shall do without coal more than a fraction of what we do with it.

I then turn to a totally different aspect of the question, leading to some estimate of the duration of our prosperity.

I first explain the natural principle of population, that a nation tends to multiply itself at a constant rate, so as to receive not equal additions in equal times, but additions rapidly growing greater and greater. In the chapter on Population it is incidentally pointed out that the nation, as a whole, has rapidly grown more numerous from the time when the steam-engine and other inventions involving the consumption of coal came into use. Until about 1820 the agricultural and manufacturing populations increased about equally. But the former then became excessive, occasioning great pauperism, while it is only our towns and coal and iron districts

which have afforded any scope for a rapid and continuous increase.

The more nearly, too, we approach industry concerned directly with coal, the more rapid and constant is the rate of growth. The progress indeed of almost every part of our population has clearly been checked by emigration, but that this emigration is not due to pressure at home is plain from the greatly increased frequency of marriages in the last ten or fifteen years.¹ And though this emigration temporarily checks our growth in mere numbers, it greatly promotes our welfare, and tends to induce greater future growths of population.

Attention is then drawn to the rapid and constant rate of multiplication displayed by the iron, cotton, shipping, and other great branches of our industry, the progress of which is in general quite unchecked up to the present time. The consumption of coal, there is every reason to suppose, has similarly been multiplying itself at a growing rate. The present rate of increase of our coal consumption is then ascertained, and

¹ The marriage-rate of 1865 and 1866 was 17·6 per 1000 of the population of England and Wales. This figure has never since been surpassed, and only once nearly equalled, namely, in 1873. When Jevons wrote, therefore, the increased frequency of marriage, which he notes, was approaching its culmination.

it is shown *that, should the consumption multiply for rather more than a century at the same rate, the average depth of our coal-mines would be 4,000 feet, and the average price of coal much higher than the highest price now paid for the finest kinds of coal.*

It is thence simply inferred that *we cannot long continue our present rate of progress.* The first check to our growing prosperity, however, must render our population excessive. Emigration may relieve it, and by exciting increased trade tend to keep up our progress ; but after a time we must either sink down into poverty, adopting wholly new habits, or else witness a constant annual exodus of the youth of the country. It is further pointed out that the ultimate results will be to render labour so abundant in the United States that our iron manufactures will be underbid by the unrivalled iron and coal resources of Pennsylvania ; and in a separate chapter it is shown that the crude iron manufacture will, in all probability, be our first loss, while it is impossible to say how much of our manufactures may not follow it.

Suggestions for checking the waste and use of coal are briefly discussed, but the general conviction must force itself upon the mind, that

restrictive legislation may mar but cannot mend the natural course of industrial development. Such is a general outline of my arguments and conclusions.

When I commenced studying this question, I had little thought of some of the results, and I might well hesitate at asserting things so little accordant with the unbounded confidence of the present day. But as serious misgivings do already exist, some discussion is necessary to set them at rest, or to confirm them, and perhaps to modify our views. And in entering on such a discussion, an unreserved, and even an overdrawn, statement of the adverse circumstances, is better than weak reticence. If my conclusions are at all true, they cannot too soon be recognised and kept in mind ; if mistaken, I shall be among the first to rejoice at a vindication of our country's resources from all misgivings.

For my own part, I am convinced that this question must before long force itself upon our attention with painful urgency. It cannot long be shirked and shelved. It must rise by degrees into the position of a great national and perhaps a party question, antithetical to that of Free Trade. There will be a Conservative Party, desirous, at all cost, to secure the continued and

exclusive prosperity of this country as a main bulwark of the general good. On the other hand, there will be the Liberal Party, less cautious, more trustful in abstract principles and the unfettered tendencies of nature.

Bulwer, in one of his Caxtonian Essays, has described, with all his usual felicity of thought and language, the confiction of these two great parties. They have fought many battles upon this soil already, and the result as yet is that wonderful union of stability and change, of the good old and the good new, which makes the English Constitution.

But if it shall seem that this is not to last indefinitely—that some of our latest determinations of policy lead directly to the exhaustion of our main wealth—the letting down of our main-spring—I know not how to express the difficulty of the moral and political questions which will arise. Some will wish to hold to our adopted principles, and leave commerce and the consumption of coal unchecked even to the last; while others, subordinating commerce to purposes of a higher nature, will tend to the prohibition of coal exports, the restriction of trade, and the adoption of every means of sparing the fuel which makes our welfare and

of the importance of coal; and, in noticing the Fifeshire coal-field, expressed considerable fears as to a future exhaustion of our mines. He correctly contrasted the fixed extent of a coal-field with the ever-growing nature of the consumption of coal.

In 1812 Robert Bald, another Scotch writer, in his very intelligent *General View of the Coal Trade of Scotland*, showed most clearly how surely and rapidly a consumption, growing in a "quick, increasing series,"¹ must overcome a fixed store, however large. Even if the Grampian mountains, he said,² were composed of coal, we would ultimately bring down their summits, and make them level with the vales.

In later years, the esteemed geologist Dr. Buckland most prominently and earnestly brought this subject before the public, both in his evidence before the Parliamentary Committees of 1830 and 1835, and in his celebrated *Bridgewater Treatise*.³ On every suitable occasion he implored the country to allow no waste of an article so invaluable as coal.

Many geologists, and other writers, without

¹ P. 94.

² P. 97.

³ See also his Address to the Geological Society, Feb. 19th, 1841, p. 41.

fully comprehending the subject, have made so-called estimates of the duration of the Newcastle coal-field. In the early part of the nineteenth century this field was so much the most important and well known, that it took the whole attention of English writers. The great fields of South Wales and Scotland, in fact, were scarcely opened. But those who did not dream of the whole coal-fields of Great Britain being capable of exhaustion, were early struck by the progressive failure of the celebrated Newcastle seams. Those concerned in the coal trade know for how many years each colliery is considered good; and perhaps, like George Stephenson in early youth, have had their homes more than once moved and broken up by the working out of a colliery.¹ It is not possible for such men to shut their eyes altogether to the facts.

I give, on the following page, a tabular summary of the chief estimates of the duration of the Newcastle field.

Suffice it to remark, concerning these estimates, that the amounts of coal supposed to exist in the Newcastle field are much more accordant than the conclusions as to the probable duration of the supply. The reason of

¹ Smiles' *Engineers*, vol. iii. pp. 18, 22.

Estimates of the Duration of the Northumberland and Durham Coal-Field

Author of Estimate	Date of Estimate	Supposed Area of Coal Measures unworked	Estimated Amount of Coal	Assumed Annual Consumption of Coal	Duration of Supply Years
		Square Miles	Millions of Tons	Tons	
MacNab ¹ . .	1792	300	—	—	360
Bailey ² . . .	1801	—	—	1,866,200	200
Thomson ³ . .	1814	—	5 575	3,700,000	1000
Bakewell ⁴ . .	—	—	—	—	350
Hugh Taylor ⁵	1830	732	6,046	3,500,000	1727
Buckland ⁶ . .	1830	—	—	—	400
Greenwell ⁷ .	1846	—	—	10,000,000	331
T. Y. Hall ⁸ .	1854	750	5,122	14,000,000	365
T. Y. Hall ⁹ .	1861	800	5,027	22,500,000	223
E. Hull ¹⁰ . .	1864	685	7,226	16,001,125	450

¹ Treatise on the Coal Trade, quoted in Appendix to J. Williams' *History of the Mineral Kingdom* : Edinburgh, 1810, vol. ii. p. 267.

² *Edinburgh Review*, vol. cxi. p. 84, note. This estimate, however, seems to refer to Durham only, and to a later year than 1801. See John Bailey, *General View of the Agriculture of the County of Durham*, 1810, p. 28.

³ *Annals of Philosophy*, December, 1814.

⁴ *Introduction to Geology*, p. 192.

⁵ Report on Coal Trade, 1830, p. 77. *Edinburgh Review*, vol. li. p. 190. M'Culloch's Dictionary, art. *Coal*.

⁶ Report on Coal Trade, 1830.

⁷ and ⁸ T. Y. Hall. *Transactions of the North of England Institute of Mining Engineers*, 1854. Fordyce, *History of Coal, Coke, and Coal-Fields* : Newcastle, 1860, p. 32.

⁹ T. Y. Hall. *Transactions of the North of England Institute of Mining Engineers*, 1861, pp. 61-2.

¹⁰ *The Coal-Fields of Great Britain*, by Edward Hull, B.A. 2nd ed. p. 161. (Stanford.)

course is that the annual consumption is a rapidly growing quantity, and it is a most short-sighted proceeding to argue as if it were constant.¹ *These so-called estimates of duration are no such thing, but only compendious statements how many times the coal existing in the earth exceeds the quantity then annually drawn.*

The apparent accordance of these writers often arises, too, from the compensation of errors. Some of them assumed, most wrongly, that the known seams extended continuously over the whole area of the field; they did not allow for the less extension of the higher seams, a point we shall have to consider; and then again, even Dr. Buckland, in accordance with the prevalent opinion of those times, did not suppose that any coal existed under the magnesian limestone strata at the southern angle of the Newcastle field. In Mr. Hull's estimate, however, allowance is made for hidden coal

¹ Mr. Hall, when writing in 1854, predicted an increase of the annual output to 20,000,000 tons, a rate of production which he estimated would exhaust the coal-field in 256 years. Similarly, anticipated expansions of industry referred to in his paper of 1861 would increase the extraction to 28,500,000 tons yearly, and lessen the duration to 177 years. The output of the counties of Northumberland and Durham exceeded 28,500,000 tons for the first time in 1871. In 1904 it amounted to 48,412,627 tons.

likely to exist. He took 460 square miles as the area of the open coal measures, and 225 square miles as the available area covered by newer geological formations.

Some writers, without going into numerical detail, have explained very clearly the bearings of this question. John Holland, for instance, the author of an excellent anonymous work on coal, has made very sound remarks upon the probable duration of our coal. "While," he says,¹ "it is manifestly inconclusive to estimate according to present demand the consumption of coals for centuries to come; and still more so to assign any specific condition of society to such a remote period; we are warranted, in the first place, in assuming that the demand for this species of fuel will not diminish, but increase with every imaginable condition of the progress of society; and, secondly, we have before us the undoubted fact that our mines are not inexhaustible. In addition to this, there is the most direct evidence to show how far some of the most valuable beds in the northern coal-fields have been worked out already; at the same time, that tolerably satisfactory calcula-

¹ *A History and Description of Fossil Fuel*: 1835, chap. xxiv. p. 454.

tions have been made as to the quantity remaining unwrought."

Mr. T. Sopwith, in 1844, in an essay on *The National Importance of Preserving Mining Records* (p. 50), made the following very excellent remarks :—"The opinion that our stores of coal are all but inexhaustible rests wholly on assumed data, and not upon any accurate and detailed statistical accounts such as alone could warrant a confident opinion. This question will, ere long, become a subject of serious concern, unless some measures are taken to found our calculations on a solid basis. It is an easy matter to assume that a considerable thickness of available coal extends over hundreds of square miles; but the different opinions formed by men of the highest respectability and talent, strongly prove how meagre and unsatisfactory are the only data on which these estimates are founded. It is not, however, the mere quantity of coal that is to be considered. Especial regard must be had to its quality, depth, thickness, extent, and position. Many of the inferior seams can only be worked in conjunction with those which, by their superior quality, repay the expense of working them at depths varying from 300 to 600 yards; and it may readily be conceived, that

General Statement of the Condition of our Coal-Fields¹

Coal Group	Area in Square Miles	Coal Contents Millions of Tons	Produce in 1861 Tons	Number of Collieries, 1861
Scotch	1,920	25,300	11,081,000	424
Newcastle	1,845	24,000	34,635,884	848
Lancashire, Staf- fordshire, &c. . }	535	7,594	25,643,000	1,158
South Wales . . .	1,094	26,560	13,201,796	516
Cumberland . . .	25	90	1,255,644	28
Totals	5,419	83,544	85,817,324	2,974

¹ The following table shows the comparison between the above estimate of resources and those of the two Royal Commissions.

AVAILABLE RESOURCES OF THE PROVED COAL-FIELDS OF THE UNITED KINGDOM
(Millions of Tons)

Not exceeding 4,000 feet in depth, and after making all necessary deductions

District	Hull, 1864	Output 1865-69	Argyll Commis- sion, 1870	Output 1870- 1904	Allerton Commission, 1904	
					Total	In seams of 2 ft. and over
A. South Wales . .	26,560	76	36,940	1,010	39,928	25,691*
B. Staffs., &c. . .	7,594	77	7,027	634	9,057	8,518
C. Lancs., &c. . .		79	7,556	830	6,267	5,450
D. Midland		81	18,243	1,259	26,499	19,676
E. Northern	24,090	132	10,442	1,368	12,308	10,433
F. Scotland	25,300	69	9,843	823	15,681	11,044
G. Ireland	—	0.6	156	4	174	174
Totals	83,544	515	90,207	5,928	100,914	80,986
In concealed and un- proved coal-fields . }	—	—	56,273	—	40,722	—
Totals	—	—	146,480	—	141,636	—

* The figures for Somersetshire, included in this total, have not undergone any deduction for seams less than two feet in thickness.

It will be seen that the data provided by later and fuller investiga-

It will be seen that his estimate, in 1864, of the total contents of our coal-fields, exceeds by only an inconsiderable quantity his estimates in 1860 and 1861. I shall accept this quantity of 83,544,000,000 tons of available coal as a convenient basis for discussion, subject to whatever may be said later on, as to some of Mr. Hull's assumptions. As Mr. Hull possesses the most intimate practical acquaintance with the Lancashire and some of the Midland coal-fields, acquired in carrying out the Geological Survey, and has at his command all the published results of the survey, the experience of his coadjutors, and the writings of previous geologists, his estimate must certainly be accepted for the present.

But whether this estimate be accurate or not, it will appear that the exact quantity of coal existing is a less important point in this question than the rate at which our consumption increases, and the natural laws which govern that consumption. The question is mainly one of statistical science, and it is only as such that I venture to have anything to do with it.

Mr. Hull, indeed, has not confined himself to
 tion do not differ from those which served as the basis of Jevons' argument in any sufficient degree to invalidate that argument. A more detailed table of the resources as reported by the Allerton Commission is given at the end of the chapter (p. 38).

the geological side of the question, and his remarks upon the statistical bearings of his estimate must not be passed over, though they are far from having the same weight as his geological statements. Throughout his work, he compares the contents of each coal-field with the present annual quantity of coal drawn from it, and his remarks on the condition of the several fields are interesting and significant. The present generation, he thinks, may see the end of the Flintshire coal-field, which was largely worked in the days of shallow pits, and contains little more than twenty millions of tons for future supply.¹ The Coalbrookdale coal-field, where the present mode of iron manufacture was first established, is even further advanced towards exhaustion, and can hardly last more than twenty years.² The South

¹ *Journal of Science*, No. I, p. 29. In the third edition of his *Coal-Fields of Great Britain*, issued in 1873, after mentioning the Argyll Commission's estimate of 718 millions of tons of available coal in the coal-field, Professor Hull states (p. 151) "The quantity of coal in the actual and visible coal-field can scarcely last more than half a century." The total reported for Flintshire by the recent Royal Commission is 771 million tons of available coal unworked.

² The following is an extract from the third edition of Professor Hull's *Coal-Fields of Great Britain* (p. 137): "The coal under a very large portion of this field has been nearly exhausted, as will be apparent to anyone who crosses it by the Wolverhampton and Shrewsbury railway, when, over a large area, nothing but dismantled engine-houses and enormous piles of refuse from abandoned coal and iron mines meets the eye. The collieries have gradually migrated from the western outcrop towards the

Staffordshire field has passed the meridian of its career, and is on the verge of old age. "Its extraordinary richness has been the principal cause of its early decline, and the treasures easily acquired have been often recklessly squandered."¹

It is true that the great South Wales and east. Under these circumstances, it is probably within the mark to deduct from the original mass of coal two-thirds for the quantity already worked out." After estimating the coal remaining at 18 millions of tons, it is pointed out that it would be exhausted in thirteen years at the rate of consumption recorded for 1870. It is added: "This estimate only applies to the actual coal-field." In 1897, in *Our Coal Resources* (p. 54), Professor Hull wrote: "Over a large part of the southern and central portions of the coal-field, the beds of coal and valuable ironstone have now been worked out."

He then gave a revised estimate of the resources of the coal-field, and estimated that about 12,600,000 tons would remain unworked at the end of the nineteenth century. The estimate of the recent Royal Commission was 153,000,000 tons. The production of Shropshire in 1904 was 805,185 tons.

The increased knowledge of the resources of different districts made available in the last forty years affords other illustrations of the point under discussion here by Jevons. Thus, in Mr. J. S. Dixon's report, prepared for the Allerton Commission, on the resources of the Scottish coal-fields, we find the following remarks (p. 9):

"It is significant that, of the estimated quantity in Lanarkshire, only 45 per cent exists in seams twenty-four inches and upwards in thickness. Since the report of the former Coal Commission in 1871, till 1902, 405,933,793 tons have been worked in Lanarkshire, thus accounting for the large exhaustion of the thicker seams. . . .

"The inference, therefore, is that the output from Lanarkshire is now unlikely to much increase, and a decrease once begun will continue."

¹ *Journal of Science*, No. I. p. 30.

Scotch coal basins contain some thousands of times their present annual yield of coal.¹ But it is obvious they will have, in future years, to compensate the falling off in all the smaller and older fields, as well as to bear their own increased local demand. Coal will be got where it can most cheaply and easily be got, and the exhaustion of one field will only throw a new demand upon fresher fields. This is a process already extensively going on.

“The supply of coal in the South Staffordshire district,” says Mr. William Mathews,² “has seriously fallen off of late years, and has become quite inadequate to meet the demand occasioned by the development of its other manufacturing resources. We are, therefore, obliged to lean somewhat on the aids which the produce of the northern coal-fields opens up to us; and if, by any chance, the resources we now enjoy, from that and other districts in England, should be withheld, we should feel the inconvenience of being deprived of such resources very sensibly indeed.”

¹ With the enlarged output of the present time, we must substitute “hundreds” for “thousands,” neither field having resources equal to one thousand times the output of 1904.

² *Trans. of the North of England Institute of Mining Engineers*, vol. x. p. 74. (1862.)

The same process is taking place, by aid of railways, in many shallow coal districts, and it may proceed until the whole country is mainly dependent on one or two of the greatest coal basins. We ought, therefore, to compare the total supply within the kingdom with the total probable demand, paying little or no regard to local circumstances.

Mr. Hull has made such a comparison. He compared the 79,843 millions of tons of his first estimate¹ with the 72 million tons of coal consumed in 1859, and deduced that, at the same rate of consumption, the supply would last 1100 years.

"Yet we have no right," he very truly remarked, "to assume that such will be the actual duration; for the history of coal mining during the last half century has been one of rapid advance." Our consumption, in short, had about doubled itself since 1840; and, supposing it to continue doubling every twenty years, our "total available supply would be exhausted before the lapse of the year 2034."²

"If we had reason," he continues,³ "to expect that the increase of future years was to progress

¹ *Coal-Fields of Great Britain*, 2nd ed. p. 236.

² The calculation is not strictly correct. ³ *loc. cit.* p. 237.

in the same ratio, we might well tremble for the result; for that would be nothing less than the utter exhaustion of our coal-fields, with its concomitant influence upon our population, our commerce, and national prosperity, in the short period of 172 years!"

No sooner has Mr. Hull reached this truly alarming result than he recoils from it. "But are we," he says, "really to expect so rapid a drain in future years? I think not." Economy will reduce our consumption; the burning waste-heaps of coal will be stopped; America will relieve us from the world-wide demand for our coal, and will eventually furnish even this country with as much as we want. Such are some of the fallacious notions with which Mr. Hull, in common with many others, sought to avoid an unwelcome conclusion. More lately, he has said:¹ "Notwithstanding these facts, however, it would be rash to assume that the experience of the past is to be a criterion of the future. We neither wish for, nor expect, an increase during the remainder of the second half of this century, at all proportionate to that of the earlier half; and this view is borne out by some of the later returns. Some of our coal-fields, as has been

¹ *Journal of Science*, No. I. p. 35.

shown, have passed their meridian, and, having expended their strength, are verging to decay. Others have attained their maximum, or nearly so ; this, indeed, is the case with the majority. The younger coal-fields will have much of their strength absorbed in compensating for the falling off of the older ; so that, in a few years, the whole of our coal-producing districts will reach a stage of activity beyond which they cannot advance, but around which they may oscillate. Entertaining these views, I am inclined to place the possible maximum of production at 100 millions of tons a year ; and yet it has been shown that, even with this enormous 'output,' there is enough coal to last for eight centuries."

The reader will easily see, in the course of our inquiry, how mistaken was Mr. Hull in 1864, in supposing our production of coal to be limited to 100 millions. It has already (in 1864) exceeded 92 millions without counting the waste of slack coal, and is yet advancing by great strides.¹ And the public seems unaware that *a sudden check to the expansion of our supply would be the very manifestation of exhaustion we dread.* It would at once bring on us the rising price, the transference of industry, and the general reverse

¹ In 1904 the output of coal exceeded 232 millions of tons.

of prosperity, which we may hope not to witness in our days. And the eight centuries of stationary existence he promises us would be little set off against a nearer prospect so critical and alarming.

Facts, however, prove the hastiness of these views. The number of collieries is rapidly increasing up to the very last accounts (1864);¹ and new collieries being mostly larger works than the old ones laid in, we may conclude that coal owners are confident of pushing the production for many years to come.

The remarks of Sir W. Armstrong on this subject, in his Address to the British Association at Newcastle, in 1863, are so excellent that I quote them at length :—"The phase of the earth's existence, suitable for the extensive formation of coal, appears to have passed away for ever ; but the quantity of that invaluable mineral which has been stored up throughout the globe for our benefit is sufficient (if used discreetly) to serve the purposes of the human race for many thousands of years. In fact, the entire quantity of coal may be considered as practically inexhaustible.

¹ Since 1875 the number of collieries has decreased considerably. As the output has grown, it needs no proof that new collieries have been larger than those older ones which have been abandoned. Recent reports continue to show that new collieries are being opened out, and the latter part of the paragraph will apply to 1905 as fully as to 1864.

“Turning, however, to our own particular country, and contemplating the rate at which we are expending those seams of coal which yield the best quality of fuel and can be worked at the least expense, we shall find much cause for anxiety. The greatness of England much depends upon the superiority of her coal, in cheapness and quality, over that of other nations ; but we have already drawn, from our choicest mines, a far larger quantity of coal than has been raised in all other parts of the world put together ; and the time is not remote when we shall have to encounter the disadvantages of increased cost of working and diminished value of produce.

“Estimates have been made at various periods of the time which would be required to produce complete exhaustion of all the accessible coal in the British Islands. The estimates are certainly discordant ; but the discrepancies arise, not from any important disagreement as to the available quantity of coal, but from the enormous difference in the rate of consumption at the various dates when the estimates were made, and also from the different views which have been entertained as to the probable increase of consumption in future years. The quantity of coal yearly worked from British mines has been almost trebled during the last twenty years, and has probably increased

tenfold since the commencement of the present century; but as this increase has taken place pending the introduction of steam navigation and railway transit, and under exceptional conditions of manufacturing development, it would be too much to assume that it will continue to advance with equal rapidity.

“The statistics collected by Mr. Hunt, of the Mining Record Office, show that, at the end of 1861, the quantity of coal raised in the United Kingdom had reached the enormous total of 86 millions of tons, and that *the average annual increase in the eight preceding years* amounted to $2\frac{3}{4}$ millions of tons.

“Let us inquire, then, what will be the duration of our coal-fields if this more moderate rate of increase be maintained. By combining the known thickness of the various workable seams of coal, and computing the area of the surface under which they lie, it is easy to arrive at an estimate of the total quantity comprised in our coal-bearing strata. Assuming 4,000 feet as the greatest depth at which it will ever be possible to carry on mining operations, and rejecting all seams of less than two feet in thickness, the entire quantity of available coal existing in these islands has been calculated to amount to about 80,000 millions of tons, which, at the present rate of con-

sumption, would be exhausted in 930 years ; but with a continued yearly increase of $2\frac{3}{4}$ millions of tons would only last 212 years.

“ It is clear that, long before complete exhaustion takes place, England will have ceased to be a coal-producing country on an extensive scale. Other nations, and especially the United States of America, which possess coal-fields thirty-seven times more extensive than ours, will then be working more accessible beds at a smaller cost, and will be able to displace the English coal from every market. The question is, not how long our coal will endure before absolute exhaustion is effected, but how long will those particular coal-seams last which yield coal of a quality and at a price to enable this country to maintain her present supremacy in manufacturing industry. So far as this particular district is concerned, it is generally admitted that 200 years will be sufficient to exhaust the principal seams, even at the present rate of working. If the production should continue to increase as it is now doing, the duration of those seams will not reach half that period. How the case may stand in other coal mining districts, I have not the means of ascertaining ; but, as the best and most accessible coal will always be worked in preference to any other, I fear the

same rapid exhaustion of our most valuable seams is everywhere taking place."

With almost every part of this statement I can concur, except the calculation by a fixed annual increase of consumption, which I shall show to be contrary to the principles of the subject, and not to reach the whole truth.

Dr. Percy, the late eminent metallurgist of the School of Mines, is one whose opinions will bear great weight on this subject; and in several passages of his treatises on Metallurgy, he has expressed his misgivings. Our coal, he says, "is not only being consumed at a prodigious rate at home, but is being largely exported; and the question as to the probable duration of our coal-fields has, of late, been discussed with reasonable anxiety. In 1862 we raised 84,000,000 tons of coal, and the demand continually increases. Hitherto, owing to the abundance of our mineral fuel, we have been, and we still are, comparatively regardless of economy in its consumption. The time has now arrived when necessity will compel us to act differently, both in our manufactories and in our households."

I conclude this chapter with the following passage from the work of two eminent geologists, who wrote, however, when the question was not so urgent as at present :—

“The manufacturing industry of this island, colossal as is the fabric which it has raised, rests principally on no other base than our fortunate position with regard to the rocks of this series. Should our coal-mines ever be exhausted it would melt away at once, and it need not be said that the effect produced on private and domestic comfort would be equally fatal with the diminution of public wealth; we should lose many of the advantages of our high civilization, and much of our cultivated grounds must be again shaded with forests to afford fuel to a remnant of our present population. That there is a progressive tendency to approach this limit is certain; but ages may yet pass before it is felt very sensibly, and, when it does approach, the increasing difficulty and expense of working the mines of coal will operate, by successive and gradual checks against its consumption, through a long period, so that the transition may not be very violent: our manufacturers would first feel the shock; the excess of population supported by them would cease to be called into existence, as the demand for their labour ceased; the cultivation of poor lands would become less profitable, and their conversion into forests more so.”¹

¹ Conybeare and Phillips, *Outlines of Geology*, pp. 324-5.

COAL RESOURCES OF THE UNITED KINGDOM, 1904.

The recent Royal Commission reported the following figures :

TOTAL AVAILABLE COAL RESOURCES OF THE PROVED COAL-FIELDS OF THE UNITED KINGDOM.

Not exceeding 4000 feet in depth, and after deductions for loss in working due to faults, &c., and for barriers, pillars for the support of surface buildings, &c.

Estimated net available quantity remaining unworked.
(Millions of tons.)

	Total	In seams of a thickness of two feet and upwards.
South Wales and Monmouthshire . .	26,471	21,372
Somersetshire and part of Gloucestershire }	4,198	No details
Forest of Dean	259	121
North Stafford	4,368	4,177
South Stafford	1,415	1,282
Warwickshire	1,127	1,095
Leicestershire	1,825	1,695
Shropshire	321	269
North Wales	1,736	1,555
Cheshire	292	240
Lancashire	4,239	3,655
Yorkshire	19,138	14,659
Derby and Notts	7,361	5,017
Durham	5,271	4,374
Northumberland	5,510	4,694
Cumberland	1,528	1,365
Scotland	15,681	11,044
Ireland	174	No details
Total United Kingdom	100,914	80,986 ¹

¹ Including total estimates where no details are given.

A further quantity, exceeding 5,239 millions of tons, is estimated as available in proved coal-fields at depths exceeding 4,000 feet.

The following is given as the Resources of the Concealed and Unproved Coal-fields, at depths less than 4,000 feet, so far as they are capable of being estimated :—

	Coal Available (Millions of Tons)
Cheshire Basin	106
Chester, Wirral and Liverpool District	2,880
Vale of Eden and Solway Firth	800
Yorkshire and Notts	23,000
South of the N. Stafford Coal-field	1,742
Between the Coal-fields of S. Staffs., Coal- brookdale and the Forest of Wyre }	5,069
Between the Coal-fields of S. Staffs., War- wickshire and Leicestershire }	5,887
Total	39,484
Cumberland, beyond 5 miles and within 12 miles of high water mark }	855
Under St. Bride's and Carmarthen Bays	383
Total	40,722

CHAPTER III

GEOLOGICAL ASPECTS OF THE QUESTION

I CANNOT pretend to do more, as regards the geological aspects of this question, than to give some brief account of the way in which geologists argue concerning it. At the most I must only try to point out what is clear and easy, and what is yet involved in doubt.

In the first place, when we know the extent and thickness of a coal seam, we easily calculate its contents by weight. Most coals range in specific gravity from about 1.25 to 1.33, or are from one and a quarter to one and a third times as heavy as an equal bulk of water. A cubic yard of solid coal therefore weighs from 2,103 lbs. to 2,243 lbs. And since 2,240 lbs. make one ton, it is quite exact enough to say that *a cubic yard is a ton in weight*.

Supposing a seam, then, to be exactly a yard thick, an acre of it will contain 4,840 tons of coal,

and a square mile 3,097,600 tons. We may say in round numbers that *a coal seam gives a million tons of coal per foot thick per square mile.*

Our task is now reduced to that of defining the area and thickness of the coal seams of any district. The manner, however, in which the seams have been formed and disposed in the crust of the earth gives rise to several difficulties.

1. The seams are of very different thickness and quality, some workable and others unworkable; we are not certain how many we may count upon.

2. The area of the seams in a district is not uniform, some having been much more denuded or swept away by aqueous agency than others.

3. Coal seams are more or less broken up by faults and hitches, and a greater or less quantity of coal must be sacrificed to the necessities of mining.

4. Coal seams on one side often sink to unexplored depths, and we are uncertain how far we can follow them. There are reasons, too, for supposing that coal measures may exist where they have never yet been reached.

The first question, of the thickness of workable seams, will be more fitly discussed in the next chapter. The fact is sufficient here, that, under

the present prices of coal, seams of less than eighteen or twenty-four inches do not repay the cost of working.¹

We have next to consider the superficial extent of coal seams. It is obvious that, so far as seams lie one above the other co-extensively, we may lump them together in our estimate. Thus, in the Newcastle field, there are ten seams of more than two feet thickness, and in workable condition. Of these the High main and Low main coal seams are each six feet thick, and the intermediate Bensham seam is nearly three feet. Adding to these the seven other less valuable seams, we have a total thickness of coal of thirty-six feet. As the area of the field, according to Mr. Hull, is 460 square miles, we might be inclined to reckon the total contents according to the rule at

¹ The economical working of thin seams has made some progress in the last forty years, but Jevons' statement remains generally true. Dealing with the point in its Final Report, the recent Royal Commission state (p. 4, §§ 27, 28):

"Whether a particular seam is workable or not depends not so much upon its thickness as upon its quality, the nature of the roof and floor, its geographical position, the cost of working and the selling price.

Thin seams are also workable when they are found in conjunction with another seam, whether of coal, iron ore, fireclay or other mineral. . . ."

Several cases where seams of less than a foot in thickness were worked, under special conditions, were mentioned by witnesses before the Commission.

460 × 36 millions of tons, or 16,560 millions. But we should here commit a considerable error, because the seams are not co-extensive. The quantity assumed by Mr. Hull, "corrected for denudation," is only 8,548 millions of tons.

The origin of the difference is very easily explained, though overlooked by many early and some late estimators. It arises from the very large portions of the upper seams that have been swept away or denuded during geological ages. The coal measures consist of many alternated beds of sand, mud, coal, and ironstone, deposited during a long interval of time in estuaries, great swamps, fresh-water lakes, deltas, or flat shores, which gradually sank as the beds were added. As first deposited, the strata must have been nearly level, but they are seldom so now. They lie at every angle from the horizontal to the vertical. Nowhere have we such good opportunities as in our coal mines of observing the upheavals, the downfalls, the dislocations, contortions, and denudations which rocks have suffered. The Scotch coal-fields must, at one time, have formed a nearly continuous and level sheet, but are now broken up into many separate irregular basins, and the seams are sometimes, as in the Mid-Lothian mines, turned up quite vertically

on their edge. In the French fields the beds are sometimes folded in and out in a highly complicated and troublesome manner.

In general the coal measures have only been tilted up on one side in sloping plains, or bent into gentle curves and basin-like depressions. These movements could not take place without destroying the continuity of the strata; for though rocks seem to us solid and immovable, they are, in comparison with volcanic forces, but as thin and incoherent crusts. Accordingly, the beds are traversed in every direction by cracks, fissures, faults, where the whole mass of strata many thousand feet thick has been cloven through, one side comparatively to the other being thrown up. The great ninety fathom dyke, for instance, which crosses the Newcastle field, in a somewhat curved line to the north of the River Tyne, has caused the downthrow of the strata on the north side to the depth of 540 feet, and has had curious influences upon the progress of the English coal trade. On the whole, the Newcastle field is one of the least disturbed, and presents few great difficulties to the miner.

The Lancashire field is more troubled. The new map of the Geological Survey, prepared by

Mr. Hull, a complete copy of which may be seen in the Museum of Practical Geology, represents it as scored and broken by a number of cracks, small and great, interlacing in a very complex manner. In short, a sheet of coal measures, to use Dr. Buckland's expression, is like a sheet of ice broken into numerous irregular pieces, but soldered together again without any bit being wholly lost.

Now, when all these disturbances took place, the surface of the ground must have been affected as well as the underground strata. We might expect to find, on the south side of the ninety fathom dyke at Newcastle, a perpendicular rocky cliff of corresponding height. But no such thing is known on any of the coal-fields. The surface of our English coal-fields is either quite flat, or only swelling in one direction into round topped hills, showing no conformity to the underground disturbances. We cannot mistake the reason. While earthquakes and intrusions of lava were breaking up the strata, winds and rains and streams, or perhaps the tides of a shallow estuary, were wearing away all prominences, and carrying off great masses of rock. It has been shown, for instance, by Professor Ramsay, that the whole body of the coal measures between

the South Wales field and that of the Forest of Dean, has been swept away; and the missing portion, far larger than mountains in mass, is conjecturally restored in the plates of one of the earlier memoirs of the Geological Survey.

During this process the upper beds, of course, would be soonest carried off. And when the beds are thrown up on one side into an inclined plane, we find the seams of coal more and more cut away as they are nearer the surface. Thus the coal measures, as they usually appear to us, successively crop up to the surface, like the layers of a piece of wood that has been planed off obliquely to its grain.

Thus it happens that the High main seam of coal at Newcastle is quite near the surface, and of comparatively limited extent; while the lower seams crop up to the surface at successively greater distances from the centre of the field, and the lowest *crow* coals, not included in the true measures, appear far away.

It is obvious, therefore, that in estimating the contents of a coal-field as we find it, we ought to lay down on a map the line of out-crop of each seam, that line at which it is cut by the surface of the ground. Then we should measure separately the area of each seam, and multiply each

area by the thickness of the seam. On many of the maps of the Geological Survey the out-crop of the seams is beautifully shown in series of devious curves, sharply dislocated here and there by the faults. But I am not aware that any person has yet estimated the seams separately.¹ The subject has hardly required so much nicety as yet, and Mr. Hull arrives at a corresponding result by what he calls a "correction for denudation," or an allowance for the large part of the upper beds worn away in the Newcastle field. How he estimates this "correction" almost amounting to half, I do not know.

But the amount of coal ascertained by multiplying the area into the thickness of a seam must not be taken as the amount available. Some part of a seam is always broken up, burnt, or spoiled by the faults and dykes which traverse it. Another considerable part is always lost in mining. Up to the end of the eighteenth century it was not usual to extract more than four-tenths of the coal in a seam, when working at a greater depth than 100 fathoms; the rest was left in the form of thick pillars to keep the roof from falling in.

¹ In the preparation of estimates of resources for the Royal Commissions, some of the reporters, at least, have adopted such methods as those here named (*cf.* for example, the reports on Districts A, D and F for the Allerton Commission).

The free use of timber to support the roof, and the introduction of long-wall and panel working has allowed the extraction of nearly all the coal in favourable positions. Still, in unfavourable circumstances, the highest mining skill will probably be unable to get the whole coal; and besides this it is always necessary to leave thick barriers of coal around the limits of the property in order to shut out the water, or the foul air, of neighbouring works. A clause to this effect is always introduced into a mining lease, and, if not observed, the mine may easily become unworkable. If to these barriers and the wasted pillars of coal we add the small coal burnt at the pit mouth, or consumed in the ventilating furnaces and engines, we cannot estimate the coal available for commerce at more than two-thirds of that which the continuous seams would contain. Accordingly, Mr. Hull allows one-third for waste.¹

¹ The estimated deductions to be made were not separately reported for all districts to the recent Royal Commission. Of the total available coal at depths not exceeding 4,000 feet, reported at 100,915 millions of tons, 30,697 millions are included in estimates reported net. The remainder is arrived at, after making deductions amounting to 20,532 million tons, from an estimated total of 90,750 millions. The allowances thus amount to 22·6 per cent., a figure which would not be reduced were the deductions in all districts ascertained, if the information given in regard to the largest of the districts which reported net may be taken as a

The contents of a coal field may, then, be estimated with some certainty, provided that the boundaries of the seam on every side be known. This is the case in a perfect coal basin like that of the Forest of Dean. In the case of fields abutting on the sea, like those of Newcastle and Whitehaven, we have only the uncertainty concerning the distance to which coal can be worked under the sea. From one to three miles is the greatest distance we can conceive possible, except under a rise of price, which would constitute the scarcity of coal to be apprehended.

It is only when coal seams sink down beyond our knowledge on one side, as in the Yorkshire field, that we are in thorough uncertainty as to the quantity of available coal. The question here becomes a two-fold one. Firstly, *how far may the coal measures be supposed to dip and extend under more modern formations?* Secondly, *how far can we follow them with profit, considering the growing costs and difficulty of deep mining?*

Leaving the second question for discussion in the next chapter, there is but little that can be said concerning the first.

guide. Adding an allowance for colliery consumption, which may be taken at 5 per cent, as a rough average, if not more, the deductions now made amount to $27\frac{1}{2}$ per cent.

If the science of geology had no other claims upon our attention, it would repay all the labour spent upon it, many times over, by showing where coal may reasonably be looked for. By fixing the geological date of each rock, it points out in what interval the coal measures must appear, if they appear at all. One-third of the whole kingdom, it is said, is excluded from the search by being formed of rocks older than the coal-bearing age. On the other hand, there are large areas of country under which coal may reasonably be expected to occur, although there are no signs of it at the surface: and geology may enable us even to fathom the thickness of overlying rocks and tell with some certainty the depth at which coal will probably occur, if at all.¹

Mr. Hull includes in his estimate 932 square miles of such country.² Of these, 225 square

¹ E. Hull, *British Association*, 1854, *Report*, p. 87.

² The Argyll Commission included about 2,150 square miles in the area of concealed coal-fields covered by their estimate of resources. The Geological Committee of the later Commission reported on unproved coal-fields extending over an area of about 3,400 square miles. The amounts of coal included in the estimates of the two Commissions for concealed or unproved coal-fields are stated above (p. 24).

The most extensive, by far, of the concealed coal-fields dealt with by the Geological Committee of the later Commission is the eastern extension of the coal-field extending from South Yorkshire

miles occur at the south-east corner of the Durham field, where the coal measures dip under the Magnesian Limestone and the New Red Sandstone. Another 400 square miles occur similarly on the eastward dip of the great Yorkshire and Derbyshire field. Wirral and other parts of the Cheshire New Red Sandstone are probably underlain by bands or sheets of coal measures, connecting the Flintshire and Denbighshire fields with the great Lancashire field. The North and South Stafford, Warwick, Coalbrookdale, and Forest of Wyre fields are more or less completely connected.¹ On the other sides the fields are definitely terminated by the appearance of the carboniferous or mountain limestone, that great basement rock which in nearly every part of the kingdom bears the coal measures.

As these sunken coal-fields are continuous with those now worked, there can be little or no doubt as to their existence. But while they can hardly contain better seams than those already

into Derbyshire and Nottinghamshire. This extension was considered by the Commission of 1866-71 to be among the available resources of the kingdom, so far as an area of about 900 square miles is concerned. The later Commission considered that an area of 2,550 square miles might be included, while Professor Kendall, who reported on this concealed coal-field, estimated the total area at 3,885 square miles.

¹ Cf. Table on p. 39.

known, the seams may very possibly thin out if followed far. And in many cases the overlying Permian and New Red Sandstone rocks may contain so much water, and swell to such a thickness, as to be quite impenetrable.

A band of coal seams connecting the Durham and Yorkshire fields is of a more conjectural character. In the country between these two fields the Magnesian Limestone, which is above the coal, lies directly upon the millstone grit and carboniferous limestone below the coal. As there is no sign of coal measures at the junction, coal cannot now exist at the point. If it ever existed in the interval, it must have been swept away before the era of the Permian or Magnesian Limestone.

Noticing, then, the rectangular direction in which the northerly edge of the Yorkshire coal, and the southerly edge of the Durham coal run under Permian beds, it seems to be wholly a matter of uncertainty how far the denudation, or absence of the coal measures, may extend.

Another possible position of coal measures is beneath the cretaceous and Wealden beds of Wilts, Berks, Surrey, and Kent. In 1855, Mr. Godwin-Austen published a remarkable argument, showing that a range of rocks, an under-

ground ridge of mountains, as it were, probably stretched from the Mendip Hills to the Ardennes in Belgium; and "we have strong *a priori* reasons for supposing that the course of a band of coal measures coincides with, and may some day be reached along, the line of the valley of the Thames, whilst some of the deeper-seated coal, as well as certain overlying and limited basins, may occur along and beneath some of the longitudinal folds of the Wealden denudation." His deductions were partially verified immediately after publication by the actual discovery of old rocks in the boring of wells at Kentish Town and Harwich.¹ But Mr. Whitaker, to whose able memoir² and kind aid I am indebted, remarks on the uncertainty of such deductions concerning coal. "It must not be supposed that because there is almost a certainty of there being a ridge of old rocks at some depth below the surface along part of the valley of the Thames, and a likelihood of some of those old rocks belonging to the *coal measures*, therefore coal will be

¹ The correctness of the age assigned to the Harwich rock was later subjected to question, and it now seems safer to regard these old rocks as pre-carboniferous. (Cf. *Final Report of Commission on Coal Supplies, Minutes of Evidence*, p. 34—Prof. Boyd Dawkins p. 42—Mr. W. Whitaker.)

² *The Geology of Parts of Middlesex, Hertfordshire, &c.*, by William Whitaker, B.A., F.G.S., 1864, p. 107. (Geological Survey.

found at a workable depth in parts of the London District; for the alternations of sandstone, shale, &c., that so generally contain workable beds of coal, and are therefore known as the 'coal measures,' are sometimes almost without that mineral."

In short, all that is shown is a *bare possibility of finding coal*. But as it is uncertain whether the coal measures are there at all—whether, if there, they contain good coal—and if so, whether they are within workable depth and circumstances, it must still be held very unlikely that coal will ever be got in this tract.¹

And on the principle that "a bird in the hand is worth two in the bush," we should avoid

¹ The coal measures were actually reached by a boring at Dover in 1890 at a depth of 1,100 feet below Ordnance Datum. Further boring at Shakespeare Cliff has penetrated 1,173 feet of the coal measures, with 13 seams of coal, and a total thickness of 18 feet of coal in seams of not less than 2 feet in thickness. At Ropersole, eight miles from Dover, the coal measures were struck at 1,181 feet, and have been penetrated to a thickness of 548 feet, the coal seams being all quite thin. At Ellinge, five miles north-west from Dover, a boring in 1901-2 reached the coal measures at a depth of 1,286 feet. These were penetrated through a thickness of 129 feet, but contain no seams of coal (*cf.* Evidence of Prof. Boyd Dawkins and Mr. Whitaker before the Commission on Coal Supplies *Final Report*, part x, pp. 26-46).

The Geological Committee of the Commission considered that, in reference to the contents of the field: "the limits are so doubtful, as to render an estimate impossible."

putting too much reliance on possible coal-fields. Their existence is doubtful—they cannot well contain better coal than that we now enjoy, and may contain much worse, and they are very probably at depths, and in conditions, where they are commercially out of the question, as regards competition with foreign coals. There is plenty of coal known to exist out of our reach without resorting to coal that may or may not exist, but is in any case perhaps out of reach.

CHAPTER IV

OF THE COST OF COAL MINING

THE difficulty and cost of winning and working coal-mines form an aspect of the question that obviously contains the solution of the whole.

In a free industrial system, such as we are developing and assisting to spread, everything is a question of cost. We have heard of moral and physical impossibilities, but we ought to be aware that there are also *commercial impossibilities*. We must ask, in undertaking a work, not only whether it can be done, or is physically possible, but also whether it will pay to do it—whether it is *commercially possible*. The works of the two Brunels were, in a mechanical point of view, at least as successful and wonderful as those of the Stephensons; but, commercially speaking, they were disastrous failures, which no one would have undertaken had the consequences been foreseen. Commerce and industry cannot

be carried on but by gain—by a return exceeding the outlay.

Now, in coal-mining, we must discriminate the physical and commercial possibilities. The second presupposes the first, but does not follow from it. The question is a twofold one :—Firstly, is it physically possible to drive our coal-mines to the depth of 4,000, 5,000, or 6,000 feet? and, secondly, is it commercially possible when in other parts of the world coal is yet being worked in the light of day? The very existence of Britain, as a great nation, is bound up in these questions.

Now I apprehend that there is not the least danger of our reaching any fixed limit of deep mining, where physical impossibility begins. In mines already 2,000 or 2,500 feet deep, there is no special difficulty felt in going deeper. But we must consider the matter a little, because the *Quarterly Review* has confidently asserted that 2,500 feet is the limit,¹ and Mr. Hull, after an express inquiry into the matter, thinks that 4,000 feet may be taken as the limit.² It has often

¹ Vol. cx., p. 329.

² *Coal-fields*, etc., 2nd ed., p. 219. About 1845 the greatest depth reached was 1,794 feet at Monkwearmouth (R. C. Taylor, *Statistics of Coal*). In 1859 a depth of 2,151 feet was reached at Dukinfield. The 1871 Commission had evidence as to three

been suggested that the increase of temperature of the earth's crust as we descend into it will prove an insuperable obstacle, and Mr. Hull and others have been inclined to hold that beyond a depth of 4,000 or 5,000 feet the temperature will entirely prevent further sinking.

The increase of temperature varies in different mines from one degree in 35 to one degree in 88 feet. The increase in the deep Monkwearmouth Pit was one degree for 60 feet; but the observations of Mr. Astley in the sinking of the Dukinfield Deep Pit showed an average increase of one degree in 83 feet, nearly the lowest rate known.¹ If with Mr. Hull we take one degree in 70 feet as a safe average rate of increase, we easily form the following table, starting from the depth of 50 feet from the surface, at which depth in this country an uniform temperature of about 50° Fahr. is found to exist.

pits of over 2,000 feet in depth, the deepest at that time being the Rose Bridge Colliery, Wigan, 2,376 feet. The recent Commission received evidence as to several pits of about 2,500 feet in depth, and a few about 3,000 feet. The deepest reported was that at Pendleton, 3,483 feet deep. All the coal won from this pit in 1902 was from depths exceeding 3,000 feet (cf. *First Report*, vol. ii, p. 16). Evidence relating to a pit near Mons, Belgium, 3,773 feet deep, was received (cf. *Final Report*, part x, p. 354).

¹ The following summary of more recent observations shows the temperatures observed in some of the deeper coal pits (cf.

Depth in feet	Increase of temperature of rock	Actual temperature of rock
50	0°	50°
1,000	14°	64°
2,000	28°	78°
3,000	42°	92°
4,000	56°	106°
5,000	71°	121°

The air in mines, independently of the rock, is also warmer than at the surface, owing to its

First Report of Commission on Coal Supplies, especially Professor Dixon's evidence, pp. 114-6).

Date	Place	Depth in feet from surface	Temperature of rock	Average feet per degree
1880	Dukinfield Colliery	2,700	86°5'	68'4
1881	Ashton Moss Colliery	2,790	85°3'	72'8
1902	Abram Colliery, Wigan	2,700	96°	58'7
"	Agecroft Colliery, Manchester	2,940	92°5'	68'2
"	Rams Mine, Pendleton	3,483	100°5'	67'9
"	Sneyd Collieries, Burslem	2,625	87°5'	68'7
"	Harris Navigation, S. Wales	2,295	77°5'	76
"	Dowlais Cardiff Colliery	2,590	74°	106
"	" " " "	2,600	77°	94'5
"	Niddrie Collieries, Portobello	2,488	73°6'	103'3
"	" " " "	2,623	74°	107'2
1904	Mons, Belgium	3,773	116°6'	55'9

In a deep boring at Schladebach, temperatures were observed to a depth of 5,630 feet in 1889. The average rate of increase was one degree in 67'1 feet. Temperatures for 4,000 feet and 5,000 feet were 108°8' and 124°2'.

The average temperature gradient accepted by the Argyll Commission was one degree in 60 feet, which has been adopted by

greater density ; for just as in ascending a mountain the barometer falls and the air grows rare and cold, so in descending a mine the barometer rises and the air grows warmer. The barometer, roughly speaking, varies about an inch for every 1,000 feet of elevation, and the temperature about one degree for every 300 feet. On these data the following table is roughly calculated :—

Depth in feet	Height of Barometer	Increase of temperature of air	Actual temperature of air
0	30°0	0°	50°
1,000	31°0	3°	53°
2,000	32°0	7°	57°
3,000	33°0	10°	60°
4,000	34°0	13°	63°
5,000	35°0	17°	67°

If air, then, of the temperature of 50° at the surface descend 5,000 feet, it will acquire the temperature of 67°. The rocks at that depth will have the temperature of 121°, and will therefore warm the air as it circulates through the mine

Mr. Hull since the date of that Commission's report. The Allerton Commission states that one degree in rather less than 64 feet is indicated. The local geological conditions cause considerable variations from the average, and the rate at which the temperature increases is not uniform at all depths. The temperature in the Rams mine increased, at the greater depths, at about one degree in 66½ feet, which would give 108·3° at 4,000 feet. The figures of the table in the text may therefore be retained as the general basis of the argument.

up to their own temperature. [The less active the circulation of air maintained in the mine the more nearly will the temperature of the air approach that of the neighbouring rocks.] The temperature of the air may be reduced by plentiful ventilation,¹ or by letting out in the mine air compressed and cooled at the surface, as is done in the new coal-cutting machines. Now, as men can work at temperatures exceeding 100°, we are not likely to encounter the physical limit of sinking on this account.

But the cost of sinking and working deep pits is quite another matter. The growing temperature will enervate, if it does not stop the labourers. Thus it is stated² that in one Cornish mine men

¹ The temperature of the air in the working places in the Rams mine was but 93·5° where the rock had a temperature of 100·5°. In the deep Belgian colliery, the air temperature was 103°, or 13·6° less than that of the rock. The air current had a velocity of 6 to 9 feet per second in this case. The maintenance of an air temperature 6° or 7° below that of the strata is recognized as quite feasible.

² *Report of Royal Commission on Mines, 1864.*

The effect of high temperatures on the efficiency of workmen depends largely on the amount of moisture present in the air. Deep pits are generally dry as compared with pits of moderate depth. The enervating effect of the heat is thus less than might otherwise be expected, since dry heat is less destructive of working energy than moist heat. It is stated that the miners work a full nine-hour shift in the deep Belgian pit.

An inquiry into the case referred to in the text was made for the Argyll Commission by Dr. J. Burdon Sanderson. He reported that "no man remained for more than fifteen minutes in the heat at one time, and not always so long. . . . Each miner, after taking

work in an atmosphere varying from 110° to 120° Fahr. But then they work only for twenty minutes at a time, with nearly naked bodies, and cold water frequently thrown over them. They sometimes lose eight or ten pounds in weight during a day's work. Much increased ventilation will be a matter of expense and difficulty; the hardening¹ of the coal and rocks will render hewing more costly; creeps and subsidences of the strata will be unavoidable, and will crush a large portion of the coal or render it inaccessible; while explosions, fires, floods, and the hundred unforeseen accidents and disappointments to which mining is always subject, will lie as a burden on the whole enterprise, a risk which no assurance company will venture upon. In addition to these special difficulties, the whole capital and current expenditure of the mine naturally grows in a higher proportion than the his turn in the heat, retreated into the comparatively cold air behind, where the temperature was about 81°."

¹ On this point the evidence before the recent Coal Commission points to a conclusion differing somewhat from that expressed in the text. The Report thus summarizes the information received:—

"The increase of pressure with depth has some advantages as well as disadvantages; it may increase the percentage of small coal, and the cost of maintaining the roadways and of timbering, but it assists the working of the coal" (*Final Report*, § 19). Thus, though the particular point of the hardening of the coal with depth is not supported, the general argument as to increase of cost is fully confirmed.

depth. The sinking of the shaft becomes a long and costly matter ; both the capital thus sunk has to be redeemed and interest upon it paid. The engine powers for raising water, coals, miners, etc., increase, and, beyond all, the careful ventilation and management of the mine render a large staff of mechanics, viewers, and attendants indispensable.

Much may be done by working larger areas from the same shaft ; by forming consolidated companies for economical drainage ; by perfecting machinery, and organizing labour to contend with the growing cost. But increased areas and distances of working, though comparatively diminishing the capital expense of the shafts and works above ground, will increase the current expenses of drainage, ventilation, and general maintenance.

A full analysis of the detailed accounts of a number of collieries of various depths would throw great light on this question, and might go far to solve the question of England's future career. But private commercial accounts are shrouded in such impenetrable closeness, that no individual inquirers can hope to gain the use of them. Even the several Parliamentary Committees, in their prolonged inquiries into the coal trade in and after 1830, were continually

frustrated by Mr. Buddle and other mining engineers, who declined to communicate information known to them professionally and confidentially. The investigation of such a subject might perhaps be best undertaken by a Committee of the British Association or some other learned Society.

An account of the South Hetton Colliery establishment, a well-arranged mine, throws light on this subject. It is published in a little work of the *Traveller's Library*,¹ remarkable for the amount of information it contains on the subject of coal.

Of 529 men employed in or about the colliery, 140 only are hewers of coal, representing the productive power of the establishment. We may divide the staff as follows:—

Hewers of coal	140
Putters, screeners, &c.	227
Employed in administration and maintenance of mine	123
Boys, variously employed	39

The “putters,” “screeners,” and others, to the number of 227, are occupied in pushing the coal along the tramways from the hewer to the shaft; in raising it to the surface; screening it, and removing the stones; and, finally, loading it into the railway waggon or ship's hold. They

¹ *Our Coal and Our Coal-pits*. The Traveller's Library, vol. 23. London: 1856.

represent, as it were, the trading part of the community, while the administration represents the government ; consisting of a manager, viewers, engineers, clerks, and a surgeon, with a great number of joiners, sawyers, enginewrights, smiths, masons, carters, waggon-wrights, and common labourers, as well as ventilators, shifters, foremen, and others of responsible duties underground ; all occupied in keeping the mine, the ventilation, machinery, engines, and the works generally in repair.¹

¹ Similar facts for a recent date are represented in the following return of mine workers in all the anthracite collieries in the State of Pennsylvania during 1901.

Inside foremen, or mine bosses	539
Fire bosses	830
Miners	37,804
Miners' labourers	26,268
Drivers and runners	10,894
Door boys and helpers	3,148
All other employees	18,951
Total inside	<u>98,434</u>
Superintendents, book-keepers, and clerks	804
Outside foremen	379
Blacksmiths and carpenters	2,331
Engineers and firemen	4,615
Slate pickers	19,564
All other employees	21,524
Total outside	<u>49,217</u>
Total inside and outside	<u>147,651</u>

As many as 108 different classes of labour are mentioned as employed by one mining company (cf. *Bulletin of the U.S. Department of Labour*, May, 1903, pp. 455 and 478).

Now, if coal were quarried at the surface, and wheeled straight away, each hewer would scarcely require more than one subsidiary labourer. In a deep mine we find that nearly three subsidiary labourers are required, so that four only accomplish what two would do at the surface, to say nothing of the timber and other materials consumed, and the great capital sunk in the shaft, engines, and works of the deep mine.

As mines become deeper and more extended, the system of management necessary to facilitate the working and diminish the risk of accidents, must become more and more complicated. The work is not of a nature to be made self-acting, and capable of execution by machinery. Even in the West Ardsley Colliery, belonging to the patentees of the coal-cutting machine, who naturally carry out its use to the utmost possible extent, this machine is found¹ to diminish the

¹ Prof. H. D. Rogers, in *Good Words*, April, 1864, p. 338.

The improvement of coal-cutting machines has greatly increased the saving of labour which they effect over that attained when Jevons wrote. Mr. W. E. Garforth, of Normanton, stated in evidence before the Allerton Commission that the use of machines enabled 280 men to get as much coal as would need 384 miners by hand-work in the Silkstone seam (4 feet thick, depth 960 feet); and that 233 men got 900 tons daily in the Diamond seam (3½ feet thick, depth 1,500 feet), an amount which would need 400 men at hand-work. Of the numbers mentioned, 60 per cent. were colliers and fillers, the remainder being engaged in other work directly in-

staff only *ten per cent.* The labour saved is only that of twenty-seven hewers, while other branches of the staff must be rather increased than diminished. So different, too, are the conditions of coal-mining, that in many collieries the use of coal-cutting machines is perhaps impracticable.

The deeper a mine the more fiery it in general becomes. Carburetted gas, distilled from the coal in the course of geological ages, lies pent up in the fissures at these profound depths, and is ever liable to blow off and endanger the lives of hundreds of persons. It was supposed that George Stephenson and Sir H. Davy had discovered a true safety lamp. But, in truth, this very ingenious invention is like the compass that Sir Thomas More describes in his *Utopia* as given to a distant people. It gave them such confidence in navigation that they were "farther from care than danger."

No lamp has been made, or, perhaps, can be made, that will prevent accidents when a feeder connection with the winning of the coal. Haulage and road repairs are not covered by any of the numbers (*First Report*, vol. ii. p. 110).

The advantage of coal-cutting machines has been found in Great Britain to be greatest in working thin seams. In adding to the safety of the miners, and to the proportion of large coal secured, further advantage from their use is found.

of gas is tapped, or a careless miner opens his lamp, or a drop of water cracks a heated glass, or a boy stumbles and breaks his lamp. The miner's lamp, in fact, is never a safety lamp, except when carefully used in a perfectly ventilated mine. Long experience shows that perfect ventilation is the only sure safeguard against explosion. But it is no easy matter to ventilate near a hundred miles of levels, inclines, stalls, and goaves in a fiery mine.

The amount of drainage required in deepening our mines is another point of the greatest importance. The coal-measures themselves, containing many beds of clay and shale, are dry enough in general, except where interrupted by faults which allow the water to penetrate. Thus, the lower parts of deep mines will in general be dry enough, but the passage through the overlying Permian and New Red Sandstone beds may often be extremely costly, or almost impossible.

“In all the sinkings through the Magnesian Limestone, feeders of water, more or less considerable, are met with at a certain distance from the surface, derived not so much by percolation through the mass of the rock—for this can obtain to a small extent only—but col-

lected in and coming off the numerous gullets and fissures which everywhere intersect and divide the mass of strata. If the shaft be not drained by pumping or otherwise, the water from these feeders rises to a point which remains, save in exceptional cases, constant. . . . Immediately underlying the limestone is a bed of sandstone of very variable thickness, which, when exposed to the action of the atmosphere, disintegrates rapidly, and has hence acquired its local name of 'friable yellow sandstone.' It is in sinking through this bed of rapidly decomposing sandstone that such great engineering difficulties have been encountered, owing to the enormous quantity of water which in some cases is met with, more especially if the bed be thick and much below the level of saturation."

"A very full account of the sinking of the Murton Winning is given by Mr. Potter.¹ . . . Nearly 10,000 gallons of water per minute were pumped out of this bed by engines exceeding in the aggregate 1,500 horse-power. The circumstances which favour the remarkable accumulation of water in the limestone, and the

¹ *Trans. of the North of England Institute of Mining Engineers*, vol. v.

rapidity with which it is drained off into pits sunk through it, are due to several causes, some of which are peculiar to this formation, and perhaps to this district. They are:—

“1. The arrangement of the beds of stratification.

“2. The contour of the country.

“3. The permeability of this formation to water.”¹

In the sinking of Pemberton's Pit at Monkwearmouth, a stratum of freestone sand at the base of the Magnesian Limestone poured 3,000 gallons of water per minute into the sinking. And when this flood of water had been overcome by an engine of 180 or 200 horse-power, and had been “tubbed back,” a new “feeder” was met at the depth of 1,000 feet, requiring fresh pumps, and an additional outlay of money.² The shaft was commenced in May, 1826; it was continued for eight and a half years before the first workable coal was reached; and it was only in April, 1846, twenty years afterwards, that the enterprise was proved successful by the winning of the “Hutton Seam.” The South Hetton and Great

¹ *Brit. Assoc. Report*, 1863, pp. 726, 727.

² *Our Coal and our Coal Pits*, p. 113.

Hetton pits were also very costly, difficult winnings, on account of the quicksands and irruptions of water. And the winning of a pit at Haswell, in the county of Durham, through the Magnesian Limestone and the underlying sand, was found impracticable for a like reason, in spite of engines capable of raising 26,700 tons of water per diem.¹

In the continuous working of pits, even where "tubbing" is used to keep the water out of the shaft as much as possible, the quantity of water is not unusually seven or eight times as great as that of the coal raised.² At the Friar's Goose Colliery, near Gateshead, 6,000 tons of water are raised from the mine every day, about twenty

¹ *Our Coal and our Coal Pits*, p. 115.

² Sir James Joicey stated in evidence before the recent Commission that, in the pits with which he was connected, the coal raised was about 5,000,000 tons yearly, and 15,000,000 tons of water were pumped (*Final Report*, part x, p. 146). Mr. H. Mungall, speaking of some Lothian collieries, stated that as much as 40 per cent. of the total output of coal was consumed in pumping. The percentage was reduced to 12 by increasing the output. In the Fifeshire Coal Company's colliery, 2,250,000 tons of coal per annum was raised, and ten tons of water pumped for each ton of coal raised (*loc. cit.*, pp. 212, 213, 216). Mr. J. Gemmell stated that in Scotland "occasionally you will find that the quantity of water pumped is 20 to 30 times as much as the coal drawn" (*First Report*, vol. ii. p. 150). In South Staffordshire, it was stated that, under the general drainage scheme, 26 or 27 tons of water have been pumped for every ton of coal won for the last twenty years (*Final Report*, part x, p. 219).

this limit be affected by probable changes in the conditions of coal-mining? A considerable advance in the price of coal will, of course, enable thinner seams to be worked with profit. Thus, to some extent, the rise of prices will be slackened. The higher the price rises, the more thoroughly will the coal-measures be worked, and the more coal becomes workable. As, however, the high price of coal constitutes the evil of exhaustion, the dreaded results are only somewhat mitigated, not prevented. And it would be wholly erroneous to suppose that when once the thicker seams of a coal district have been worked out, we can readily, at a future time, work out the thinner seams, when the increased price of coal warrants it. For it must be observed, that a very large part of the cost of mining consists in the cost of draining, ventilation, and maintenance of the shaft, and works at the bank, which we may call the general mining expenses. Now, when these expenses are undertaken for the purpose of working a thick and valuable seam, it is

Great Britain came from seams 3 feet and under in thickness. In East Lancashire, of a total of about 10,000,000 tons, about 3,000,000 tons were from seams not exceeding 3 feet in thickness, about 860,000 tons being from seams of 2 feet and less, and 290,000 tons from seams not over 18 inches thick. Seams less than a foot thick contributed only 15,000 tons (*First Report*, vol. ii, pp. 25-6).

often possible to work thin seams of less than 24 inches without any considerable increase in the general expenses. In short, the thick seam pays the general expenses of the mine as well as its own cost of hewing, while it is sufficient if the thin seam leaves a small profit on the expenses of hewing only. But the price of coal must rise in a very extreme degree, that an unworked thin seam should, at a future time, pay the general costs of drainage, ventilation, and maintenance, as well as the cost of hewing.

The same is true of immense masses of coal left underground during the former working of mines, as small or crushed coal, as pillars and barriers, or as outlying portions rendered difficult to mine by faults, or other mining troubles. If such portions of coal could not pay for removal when the mine was in full working efficiency, they cannot pay the whole costs of restoring and maintaining the mine in a workable condition, not at least until the price of coal has risen manifold.

All, then, that we can hope from thin seams, or abandoned coal, *is a retardation of the rise of price after a considerable rise has already taken place.* This will hardly prevent the evils apprehended from exhaustion.

Nor will the use of the coal-cutting machine much affect this question. By reducing the cost of hewing and the waste of coal in the "kirving," or cut made by the hewer, it will, undoubtedly, to some extent, allow thinner seams to be worked. At the same time, it will not affect the cost of removing large masses of profitless rock, which is essential in working thin seams, nor the general cost of the maintenance of the mine. If seams of 18 inches are now occasionally workable, the coal-cutting machine may reduce the limit a few inches ; but it is evident that seams of less than 12 inches could never be worked while the price of coal remained at all tolerable.¹

Coal-mining is a fair fight with difficulties, and just as the balance inclines between the difficulties and the powers we possess to overcome them, will the cost of coal and the prospects of this country oscillate. What we can do to cheapen extraction, indeed, is chiefly effected by turning the powers of coal against itself, by multiplying steam power to pump and wind, and

¹ It is for the purpose of supplying special local markets that most thin seams which are not worked in conjunction with other seams are exploited : they are workable "where there is little or no competition with thicker seams" (cf. *Final Report of Commission on Coal Supplies*, § 28). See also footnote p. 67, *ante*.

cut and draw the coal. But then the greater part of the work within the colliery is of a kind that cannot be executed by machinery, just as the building of houses, or the digging of holes, never has been, and scarcely can be, done wholly by machinery.

But be the difficulties what they may, we would have ingenuity and energy enough to overcome them, were the question one of a simple absolute amount of difficulty. But in reality we must consider our mines not by themselves, but in comparison with those of other countries. Our main branches of iron industry grew up at places like Wednesbury, in South Staffordshire, "where there being but little earth lying over the measure of coal, the workmen rid off the earth and dig the coal under their feet, and carry it out in wheelbarrows, there being no need for windlass, rope, or corf."¹

Our industry will certainly last and grow until our mines are commonly sunk 2,000 or 3,000, or even 4,000 feet deep. But when this time comes, the States of North America will still be working coal in the light of day, quarrying it in the banks of the Ohio, and running it

¹ Dr. Plot's *Natural History of Staffordshire*, quoted in the *History of Wednesbury*, p. 101.

coal such as would be the sign of incipient exhaustion. Had a considerable recent rise occurred, as I have heard asserted, it might be argued that no such evil results have followed as alarmists prophesy, and then the optimist would conclude, that, perhaps, after all, "dear coal" is not the fatal thing some suppose; this country may surmount that evil, it will be said, as it has surmounted worse evils.

From what reliable accounts I have been able to meet with, it is certain that there has been no such recent rise of price as could at all operate as a check upon our industry. Yet it is certain that coal has been cheaper in the past than it can again be, and that in the Great Northern market the growth of demand during the last century has been accompanied by a considerable but indefinite rise of price.

Where coal, indeed, used formerly to be had almost for the asking, it now bears a fair price. In the palmy day of the Staffordshire "Thick Coal" the price of the best large coal was 6s. per ton of 21 cwts., and 120 lbs. to the cwt., or 5s. 4d. per ton of 2,240 lbs. Coal was a drug about Birmingham, "so much so, as to cause the coalowners to give great extra weight There are many other veins at present not

thought worth getting, of from one to three yards thick ; inferior coals are sold at 3s. per ton, and from that upwards, in proportion to their quality ; the small coals, for working engines, are sold from 1s. to 1s. 6d. per ton ; the supply produced for the manufactures of the country would always be sufficient, in my opinion, without increasing the present price, as there are many new collieries now opening.”¹

The anticipations of the Ironmaster who gave this opinion before the Committee of 1800 have not proved true. The price of best coal in Staffordshire is now 9s. or more per ton,² and many writers concur in stating that the magnificent “Thick Coal” of South Staffordshire has been either used or wasted away. The wonderful “black country” already leans for its supplies of coal and ore upon neighbouring parts ;³ it seems to be already overshadowed by the approaching decline of prosperity. “He that liveth longest, let him fetch fire furthest,” was a proverb quoted by Dudley,⁴ two and a half centuries ago, with reference to the lamentable

¹ Evidence of Alex. Raby, *First Report on Coal Trade*, 1800, pp. 76, 77.

² The price of best Staffordshire house coals at the pit has been at or above 16s. per ton during 1903 and 1904.

³ See chap. xv.

⁴ *Metallum Martis*, p. 8.

waste of the Thick Coal, and now the force of the proverb is becoming apparent.

It is almost impossible to get such general and uniform statements of the price of coal as would warrant us in drawing comparisons over long periods of time. The variations in the quality, size, and distance of supply constantly affect the price, independently of duties and other obstacles. Almost all the quotations of prices available for comparisons over long periods refer to the London market, and are useless, because the prices there are not only affected by freights, but have been burdened, more or less, by duties and charges of a most complicated character.

The only series of prices I have been able to make out gives *the average price of the best large coal as put free on board at Newcastle*, and the other shipping places of the North. The first two prices (1771 and 1794) are derived from the Report of the Select Committee of the House of Commons on the Coal Trade in 1830 (p. 7). The prices of 1801—1851, are from a table of yearly prices published by Mr. Porter, in his *Progress of the Nation* (p. 277), and are the average shipping prices as returned to the Coal Exchange in London under Act of Parliament. The last price (1860) is an average computed for the General

Committee of the Coal Trade of Newcastle, and communicated to the Mining Record Office.¹

Year	Average Shipping Price of Newcastle Coal		per ton
	s.	d.	
1771	5	4	
1794	7	6	"
1801	10	4	"
1811	13	0	"
1821	12	8	"
1831	12	4	"
1841	10	6	"
1850	9	6	"
1860	9	0	"

This is probably as good and comparable a series of prices as could be got²; yet it is very difficult to draw inferences from it beyond the

¹ *Mineral Statistics for 1860*, p. xxiii.

² The Coal Commission of 1871 gathered a considerable amount of information bearing on the price of coal, but little of that printed in the Report of Committee E will serve to throw light on the problem here under consideration. The price of best coal at Newcastle about the year 1600 may be taken at about 10s. the chaldron, or 3s. 9d. per ton, taking the Newcastle chaldron at 53 cwt. This price for best coal is given as occurring in 1602 and also 1580-90. A quotation for 1655 is given at 11s. the chaldron at Newcastle, which may be represented by 4s. 2d. the ton. Quoting from the *Newcastle Chronicle*, the price for 1761 is given at 15s. the chaldron, equivalent to 5s. 8d. per ton.

Reference to R. C. Taylor's *Statistics of Coal* (pp. 261, 263) shows that Porter's prices include a charge of 10d. per chaldron, or about 4d. per ton, for weighing and measuring, in addition to the prices quoted for coal on board ship. This item, as well as the fact that these prices are "for Coals of the First Quality shipped for London, at the beginning of June in each year" (Porter, p. 277), must be taken into account in any attempt to obtain figures continuing the table to later dates, and also in comparing the prices for 1801-1850 with those for earlier dates. The difference between the prices for June and yearly average prices

contradiction of any recent considerable rise. The great rise of price up to 1811 was more or less due to the depreciation of gold and paper currency, or to the other causes, whatever they may have been, of the great general rise of prices.

may be judged from a statement of prices of coal at Newcastle in January and July of each year from 1819 to 1832 given in the *Appendix to the Report of the Committee of Secrecy on the Bank of England Charter*, 1833 (p. 92). The prices for July are about 10 per cent lower than those for January on the average. Then, again, a yearly average price, such as that for 1860, referring to all grades of coal, shipped to all destinations, is not directly comparable with prices of best coals shipped for London. In this connection, too, the point to which Jevons refers in the sequel has some importance. Owing to the combination of coalowners in the North which existed from 1771 to 1845, it is stated in Porter's account that the price of coal shipped to London was, at times, much above that at which coals for export to foreign countries were sold, a phenomenon paralleled in modern times, for example, in connection with prices of steel in the United States. If this be so, the series of prices which deals with coal sold for shipment to London would hardly afford a true index of the course of prices, even for the best grade of Newcastle coals. In view of the difficulties involved, an attempt to continue the table to later dates, rather than to trace the course of coal prices by using other tables, has not been made.

The following table of prices of coal in Newcastle and Sunderland is derived from figures contained in the evidence taken before the *Secret Committee on Commercial Distress* in 1848:—

Newcastle			Sunderland			Newcastle			Sunderland		
		s. d.		s. d.			s. d.		s. d.		s. d.
1784-90	per ton	7 6	—		1812-18	per ton	14 3	12 6			
1791-97	"	9 9	—		1819-25	"	11 8	12 0			
1798-1804	"	12 6	11 1		1826-32	"	10 5	11 1			
1805-11	"	15 2	12 2		1833-37	"	9 4	9 10			

Comparison of these figures with the average value of coal shipped from the two ports in the years 1833-37 suggests that a superior quality of coal is referred to. The inflation of prices during the later years of the Bank Restriction is shown more markedly here than in Porter's figures.

The subsequent fall is, of course, partly due to the restoration of our currency, and to the other debatable causes of a general fall of prices.¹

There are, however, at least two other circumstances not to be lost sight of in comparing early and late prices of coal.

Some indication of the approximate level of prices which a continuation of the table in the text might be expected to show may, probably, be obtained from the following series from the *Economist* of the prices of best Northumberland steam coals, f.o.b. Tyne, in selected years. The quotations are for July 1st except in the case of the first figure of the series, which is for January 1st. By using the middle of the year quotation, we approximate to the period of the year to which Porter's figures are stated to apply.

PRICES OF BEST NORTHUMBERLAND STEAM COAL, F.O.B. TYNE :—

	s. d.		s. d.
1871 (Jan.)	11 0	1896 (July)	8 6
1881 (July)	9 0	1901 (July)	13 0
1885 (July)	8 0	1904 (July)	10 3
1891 (July)	13 7	1905 (July)	9 3

These figures, for the later dates, include the export tax of 1s. per ton, imposed in 1901.

The price of household coals, rather than of steam coals, may perhaps be needed for carrying on the table in the text. In recent years the former price has generally been somewhat higher than the latter (*v.* Final Report of the Royal Commission on Coal Supplies, Part x, p. 135). This relation is, however, not shown in all years. The course of coal prices is further dealt with in a note at the end of the chapter (p. 90).

¹ In the First Edition of this work, a comparison was made between the change in the level of coal prices between 1794 and 1860 and the average change in the prices of forty of the chief materials of commerce. The price of coal rose in the proportion of 100 to 120. The fall of prices of commodities in general, as corrected later by the author, was in the proportion of 100 to 81. See Jevons' *Investigations in Currency and Finance*, pp. 144-5.

Firstly, there is the *limitation of the vend*, an arrangement which used to exist among the coal proprietors of the North, to limit the amount sold by any colliery, in order that each colliery might have a share of the trade proportional to its capabilities. This combination maintained itself at intervals for about two centuries, and was much complained of because it was supposed to raise the price of coal. It may have had some effect, especially upon those better kinds of coal of which the price is quoted.

Secondly, there is the practice of screening coals, whereby a considerable portion of the coal raised at the beginning of the century used to be separated out and burnt as waste, the whole cost of raising the coal being paid in the price of the large coal sold. Though coals are still generally screened, the "seconds," "nuts," and even the "dead small," or "slack," are usually sold for manufacturing purposes at prices proportional to the size of the coal. The total price thus returned is increased by more than is represented in the price of the large coal.

Both the limitation of the vend and the practice of screening would thus tend to raise the earlier quotations of price of large coal, as compared with late quotations, and thus disguise the real rise of

price due to the growing demand and the depth of the mines.¹

I take it, therefore, to be pretty certain that the cost of the best quality of Newcastle coal has been considerably more than doubled within a century by the growing depth of the collieries. It is not to be said that trade is much affected by the price of the very best coals, which are chiefly valued for household purposes. But from the price of such coal we learn what we should have to pay were all coals drawn from the depths of 1,000 or 2,000 feet or more. The mines of South Wales, Scotland, and Yorkshire are yet shallow (1865), and the coal cheap enough. The cost of the coal, especially, which supports the great and rising iron trade in South Wales and Scotland, is only 4s. or 5s. per ton (1865).

The following are some returns of the price of coal published by Mr. Hunt in the *Mineral Statistics* for 1860:—

	Description of Coal	Price per Ton	
		s.	d.
Newcastle	House Coal	9	0
	Steam	8	0
	Gas, Coking, and Manufacturing	5	6

¹ The practice of preparing the coal for market by screening, separating several different sizes in this way, has been carried out more thoroughly in recent years. The smaller sizes have been found quite capable of giving satisfactory results in use, when suitable appliances are provided, and thus the point made by Jevons has added emphasis at the present time.

Description of Coal		Price per Ton	
		s.	d.
Derbyshire	Best Coal	9	0
	Common	6	6
	Cost of Getting	5s. to 5	6
North Staffordshire	Best	9	2
	Common	6	0
	Cost of Getting	2s. 6d. to 4	6
Lancashire	Best Coal	6	3
	Lately	5	6
South Wales and Mon- mouthshire	Large Coal	6	6
	Small	4	6
Scotland	Average	4	0
	Cost of Getting	2	8

The average cost of getting coal throughout the country was stated to be 4s. 10d. per ton, not including profits, rent, and other charges.

In the very various prices of coal from the several collieries of the Newcastle district, we have evidence of the rise of price due to the depth of mines. Shipping prices of coal are given in full detail in the Report of the Committee of 1838 (p. 240); and taking the coals classed as Newcastle Wallsend only, we find the price varying from 6s. 6d. to 11s. 6d., the nuts and small coal ranging down to 3s. 9d. It is obvious that *the difference of five shillings per ton in Wallsend coal must either be absorbed by the expenses of deep mining, or else it must make the fortune of the proprietors or workers of the mines.* That in some cases prodigious profits are

made, as in the case of the original Wallsend mine, is well known. But this cannot usually be the case, otherwise the wide areas of land yet known to contain untouched seams of coal of the finest qualities, would at once be broken up by speculators, who are never wanting. *That deep mines are so deliberately opened is a sufficient proof that the highest prices obtained are, taking all mining risks and charges into account, only an average equivalent for the capital invested.* These deep pits can only be undertaken at present in search of coal of the finest quality. The Monkwearmouth Pit was sunk to win the Hutton seam, which yields coal of the highest possible character. The Dukinfield Deep Pit was undertaken to follow the celebrated Lancashire "Black Mine," a four feet seam of the finest coal, selling for 10s. per ton at the pit's mouth, the small coal returning 5s. 6d. per ton.

The high prices, which are necessary in order to tempt speculators to undertake deep mining, afford a rough but sure indication of the effect of depth upon the cost of coal. When the general depth of coal workings has increased to 2,000 feet, little or no coal will be sold for less than 10s. per ton, and the choice large coal will have risen to a much higher price. Our iron and

general manufacturing industries will have to contend with a nearly double cost of fuel. And when, with the growth of our trade and the course of time, our mines inevitably reach a depth of 3,000 or 4,000 feet, the increasing cost of fuel will be an incalculable obstacle to our further progress.

NOTE ON THE COURSE OF COAL PRICES

In order to trace the history of coal prices in an effective manner, it would be necessary to obtain quotations of the prices of coals of different characters, as sold at definite places, for the period whose history was desired. The general relation of the price of coal to that of other commodities can, however, be shown sufficiently well by using the average export value of coal for the entire United Kingdom, which is recorded in the *Report on Wholesale and Retail Prices* prepared by the Board of Trade in 1903. In addition to showing the average export value of coal, the following table also records that for coal exported from Cardiff. Inasmuch as South Wales has taken an increasing share in the export trade, the comparison of the two series of prices will afford some clue to the degree in which the general average has been raised by the inclusion

of a larger proportion of coal of a more valuable kind. The comparison of the movement of the price of coal with an index number of general price-movement introduces a point included in Jevons' First Edition, but omitted in the Second, a point which has been elaborated by the Right Hon. Leonard Courtney in his presidential address to the Royal Statistical Society in 1897.

Years	Average Declared Value per Ton Exported				Sauerbeck's Index Number
	From Cardiff		From United Kingdom		
	Actual Value	Proportionate Number	Actual Value	Proportionate Number	
1833-4	s. d. 7 9½	68·5	s. d. 7 2	73·3	90·5
1835-9	8 4½	74·4	7 3	73·9	98·0
1840-4	9 5½	84·0	7 3	73·9	92·2
1845-9	9 9½	86·9	7 6½	77·1	84·6
1850-4	9 8½	86·2	7 11½	81·5	85·4
1855-9	10 3	90·1	9 3½	95·0	98·4
1860-4	9 11½	88·3	9 0	91·8	101·2
1865-9	11 3	100	9 9½	100	100
1870-4	16 4½	146·2	14 5	147·2	103·6
1875-9	11 0	97·8	10 4½	106·1	91·0
1880-4	10 0½	89·1	9 0	91·9	83·0
1885-9	9 10½	87·6	8 9	89·2	70·2
1890-4	12 2	108·1	11 1	113·2	68·6
1895-9	10 5½	92·9	9 5½	96·6	63·4
1900-04	15 0*	133·3	13 0*	132·9	70·6

* These prices include export duty in and after 1901. Excluding the duty the percentage figures would be about 125.

Comparing the price of coal with prices in general, as represented by Mr. Sauerbeck's well-known index number, it will be seen that, while general prices stood only 2 per cent higher¹ in the later sixties than they had done thirty years before, the price of coal had risen by about 35 per cent.

The five-year period 1895-9 gives, within a very little, the lowest average price for coal of any consecutive five years since that which ended in 1889. Yet this shows a fall, as compared with thirty years earlier, of barely $3\frac{1}{2}$ per cent., while average prices have fallen $36\frac{1}{2}$ per cent. The relative movement of coal prices and general prices in the thirty years preceding, and in a like period following, the latter half of the sixties has therefore been similar, though the one is shown by a change in the price of coal while the general level of prices remained almost unaltered, the other by a price of coal almost unchanged while general prices fell largely.

The movement in coal prices has been more violent in the extent of its fluctuations than that of the average of wholesale commodities represented in Sauerbeck's index number. The latest quinquennium in the table, if a deduction for coal

¹ Jevons' index number makes them *lower* by between 8 and 9 per cent

tax be made, would show coal at about 25 per cent. higher prices than in 1865-9, while the average of prices was nearly 30 per cent. lower. As small coal, under six shillings per ton, is free from the export duty, the deduction to be made for duty is somewhat less than one shilling, the rate per ton of the duty. It is noteworthy that, comparing the period 1835-9 with 1865-9, and again comparing the latter period with 1900-04, the proportionate changes of price have been, alike for Cardiff coal and for coal exported from all ports, from 74 to 100 in the first period, and from 100 to about 133 in the second, though the detail of the course of prices in the intervals has not been precisely alike for the two series of quotations. A table found in the report of the Commission of 1871 affords a somewhat remarkable comparison with the above figures. It shows the f.o.b. values at Cardiff of large and small house coal, and large and small steam coal in each of the years 1858 to 1868 inclusive. The averages for the eleven years are as follows (Report of Committee E, Appendix, p. 211):—

House Coal, Large . .	$\begin{smallmatrix} s. & d. \\ 8 & 9\cdot6 \end{smallmatrix}$	Steam Coal, Large . .	$\begin{smallmatrix} s. & d. \\ 9 & 8\cdot2 \end{smallmatrix}$
Small . .	5 11\cdot5	Small . .	2 11\cdot7

The average for the same years of the figures

of the table from which that given on page 91 is abbreviated is, for Cardiff shipments, 10s. 5·6*d.* per ton. The note to the quotations in the Commission's report states that very prime qualities of steam coals fetched 6*d.* more than the prices given at Cardiff. The fact that the average value of all kinds of coal is above the quotation for large steam coal illustrates the difficulty of obtaining satisfactory records of prices. The average export value of Cardiff coal in the table on page 91 is very close to, sometimes higher than, market quotations for best Welsh steam coal (f.o.b.) in the last thirty years also. The Newcastle quotations given in the note on p. 85 are related more naturally to the average export values, since the latter are in every case lower than the quoted prices for steam coals of the best quality. The difference is generally quite considerable.

For the last thirty years, a figure somewhat more useful than the average export value can be given, namely, the average value at the pit's mouth. The annual *Report on Mines and Quarries* records this value for the years 1882 to date. The data periodically ascertained for the determination of miners' wages in Northumber-

land and Durham afford a record extending back to 1875, with a further figure for April, 1871.¹

Average Selling Price per Ton of Coal at the Pit's Mouth

Period	Northumber- land	England	Wales	Scotland	United Kingdom	
					Pit's Mouth	Export
1871	<i>s. d.</i> 5 4 ⁸ / ₅	<i>s. d.</i> —	<i>s. d.</i> —	<i>s. d.</i> —	<i>s. d.</i> —	<i>s. d.</i> 9 7 ¹ / ₂
1875-77	6 10 ⁰ / ₃	—	—	—	—	11 4
1878-82	4 10 ² / ₉	5 8*	5 9*	4 5*	5 7 ¹ / ₂ *	8 11
1883-87	4 10 ⁵ / ₃	5 2	5 9 ¹ / ₂	4 5	5 2	8 9
1888-92	6 2 ⁹ / ₈	6 11	8 7 ¹ / ₂	5 7 ¹ / ₂	7 0	10 8 ¹ / ₂
1893-97	5 7 ⁹ / ₃	6 2 ¹ / ₂	7 1 ¹ / ₂	5 6	6 3	9 4 ¹ / ₂
1898-1902	7 11 ¹ / ₁₉	8 4	9 10	7 9 ¹ / ₂	8 5 ¹ / ₂	12 6 ¹ / ₂
1903-04	6 8 ⁰ / ₃	7 4	9 4	6 1	7 5	11 3 ¹ / ₂

* Year 1882 only.

The average export value, as declared, has been added for comparison. It will be noticed that the correspondence between the figures for Northumberland and those for the United Kingdom is sufficient to justify reliance on the former as an indication of the general level of pit-mouth values for periods when the latter is not available.

The following comparison of values at the pit-mouth in Staffordshire three-quarters of a century ago and at the present day is afforded by taking

¹ Cf. *Final Report of Commission on Coal Supplies*, part x, p. 96, and the *Labour Gazette* for later figures for Northumberland.

the prices given to the Select Committee on the Coal Trade (Port of London) Bill in 1838 by Mr. F. Finch. These prices relate to a single colliery, not to the entire county.

Pit-Mouth Prices of Coal in Staffordshire

Period	Large	Intermediate (Lumps)	Small (Slack)
Michaelmas Quarter {	<i>s. d.</i> 7 5½	<i>s. d.</i> 3 7	<i>s. d.</i> 2 7
	1828-32 9 8	1833-37 5 8	2 9*
Period	Average Price	Period	Average Price
1883-87	<i>s. d.</i> 6 1	1893-97	<i>s. d.</i> 6 7
1888-92	6 10	1898-1902	8 0½

* No quotation in 1837.

It is not, however, the absolute level of coal prices in this country, or the relative movements of coal prices and general prices, which is the matter of final interest in connection with the problem discussed by Jevons, but, as shown in other parts of his treatise, the relative course of prices in Great Britain and elsewhere. An especial interest attaches to the comparison of British with German and American coal prices. The "Coal Tables" issued in recent years by the Board of Trade afford the following comparison of pit-mouth values of coal, two columns being added from the United States Geological Survey's

Mineral Resources of the United States, 1902 (p. 324), to show separately the value of anthracite and bituminous coal.

Average Value per Ton of Coal Produced

Period	Belgium	France	Germany	United States			United Kingdom
				Total	Anthracite	Bituminous	
1883-87 . .	s. d. 7 2	s. d. 9 4½	s. d. 5 2½	s. d. 6 4	s. d. 9 0	s. d. 4 10½	s. d. 5 2
1888-92 . .	8 7½	9 4½	6 9½	5 5½	7 2½	4 6½	7 0
1893-97 . .	7 8	8 10¾	6 10	4 11	6 11	4 0½	6 3
1898-1902 .	11 2	11 1½	8 5½	5 1½	7 3	4 6	8 5½

While no large difference is shown in the mine-value of coal in Germany and Great Britain, and the general course of values has been upwards in each of the countries over the period dealt with, the bituminous coal of the United States is produced at a lower cost than the coal of Great Britain, and the advantage has largely increased during the period represented in the table.

A somewhat more extensive view of the course of coal-values in the three principal countries may be secured by using data which, though not presenting averages for the whole country, are yet fairly representative of general conditions.

The last four columns in the table on the following page represent facts more nearly

similar among themselves than any of them are to those represented in the first three columns of prices. The fact that, as their coal resources have been developed, the United States have had an increasing relative advantage over Great

Average Price of Coal in Different Countries (per Ton)

Period	Northumberland		West-phalia ¹		France ²		United States ³		Great Britain
	Selling Price at Mines				Price at place of consumption	Anthracite at Philadelphia	Bituminous at Baltimore	Export value	
1857-61 . .	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	
1867-71 . .	—	—	9 8	18 10	14 2½	15 2	9 1		
1872-76 . .	7 2½	8 8½	12 4	22 3	17 0½	18 2	15 4½		
1877-81 . .	5 1½	5 4	10 5	17 6	14 4½	13 4	9 1½		
1882-86 . .	4 11½	5 9	9 6	16 6	17 9	10 10	8 11		
1887-91 . .	5 10½	7 4	8 11½	16 5	16 5	11 4	10 2		
1892-96 . .	5 11	7 10½	9 0½	15 9	15 4½	9 5	9 9½		
1897-1901 .	7 6	9 2	10 4	18 0	14 9	8 6	11 10½		

¹ Cf. Evidence of Consul-General Mulvany before Royal Commission on Coal Supplies (*Final Report*, part x, p. 309), prices obtained at Dahlbuck Collieries, Gelsenkirchen. For the years 1894-1901 these prices approximate very closely to those realised by the Rhenish-Westphalian Coal Syndicate (cf. Evidence of Consul-General Oppenheimer, *loc. cit.*, p. 297). Prices are per metric ton.

² From *Statistique de l'Industrie Minière* (cf. *Monthly Summary of Commerce and Finance of the United States*, Sept., 1902, p. 728). Prices are per metric ton.

³ *Statistical Abstract of the United States*, 1904, p. 460. The prices given for bituminous (Cumberland) coal, as well as for anthracite, appear to refer to the long ton of 2,240 lbs.

⁴ Average of 1875-6 only.

Britain, is reflected in the table, while the further fact, also in agreement with the previsions of Jevons, that Germany and France have not gained much recently on Great Britain, if at all, in respect of the cost of coal mined within their

own borders, is also brought out. The increase of the cost of coal in the Dortmund district of Germany is well shown in a table on p. 156 of Mr. Francis Walker's *Monopolistic Combinations in the German Coal Industry*, quoted from the *Zeitschrift f. d. Berg-Hütten und Salinenwesen*. It may be noted that R. C. Taylor's *Statistics of Coal* refers to the price of coals at the pit's mouth being much higher in Germany than in England. He quotes prices of 7s. 7d. per ton in Westphalia and 5s. per ton in England as illustrating the remark. These refer apparently to about the year 1845 (*loc. cit.* p. 514). The reduction in the prices of coal quoted for the United States is largely due to reduced cost of transport. The freight rate from the Georges Creek district to Philadelphia is given in the *Twenty-Second Annual Report of the United States Geological Survey*, part iii. (p. 214), as \$1.18 by water, and \$1.45 by rail, per ton to Baltimore. This relates to the year 1900, and is in agreement with quoted prices of Georges Creek coal at the mine. Thus more than half the price of bituminous coal at Baltimore, as quoted above, represents freight. Twenty to thirty years ago the freight rate was fully double that of recent years.

CHAPTER VI

OF BRITISH INVENTION

THE history of discovery and invention, like the history of mankind in general, can never become the matter of an exact science. The extension of the sciences and arts is the last thing that can be subjected to rigorous laws. Yet in a long course of progress, like that which marks the rise of civilisation in England, we may observe tendencies, not free from exception, but of an instructive kind, and bearing powerfully upon the general subject of our inquiry.

The usefulness of Britain greatly depends upon the arts she has contributed for the benefit of mankind, and her own pre-eminence in the practice of those arts. But an Englishman who goes with the current of insular opinion is too apt to assume that Britain is great in everything. There is no discrimination in popular opinion. As Shakespeare is the acknowledged poet of modern

times, so Francis Bacon is supposed to be the philosopher who brought about the revival of knowledge and the arts. Now, though we have poets and philosophers, works and discoveries, which in their own way are unrivalled, we should remember that other nations have their triumphs in their way unrivalled. And if we at present possess a certain leading and world-wide influence, it is not due to any general intellectual superiority, but to the union of certain happy mental qualities with material resources of an altogether peculiar character.

We may observe, in the first place, that almost all the arts practised in England before the middle of the eighteenth century were of continental origin. England, until lately, was young and inferior in the arts.

Secondly, we may observe that by far the greater part of the arts and inventions we have of late contributed, spring from our command of coal, or at any rate depend upon its profuse consumption.

Such generalisations are very often subject to exception. Roger Bacon, for instance, is an illustrious exception, and it seems likely that there were other Englishmen in his days of lofty talents. Still, they drew their education and in-

formation from the Continent, and they lived in such a time and place that their works were unappreciated, and left no mark in the creation of the arts. Francis Bacon has usurped much of the fame due to Roger Bacon. No one in the least degree acquainted with the history of science in Europe can suppose that Francis Bacon gave rise to the sciences and arts which were rising and flourishing in Italy and France and Germany before his time. Great as was Bacon in many ways, we cannot regard him as more than a crude but striking expounder of the scientific tendency of his age. After the severe and partially true exposure of his claims by Baron Liebig,¹ it is to be hoped that we shall give up some of our absurd national fallacies concerning him.

How much of the arts we owe to continental nations, may be learnt from a simple enumeration of our principal debts. It is in Mr. Smiles' volumes that the history of the arts in Britain has been best brought to our notice. These volumes seem to me to be a most valuable contribution to our general history, and the facts

¹ *Macmillan's Magazine*, July, August, 1863. Liebig's pamphlet, *Ueber Francis Bacon v. Verulam und die Methode der Naturforschung*, appeared originally in Munich in 1863. A like severe criticism is contained in A. Lasson's *Ueber Baco's von Verulam wissenschaftliche Prinzipien*, Berlin, 1860.

adduced by him clearly establish that until about the middle of the eighteenth century we were wholly behindhand in all that relates to skilled industry, and were justly treated by the great advanced nations of the Continent—by Italy, Spain, France, and Holland—as poor, uncultivated, but proud islanders. “England,” he says, “was then regarded principally as a magazine for the supply of raw materials, which were carried away in foreign ships, and partly returned to us in manufactures, worked up by foreign artisans. We grew wool for Flanders, as America grows cotton for England now. Even the little manufactured at home was sent to the Low Countries to be dyed.”¹

Generalisations on this subject, I have said, are open to exceptions. It is not true that England made no contributions to the arts down to the time of the steam-engine and the coal-blast furnace; but I know of only one exception, the knitting-frame of William Lee, a truly singular invention of the year 1589. This invention is favourably mentioned by Sturtevant in his curious treatise on Metallurgy of the year 1612. Its solitary character is shown by the fact that an Act prohibiting the export of stocking-frames was

¹ Smiles' *Engineers*, vol. i, preface, p. v.

passed as early as 1696,¹ but that no other Act of the same kind was thought needful until 1750. It was not till 1774 that a third Act of the kind² made a beginning of the general system of prohibiting the export of machinery, contrived to protect our rising success in the cotton, linen, and other manufactures. In this mistaken and illiberal system the English Government persevered until August, 1843.

Mining is an art in which we are now at least eminent. But a hundred and fifty years ago, as most Englishmen will be surprised to learn, the engines and contrivances in common use in England were only those familiar to the Germans 100 or 200 years before. The horse-gin, the double reversing water-wheel, the chain-pump, ventilating contrivances, such as bellows, fans, lamps, furnaces, together with the underground wheeled carriage, were introduced from Germany, probably by the German miners brought over in considerable numbers during the reigns of Elizabeth and the Stuarts. These inventions, in fact, were described in the work of Agricola published in 1556, and this writer was acquainted with such valuable contrivances as the fly-wheel, and the

¹ 7th and 8th William III, cap. xx, sec. 8 and 9.

² 14th Geo. III, cap. lxxi.

crank and beam.¹ Hooson, an early writer on coal-mining, expressly says, "We do not know of anything material or useful that has been found out for the better, than what has been left us by our forefathers; but rather much impaired by neglect and idleness."²

Gunpowder is an almost indispensable agent in mining, and was used by the Germans as early as 1613. Its use for blasting was introduced into this country in 1665, and, according to Robert Bald,³ the ancient method of drilling and wedging rocks open by the stook and feathers, without powder, was still used in Scotland at the beginning of the eighteenth century.

Metallurgy is an art which we now carry out on a vast scale; but, with the exception of the processes depending on the superior abundance and excellence of our coal, both the theory and practice of metallurgy are mainly due to the Germans. Dr. Percy, in the preface to his important work on Metallurgy, drew attention to the fact that we had scarcely any literature on the subject, and must draw our information from the two leading works of Agricola in 1556, and

¹ Taylor's *Archæology of the Coal Trade*, p. 186, in *Memoirs of the British Archæological Association*, 1858.

² Hooson's *Miner's Dictionary*, 1747, quoted by Taylor, p. 187.

³ *Scotch Coal Trade*, p. 12.

Karsten in 1831, or from the large collection of monographs, periodical publications, and complete treatises on Metallurgy, with which the German language abounds. Even the Swedish physicists, Scheele and Berzelius, made greater contributions to the art than individual Englishmen can boast of.

Many of the arts of working iron were drawn from the Continent. It will be shown in the chapter on the Iron Trade, that the first efforts towards the erection of our great iron manufacture were made by German metallurgists. It was Godfrey Box, of Liège, who erected at Dartford, in 1590, the first iron mill for slitting bars; and from the slitting-mill was no doubt derived the notion of the rolling-mill as invented by Cort. Yarranton went to Saxony to learn the process of tinning iron plates, as carried on there with great profit, and he was allowed to engage workmen and to inspect all the operations of the manufacture. The making of clasp-knives was introduced into Sheffield in 1650, by Flemish workmen, such knives having been previously known as *joc-te-legs*,¹ from Jacques de Liège, a celebrated foreign

¹ See Burns, *On the late Captain Grose's Peregrinations*, "A faulding jocteleg." In some parts of Yorkshire a large clasp-knife is still known as a "jack-a-leg's knife."

cutler.¹ The casting of iron cannon was a French invention, introduced into Sussex in 1543, by Peter Baude, a Frenchman, brought over by Ralph Hogge, the Sussex ironmaster, who also employed a Flemish gunsmith, Peter Van Collet, to make his explosive shells.²

Engineering was taught us by continental nations until we developed our own new modes of engineering with iron. The Dutch, having redeemed their own country from the sea, were masters of the art of embankment, drainage, and inland navigation. The history of the works carried out by them in our fens, of the skill, capital, and labour they expended here, and the precarious profits they carried back, is to be found in Mr. Smiles' volumes.³ We are reminded of the part which English engineers and capitalists have been accustomed to play of late years in constructing the railways, canals, and public works of the Colonies and many foreign States. Even as late as 1748, we owed to Labeyle, the Swiss architect, the reconstruction of the south level of the Fens, and the building of Westminster Bridge.⁴ When a tidal engine was required to pump water from the Thames

¹ Smiles' *Industrial Biography*, p. 68.

² *Ibid.*, p. 33.

³ *Lives of the Engineers*, vol. i, pp. 39, 40.

⁴ *Ibid.*, p. 66.

for the supply of London, Peter Morice, a Dutchman, was employed to erect it.¹

Scotland was even more backward than England. When in 1708 windmills were wanted to make an attempt at draining certain Scotch coal-mines, John Young, the millwright of Montrose, was found to be the only man in the country who could erect windmills. He had "been sent at the expense of that town to Holland, in order to inspect the machinery of that country," and "it was suggested that, if this millwright could not be procured, application should be made to the *Mechanical Priest in Lancashire* for his advice."²

In maritime enterprise the British were always daring, but only of late have we been eminently expert or successful. "At a time," says Mr. Smiles,³ "when Spain, Holland, France, Genoa, and Venice were great maritime powers, England was almost without a fleet, the little trade which it carried on with other countries being conducted principally by foreigners. Our best ships were also built abroad by the Venetians or the Danes, but they were mostly of small tonnage, little bigger than modern herring boats."

¹ *Lives of the Engineers*, preface, p. vi.

² Bald, *Scotch Coal Trade*, p. 7.

³ *Lives of the Engineers*, vol. i, p. 276.

The herring fishery was regarded both by Holland and England as the "chiefest trade and gold-mine," and "the way to winne wealth." It was thought to lead to the direct creation of riches, and to nourish at the same time a race of hardy seamen that are the pride and safeguard of the kingdom. But it raised unutterable feelings of envy and disgust in English writers of a century or two ago, to observe that the Dutch fished our own seas. Holland, "not exceeded in quantity by Norfolk and Suffolk, hath gotten the sea," bitterly says the author of *The Trades' Increase*. And even when we caught a few herrings, we had to learn from the Flemings how to cure them.

The Dutch, as is well known, were our predecessors in the general commerce of the world. A writer of the year 1615 thus speaks, "Without love or anger, but with admiration of our neighbours, the now Sea Herrs, the nation that get health out of their own sicknesse, whose troubles begot their liberty, brought forth their wealth, and brought up their strength, that have, out of our leavings, gotten themselves a living, out of our wants make their own supply of trade and shipping there; they coming in long after us, equal us in those parts in all respects of privilege

and port ; that have devanced us so farre in shipping that the Hollanders have more than one hundred saile of shippes that use those ports, continually going and returning, and the chiefest matters they doe lade outward be English commodities, as Tinne, Lead, and Bailes, of such like stuffe, as are made at Norwich.”¹

Campbell was aware of their commercial superiority. “By keeping their customs low,” he says, “they have their warehouses always full of goods and manufactures of every kind. . . . Rough and raw materials they cleanse and sort ; gross and bulky commodities they import in one kind of vessels, divide and export them in others. A low interest keeps the bulk of their cash in trade ; working cheap, and selling at a small profit, secures them in continual employment.”² The Dutch, in short, understood the principles and practice of commerce, and had a free and far-spreading trade when we were yet sunk in poverty and the fallacies of the mercantile and restrictive systems. And it was undoubtedly the Venetians, Jews, and other foreign merchants of Lombard Street, who laid the foundations of our vast banking and monetary system.

¹ *The Trades Increase*, p. 7.

² *Campbell's Survey*, vol. i, p. 15.

While we were so much inferior to continental nations in the fundamental operations of trade and industry, it is almost needless to observe, that in the more luxurious arts of life we were wholly indebted to them. "Our first cloth-workers, silk-weavers, and lace-workers were French and Flemish refugees. The brothers Elers, Dutchmen, began the pottery manufacture; Spillman, a German, erected the first paper-mill at Dartford; and Boomen, a Dutchman, brought the first coach into England."¹ The name of the fabric, Brown Holland, shows whence we derived it. The arts, indeed, of weaving and whitening linen attained high perfection in Flanders and Harlem especially, while the common processes of dyeing were wholly the work of foreigners, chiefly Germans.²

France was then, as now, supreme in many little branches of manufacture, such as those of glass, hats, paper, linen, sail-cloth, sword-blades, scissors, and many steel "toys." The "running" of such light articles fortunately could not be prevented. We also drew from them "wine, brandy, linen, fine lace, fine cambricks, and cambrick lawns, to a prodigious value; brocades,

¹ *Smiles' Engineers*, vol. i, preface, p. vi.

² *Barlow's Cyclopædia*, p. 521.

velvets, and many other rich silk manufactures, which are either run in upon us, or come by way of Holland.”¹

Generally the advanced arts and knowledge of continental nations seem to have been communicated to us without jealousy or reserve. Yarranton, for instance, in his tours of observation in Holland, enjoyed every facility. Sometimes we resorted to deceit; as when Foley, according to one account, learned the art of splitting iron from the Swedes, and Sir Thomas Lombe gained the use of the water-frame in the silk manufacture. Such achievements, when in our favour, are treated as romantic and courageous adventures; but when foreigners now come prying into our factories, forges, and chemical works, we are apt to treat them as rogues.

Even the steam-engine cannot be claimed as a purely indigenous invention. But before we consider this point, or go on to enumerate the undoubted contributions made by British inventors, it is necessary to discriminate the conditions of invention.

There seem to be three essential conditions, too often confused or overlooked:—First, a dis-

¹ Joshua Gee, *The Trade and Navigation of Great Britain considered*, 1738, 4th ed., p. 18.

tinct PURPOSE, arising from an urgent need of some new means of accomplishing a definite end. Secondly, a new PRINCIPLE, or mode, by which it is to be accomplished. Thirdly, the material, power, and skill for embodying this principle in a successful machine,—in short, the CONSTRUCTION.

For instance, as a maritime nation, we felt during the eighteenth century the most urgent need of a sure method of determining the longitude of a ship at sea : here was a strong *purpose*. Astronomy pointed out several different *principles* on which it might be done, the most convenient principle involving the use of a good time-keeper. It was Harrison, of Liverpool, who, under the stimulus of a large Government reward, invented the ship's chronometer, and supplied the material instrument or *construction* of the method commonly employed.

Now, as regards the history of the steam-engine, there can be no doubt that an urgent need was felt at the beginning of the seventeenth century for a more powerful means of draining mines. Sir George Selby said in Parliament, as early as 1610, that "the coal-mines of Newcastle could not hold out the term of their lease of twenty-one years."¹ This was on account

¹ Taylor's *Archæology of the Coal Trade*, p. 186.

of the cost or impossibility of draining them to any great depth. The terms in which the steam-engine was first described, and the way in which it was actually used for nearly two centuries, show that the raising of water out of our mines was the all-important object aimed at—the first condition—the purpose.

The cheap coal, drawn from the same mines, was to prove the material power or third condition of the great invention; but, in the meantime, we needed a new natural principle of action. Candour obliges us to allow that we owe this principle to science and to France. It is true that the English writer Hugh Platte had, in 1594, shown how the steam of boiling water might be made to issue in a powerful jet, sufficient to blow a fire.¹ But he probably owed this notion to some of the works of practical science and ingenuity which abounded at that time on the Continent. No doubt Arago was right in insisting² that Solomon de Caus, a French engineer employed by King Charles, first spread abroad in England scientific notions about raising water by the expansive force of steam. His work, *Les Raisons des Forces Mouvantes*,

¹ Jewell, *House of Art and Nature*, No. 21; London.

² *Life of Watt*, 1839, p. 46.

was first published in the year 1615, several years before the era of Bacon's *Novum Organum*. A print in this work shows a metallic globe, containing water heated by a fire. A long, upright, open pipe passes air-tight through the top of the globe, and terminates in the water near the bottom of the globe. The water, urged by the expansive force of the steam within the globe, is represented as issuing forcibly from the top of the pipe. A second edition of the work appeared in 1624; and in 1644 was published, at London, by Isaac de Caus, a partial reprint, distinctly entitled *Nouvelle Invention de lever l'Eau*.¹

Now, considering that the earliest patents which apparently refer to a steam-engine are of the years 1628 and 1631;² that the Marquis of Worcester's "water-commanding engine" and his almost prophetic statements were of the year 1663; that Sir S. Morland's proposals were made in 1683; and Thomas Savery's success achieved in 1698,—it is hard to deny that we owe the engine, as regards the second or scientific condition, to a French work.

The Marquis of Worcester's engine was the

¹ Dircks in his *Life of the Marquis of Worcester* strangely overlooked this work of Isaac de Caus.

² Rymer's *Fœdera*, vols. xviii p. 992, xix pp. 236 and 239; or, *Calendars of the State Paper Office*, Domestic Series, 1629-31, pp. 396, 483.

first which we know to have been really constructed. Its purpose is clearly stated in the "Exact and True Definition," by "an antient Servant of his Lordship."

"There being, indeed, no place but either wanteth water, or is overburdened therewith, (and) by this engine either defect is remediable." Its principle, there is little doubt, was that enunciated by De Caus, from whom it was in all probability derived. For, as Dircks admits,¹ and as it was perfectly right and wise to do, the Marquis "evidently availed himself of every suggestion that either reading, accident, experience, or travel, threw into his way." With the construction of Worcester's Engine we are not acquainted, but it seems to have been in part due to his assistant Caspar Kaltoff, a Dutchman and an "unparalleled workman both for trust and skill."

It is in Thomas Savery's description of his engine that we can most clearly discriminate the conditions of the great invention. The purpose was clearly to raise water and drain mines, as indicated by the title of his excellent little publication, *The Miner's Friend*, but most explicitly stated within. "I do not doubt," he says,² "that,

¹ H. Dircks, *Life of Worcester*, p. 354.

² Page 6.

in a few years, it will be a means of making our mining trade, which is no small part of the wealth of this kingdom, double if not treble to what it now is." He continues,¹—"The coals used in this engine are of as little value as the coals commonly burned on the mouths of the coal-pits are;" and "the charge of them is not to be mentioned, when we consider the vast quantity of water raised, by the inconsiderable value of the coals used, and burned in so small a furnace." Here we have the most distinct statement that the purpose of the engine was to use the waste and valueless slack coals to overcome the great obstacle to the progress of our mines. The position which Savery contemplated for his engine was clearly the mouth of a coal-pit.

As to the principle of the invention, it was that of De Caus, with the additional use of the vacuum, which may have been the discovery of Savery himself. It is, however, in the construction of the machine that Savery's highest credit seems to lie. "I have met," he says,² "with great difficulties and expense to instruct handicraft artificers to forme my engine, according to my design." And whoever examines the picture

¹ Pages 35, 36.

² *Miner's Friend*, Prefatory Address to the Royal Society.

of his engine, either in the original work or in copies, will be struck by the very compact and workmanlike form of the machine, which would be a creditable piece of mechanism even at the present day. There is no doubt that by this time the use of cheap and excellent coal at Wolverhampton, Birmingham, and Sheffield, had enabled our artisans to acquire remarkable skill in the working of metals;¹ and it is to this facility of construction, joined to the principle published by De Caus, but especially to the strong purpose and incitement offered by the condition of our coal-mines, that I should attribute the complete invention of the steam-engine.

Savery's engine was extremely wasteful of heat, because the steam came into contact, not only with the cold vessel, but also with the cold water to be moved. It was so uneconomical, that, in spite of the cheapness of coals, it could not come into common use. Denis Papin, a French refugee, and an engineer of the highest mechanical talents, discovered and published, before the Royal Society in 1699, the new principle required to perfect the engine, that of a piston

¹ See Dr. Plot's account of the artisans of Wolverhampton, Walsall, and the Neighbourhood, *Natural History of Staffordshire*, p. 376; also Smiles' *Lives of Boulton and Watt*, p. 163.

intervening between the steam and the water. But the Frenchman was deficient in constructive power, and it was reserved for Newcomen to accomplish the atmospheric engine, which was found to be capable of draining our mines and reviving our industry.

The subsequent steps in the improvement of the engine consisted chiefly in methods of using the steam more economically. They will be considered in the following chapter.

The atmospheric engine, perfected in some mechanical details by Smeaton, was employed throughout the eighteenth century, not only to drain the coal and Cornish mines, but, in the absence of the crank and the sun and planet wheels of Watt, to raise water *to turn water-wheels* in places where a natural supply of water was deficient, an employment anticipated by Ramsey, Worcester, Morland, and Savery.

The engine, from an early period of its history, turned the tide of the arts. As Briavoinne remarks,¹ it was indispensable that other nations should follow England in adopting this newly found power; and, between 1722 and 1733, the first engine was sent from England to Belgium,

¹ Briavoinne, *De l'Industrie en Belgique*, Bruxelles, 1839, p. 201.

and set to work by the aid of English mechanics.¹

Its effect upon the English mines was extraordinary. "The steam-engine produced a new era in the mining and commercial interests of Britain, and, as it were in an instant, put every coal-field, which was considered as lost, within the grasp of its owners. Collieries were opened in every district, and such has been the astonishing effect produced by this machine, that great coal was shipping free on board in the River Forth, in the year 1785, at 4s. 10d. per ton; that is, after a period of seventy years, coals had only advanced 2d. per ton, while the price of labour and all materials was doubled."²

Of hardly less importance than the steam-engine are the new modes of conveyance, gradually introduced or discovered here, during the last two hundred and fifty years. Common roads, worth calling such, only began to be made in the middle of the eighteenth century, when the enterprise of the country was roused by the new influence of steam and iron. Between 1760 and 1774, no fewer than 452 Acts for making or

¹ Toilliez, *Mémoire sur l'Introduction des Machines à Vapeur dans le Hainaut*. Quoted by Briavoinne, p. 226.

² Bald, *Scotch Coal Trade*, p. 24.

repairing highways passed through Parliament ;¹ and it is necessary to read Mr. Smiles' volume to form a notion of the previous wretched state of our communications. Common roads, however, have little further connexion with our subject.

Canals might also seem utterly disconnected from the use of coal. Certainly, both in principle and construction, they have nothing to do with it. Holland, France, Sweden, and Russia had created and developed, on a large scale, the art of making canals long before we had a single canal. Holland enjoyed a magnificent system of artificial water communication. France had connected the Loire and Seine, the Loire and Saône and the Atlantic Ocean with the Mediterranean ; Peter the Great had constructed a canal from the Don to the Volga.

But until coal supplied the *purpose* there was not spirit enough in this country to undertake so formidable a work as a canal. In spite of Yarranton's demonstration of the advantages of inland navigation, the first true canal Act was that passed in 1755 for making the Sankey Brook Cut, to enable the coal of St. Helen's to reach the Mersey. This small work drew the Duke of Bridgewater's attention to the profit to be derived

¹ Smiles' *Lives of the Engineers*, vol. i, p. 206.

from a more economical mode of conveying coal to Manchester. In getting an Act passed to cut the celebrated canal from his mines at Worsley to Salford, he bound himself not to charge more freight on coal than 2s. 6d., the previous cost of carriage having been 9s. or 10s. The opening of the canal at once reduced the price of coal in Manchester, from 7d. per cwt. (120 lbs.) to 3½d.;¹ and it is impossible to say how much such a reduction may not have contributed to the growth of industry in this great centre. And, while one branch carried fuel, the other branch of this grand work was carried from Manchester to the Mersey, in order that raw materials might be brought into conjunction with the fuel, and the finished products conveyed back. The Duke of Bridgewater's view of the innate power of England was clearly shown in his saying that "a navigation should always have coals at the heels of it."²

Railroads, however, are perhaps our great, and, it would seem, our purely indigenous invention. The principle involved is little more than that of a wheel upon a hard road, but it is surprising how entirely the development of the principle has been connected with our coal trade. The

¹ Smiles' *Lives of the Engineers*, vol. i, pp. 344—361.

² *Ibid.* vol. i, p. 401.

first known use of the rail is due to Beaumont, in the year 1630. This gentleman went to Newcastle at a period of our history when enterprise and ingenuity seemed the rule. But his merits and his reward are summed up in a quaint passage:—"One Master Beaumont, a gentleman of great ingenuity and rare parts, adventured into the mines of Northumberland with his £30,000, and brought with him many rare engines, not then known in that shire, and waggons with one horse, to carry down coals from the pits to the river; but within a few years he consumed all his money, and rode home upon his light horse."

The early rails were simple bars of wood, laid parallel upon wooden sleepers or embedded in the ordinary track to diminish friction. They were gradually introduced into the other coal districts of Wales, Cumberland, and Scotland—at Whitehaven as early as 1738. It was soon found that a slip of iron, nailed upon the wooden rail, was economical in preventing wear; and when the abundance of iron had been increased by the coal-blast furnace, rails made entirely of iron were substituted. Such iron rails were first used by Reynolds at the Coalbrookdale works, the birthplace of the smelting furnace, to facilitate

the conveyance of coal and ore. In 1776, again, a cast-iron tramway, or plate-way, was introduced into the underground workings of the Duke of Norfolk's colliery, at Sheffield, by John Curr, whose writings prove his perception of the importance of the improvement.¹ It was in 1789 that William Jessop made a railway at Loughborough, with cast-iron edge rails, and a flange transferred to the waggon wheel. Finally, in 1820, nearly two hundred years after the employment of wooden rails, wrought-iron rails, invented by Mr. Birkenshaw, were rolled at the Bedlington iron-works, on the river Blyth, near Newcastle.²

But the railway was incomplete without steam power. Every one knows the history of the locomotive—that it was brought into successful use by *George Stephenson, the colliery engineman, for the purpose of leading coals from the pit to the shipping place*; that, after long exertions, it was proved more economical than horse-power, and that when the growing goods traffic between the coal-driven factories of Manchester and the port at Liverpool had altogether exceeded the powers of the canal, a railway was undertaken which led to our present system.

¹ *Coal Viewer's and Engine Builder's Practical Companion*, 1797.

² *Report of British Association*, 1863, p. 760.

Throughout the history, then, of this great and indigenous invention, we constantly find the *purpose* and *construction* alike dependent on the working of coal. The conveyance of great weights of coal was the purpose ; the energy that is in coal, and the cheap iron it yields, supplied the constructive means of accomplishing that purpose. Not unnaturally, then, was Newcastle the cradle of the railway system.

Although, in later years, railways have been extended through purely agricultural countries, such as Russia or the Western States of North America, yet we may observe, in many places, and especially in England, that the rapid extension of railways is mainly due to the traffic and wealth occasioned by the use of coal in manufactures. It was long ago observed by a writer on the coal trade, that "the numerous canals and conveyances from the distant parts of the kingdom, and to local stations, owe their existence to the wealth acquired by the use of coal."¹ Now, if a series of railway-maps of Great Britain, for the last [sixty or seventy] years, be closely examined, it will be apparent, not only that the railway system was developed on the coal-fields, but that it yet converges upon them,

¹ C. Beaumont, *Treatise on the Coal Trade*, 1789, p. 2.

just as the arteries and veins of the animal body converge upon the heart and lungs. The densely crowded lines of railway around Newcastle, Manchester, and Wolverhampton form the heart of the railway system. There are, indeed, several great aortal lines which connect the coal-fields with each other or with the metropolis, the head of the body; or the metropolis with the Continent; but in every other direction, it will be observed that the railway system becomes sluggish in proportion to its distance from a coal-field, the traffic subdividing and dwindling away like the arterial streams of the animal body. For many years the least successful railways were the Great Western, the Great Eastern, and other lines of railway which run into the most purely agricultural parts of the kingdom. Wise and far-seeing, then, were the favourite notions of George Stephenson:—"The strength of Britain," he used to say, "lies in her iron and coal-beds; and the locomotive is destined, above all other agencies, to bring it forth. The Lord Chancellor now sits upon a bag of wool, but wool has long ceased to be emblematical of the staple commodity of England. He ought to sit upon a bag of coals."¹

¹ Smiles' *Engineers*, vol. iii, p. 357.

As regards bridges, the command of iron has given us advantages of construction never before enjoyed. Italian and French engineers were altogether our superiors in bridge-building until near the end of the eighteenth century ; but they failed, as in an instance at Lyons in 1755, in iron bridges, "chiefly because of the inability of the early founders to cast large masses of iron, and also because the metal was then more expensive than either stone or timber." ¹ The first iron bridge was erected at Coalbrookdale by Messrs. Reynolds and Darby in 1777 ; and we know what has since been accomplished in the construction of iron bridges, when the extension of roads and railways presented an adequate purpose.

Iron presents the necessary material condition of several things, which would not be supposed to be dependent on it. The supply of water depends on the use of iron pipes. When Sir H. Middleton had brought the New River to London, he found the distribution of the water a matter of the greatest difficulty—the old wooden pipes wasting one-fourth of the supply, and being subject to rapid decay.² Coal-gas, again, itself an important product of coal, could not be used

¹ Smiles' *Engineers*, vol. ii, p. 355.

² *Ibid.* vol. i, p. 126.

in its present abundance and economy, without the use of iron distributing-pipes.¹

A more important use of iron is in the development of mechanical engineering in general. Our inventions for spinning and weaving by machinery are not, in their origin, dependent on coal. The early mills were turned by water, and involved but little iron work. The development and perfection of our factory system, however, could never have been carried far without abundance of iron. "The inventions of Arkwright, Crompton, and others," says Mr. Fairbairn,² "could not have been executed but for iron; and it is fortunate for the industrial resources of the country, that the manufacture of iron has kept pace with our industrial progress. I am not able to state the amount of consumption of iron in machine-making alone, but taking that for cotton machinery in only one of our largest firms, that of Messrs. Platt and Co. of Oldham, I should average it at 400 or 500 tons per week; and in that of my late brother, Sir Peter Fairbairn, of Leeds, in flax and other machines, at 250 to 300 tons per week."

¹ Hearn's *Plutology*, 1864, p. 193.

² *Two Lectures on Iron and its Applications*, Newcastle, 1864, p. 15.

In some of the old water-mills, yet working in remote country places, we may see ponderous wooden shafts, spindles, and wheels, which seem hardly adapted now-a-days to receive motion, much less to communicate it. Brindley was brought up as a millwright, in the use of wood, and long clung to it—even making wooden-hooped cylinders for engines, which were naturally apt to break down. But having at last discarded brick, stone, and wood, he constructed in 1763, at Coalbrookdale, an engine that was a “complete and noble piece of iron-work.”¹ Smeaton carried forward the substitution of iron for wood ; but it was Rennie who established its general use, in his celebrated Albion Mills, the whole of his wheels and shafts being made of cast-iron. We find, then, in cast-iron, a material condition which allowed a general advance in the construction of our machines.

A second substitution, however, took place, of wrought-iron for cast-iron. It was Mr. Fairbairn who chiefly introduced the use of light wrought-iron shafting for heavy, slow, cast-iron work, and thus effected a general economy and advance in the employment of machine power, almost com-

¹ Smiles' *Engineers*, vol. i, pp. 332, 333.

parable with that of Brindley, Smeaton, and Rennie.¹

[The use of steel, since the perfecting of the Bessemer process has afforded a cheap and abundant supply, has occasioned] a third, and as far as we can see, a final substitution of steel for nearly every other material ; so that our machines are carried to an apparent maximum of efficiency, economy, and elegance, as regards the material of our works.²

The shaping and moulding of iron, on the large scale, demanded a wholly new set of arrangements. A purpose having arisen for new inventions, the ancient principles of the lathe, the hammer, and the plane were developed by workmen such as Bramah, Maudslay, Clements, Roberts, Whitworth, Nasmyth, and Wilson. Thus there gradually grew up a system of machine-tool labour, the substitution of iron hands for human hands, without which the execution of engines and machines, in their present perfection and size, would be impossible.

¹ Fairbairn on *Mills and Mill-work*.

² The language of anticipation used by Jevons in regard to this further change, may now be replaced by that expressing attainment. It was nearly a decade after he wrote before the improved processes of manufacture had so far reduced the cost of steel as to make steel rails cheaper than wrought-iron rails. (See also Chap. xv.)

“When I first entered this city,” said Mr. Fairbairn, in his address to the British Association at Manchester, in 1861, “the whole of the machinery was executed by hand. There were neither planing, slotting, nor shaping machines ; and, with the exception of very imperfect lathes, and a few drills, the preparatory operations of construction were effected entirely by the hands of the workmen. Now everything is done by machine tools with a degree of accuracy which the unaided hand could never accomplish.”

Any one who reflects upon what has been brought to pass by the use of abundant iron will agree with the remark of Locke, that “he who first made known the uses of iron may be truly styled the Father of Arts, and the Author of Plenty.” Such has been our work in recent times.

It would be absurd to try to follow out in detail the mechanical contrivances of the present age. Reflection will show that they are mainly but the completions of a system of machine labour, in which steam is the motive power, and iron the fulcrum and the lever. The principles of science involved are in no way our own property, being quite as successfully studied on the Continent as

here. But from the cheapness of coal and iron we have had a peculiar advantage in developing their use; and therefore all the details of machine construction are pushed forward in one great system, of which no part can advance far without the rest.

The Britannia Bridge, our truest national monument, "was the result of a vast combination of skill and industry. But for the perfection of our tools, and the ability of our mechanics to use them to the greatest advantage; but for the matured powers of the steam-engine; but for the improvements in the iron manufacture, which enabled blooms to be puddled of sizes before deemed impracticable, and plates and bars of immense size to be rolled and forged; but for these the Britannia Bridge would have been designed in vain. Thus it was not the product of the genius of the railway engineer alone, but of the collective mechanical genius of the English nation;"¹ and Mr. Robert Stephenson himself said, "The locomotive is not the invention of one man, but of a nation of mechanical engineers."²

There is no better example of what our united inventions can accomplish than the iron or steel screw steam-vessel, the product of coal from truck to keel—hull, engines, masts, rigging, anchors.

¹ Smiles' *Engineers*, vol. iii, p. 440.

² *Ibid.* p. 8.

Of this product of our industry, Mr. Porter remarked, that "it was one in which our mineral riches and our great mechanical skill will secure to us a virtual monopoly."¹ But we cannot forget that a steam-vessel is endowed with a constant and voracious appetite for coal, that must fearfully accelerate the drain upon our mines.

There yet remains a whole class of inventions, of a chemical rather than a mechanical nature, where a substance has to be altered in its intimate constitution, instead of its outward form. In these inventions iron is in a very minor degree useful; and accordingly, it can hardly be asserted that in the chemical and experimental sciences and arts we are more than barely equal to the French or Germans. Photography, for instance, presents an instance of equal progress in several different nations.

Many remarkable instances have occurred of

¹ *Progress of the Nation*, p. 577 (ed. of 1851). In the former editions, the text included the following lines at this point:—"And any one who considers the present progress of iron ship-building in this country must see that half a century hence our chief ocean conveyances will be wholly by steam. Sailing vessels will not be entirely discarded, but will occupy a subordinate rank, similar to that of canal boats and coasting vessels. Our world-wide communications will be improved in a degree now perhaps unthought of." The attainment of the supremacy of steamships over sailing ships makes the passage superfluous in the text. It so well illustrates the accuracy of Jevons' grasp of the conditions of our maritime trade that it seems undesirable to omit it entirely.

the commercial replacement of one chemical substance by another. The progress of commerce often depends on such replacements, as when the palm and cocoa oils are used instead of tallow and linseed oils; silk instead of wool, cotton instead of flax, Spanish grass [or wood-pulp] instead of rags, wheat instead of rye or buckwheat, turnips instead of hay.

So far as such substances are beyond the constructive arts, and of purely organic origin, they are beyond our present subject. But many of the more important substitutions are due to coal. Most chemical processes depend on the use of heat; and our cheap fuel has enabled us to raise many great branches of chemical manufacture. Our Cheshire salt mines, with the aid of cheap coal, give us a supremacy in the salt trade, reversing the import trade which used to be carried on, when salt was made by the natural evaporation of sea-water on the coasts of France, Spain, and the Mediterranean. Cheap salt, again, with abundance of fuel, was made to yield carbonate of soda, which replaced, with a great reduction of price, the soda formerly got from kelp or barilla, the ashes of sea-weed. This cheap supply of alkali is all-important in our soap and glass trades, and in a great variety of minor chemical manu-

factures. Potash, on the contrary, still continues to be obtained from the ashes of wood, and is accordingly imported at a high price from Canada or Russia. If ever it be extracted from its natural source in felspar, it must be done by an abundant use of fuel.¹

When the Government of the Two Sicilies placed an exorbitant tax on sulphur, Italy having, as it was thought, a monopoly of native sulphur, our manufacturers soon had resort to the distillation of iron pyrites, or sulphide of iron; and it has been remarked by Liebig that sulphur could have been extracted, if necessary, from gypsum, or sulphate of lime.² Cheap fuel would still be the all-important condition.

Perhaps the most wonderful mode of employing

¹ Roscoe and Schorlemmer, referring to the extraction of potash from felspar, say that "experience has shown it to be impossible to obtain potash from this source, and fortunately other richer sources of potassium compounds have been discovered" (*A Treatise on Chemistry*, London, 1897, vol. ii, p. 258). "Potashes are . . . manufactured . . . from potassium sulphate, which is obtained in considerable quantity both from the Stassfurt beds and from seawater" (*ibid.* p. 259). For the purpose of converting the sulphate into the carbonate, it is heated in a reverberatory furnace with the requisite quantity of limestone and coal. Jevons' contention, though formally not realised, is in effect borne out in practice. *The Mineral Industry* for 1902 states that "the world's supply of potassium salts, with the exception of saltpetre, continues to be derived from Germany." The production of carnallite at Stassfurt began in 1861, of kainite in 1865, the latter being the chief present source of potash. ² Liebig's *Letters on Chemistry*, pp. 152, 153.

coal is in the ice-machine, two kinds of which, of French and English invention respectively, were at work in the Exhibition of 1862. By such machines, *we may make fire, in the hottest climate, produce the cold of the Polar Regions!*

With fuel and fire, then, almost anything is easy. By its aid in the smelting furnace or the steam-engine we have effected, for more than a century past, those successive substitutions of a better for a worse, a cheaper for a dearer, a new for an old process, which advance our material civilisation. But when this fuel, our material energy, fails us, whence will come the power to do equal or greater things in the future? A man cannot expect that because he has done much when in stout health and bodily vigour, he will do still more when his strength has departed. Yet such is the position of our national body, unless either the source of our strength be carefully spared, or something can be found better than coal to replace it, and carry on the substitution of the better for the worse. Whether the consumption of coal can be kept down in our free system of industry, or whether in the process of discovery we can expect to find some substitute for coal, must next be considered. The dispassionate conclusion will be far from satisfactory.

CHAPTER VII

OF THE ECONOMY OF FUEL

It is very commonly urged, that the failing supply of coal will be met by new modes of using it efficiently and economically. The amount of useful work got out of coal may be made to increase manifold, while the amount of coal consumed is stationary or diminishing. We have thus, it is supposed, the means of completely neutralising the evils of scarce and costly fuel.¹ It is shown, in fact, by the mechanical theory of heat, that a good engine of the present day does not convert into useful work more than one-sixth part of the energy developed in the combustion of the coal consumed.² In furnaces, too, the

¹ See for instance the remarks of Waterston in his *Cyclopædia of Commerce*, 1846, pp. 163, 164.

² A pound of coal may be taken as yielding 13,500 thermal units

portion of heat actually used is a small and often infinitesimal fraction of the heat wasted; and in the domestic use of coal, in open grates, at least four-fifths of the heat escapes up the chimney unheeded.

I speak not here of the *domestic consumption of coal*. This is undoubtedly capable of being cut down without other harm than curtailing our home comforts, and somewhat altering our confirmed national habits. The coal thus saved would be, for the most part, laid up for the use of posterity. But even if our population could be induced to abstain from the enjoyment of a good fire, the saving effected would not extend over more than about [one-fifth] part of the total consumption of coal; the domestic consumption being, on an average, about [fifteen hundred-weights] per annum per head of the population. Of the other [four-fifths] nearly a [quarter] is used in our iron manufactures; and the remainder in

in burning, which is equivalent to $13,500 \times 772 = 10,422,000$ foot-pounds of work. One-sixth part of this is 1,737,000 foot-pounds. One horse-power exerted for one hour is equivalent to 1,980,000 foot-pounds. To utilise one-sixth of the heat of combustion, it would be necessary to develop a horse-power by the consumption of 1.14 lbs. coal per hour. The most economical result so far attained with steam-engines is a consumption of .97 lb. of coal per horse-power hour. An engine may be called good even though consuming double this amount (*cf.* also footnote, p. 148).

our factories, furnaces, and machine shops generally.¹

¹ The following table shows the distribution of the uses of coal as reported by the two Royal Commissions :—

	Tons	
	1869	1903
Railways (all purposes)	2,030,000	13,000,000
General Manufacture	22,780,000	53,000,000
Mines and Collieries	7,200,000	18,000,000
Iron and Steel Industries	32,450,000	28,000,000
Other Metals and Minerals	860,000	1,000,000
Brick, Pottery, Glass, and Chemical Works	3,060,000	5,000,000
Gas Works	6,300,000	15,000,000
Domestic Consumption	18,480,000	32,000,000
Coasting Steamers (bunkers)	1,200,000	2,000,000
Home Consumption	94,360,000	167,000,000
Foreign-going Steamers (bunkers)	2,080,000	16,800,000
Exported (Coal, Coke, and Patent Fuel)	10,960,000	47,000,000
Total raised	107,427,557	230,334,469

The totals have been given in exact figures, though for the details the plan followed in the 1904 report, of rounding off the figures, has been partially adopted for the 1869 figures also. The figure of exports in the 1871 report has been replaced by a figure computed, like that for 1903, to include the coal equivalent of coke and patent fuel exported, not coal only. This necessitated an adjustment of the figure for general manufacture, in order not to make the total too great. The amount given as used on steamships in the 1871 report is 3,277,562 tons. For comparison with the later date it seemed better to divide this into that used by foreign-going and by coasting steamers respectively. The former has been computed on the basis of tonnage of steam-vessels cleared, allowing a proportion of bunker coal about 10 per cent greater than that reported in and after 1873. The allowance is, perhaps, somewhat too small. The remainder of the 1871 Commission's allowance for steam-ships is placed under the heading "coastwise." It seems too large relatively, and if an independent estimate had been required would have been considerably less.

It will be observed that, in the estimate for 1869, the domestic consumption, which Jevons originally estimated at one ton per

But the economy of coal in manufactures is a different matter. *It is wholly a confusion of ideas to suppose that the economical use of fuel is equivalent to a diminished consumption. The very contrary is the truth.*

As a rule, new modes of economy will lead to an increase of consumption according to a principle recognised in many parallel instances. The economy of labour effected by the introduction of new machinery throws labourers out of employment for the moment. But such is the increased demand for the cheapened products, that eventually the sphere of employment is greatly widened. Often the very labourers whose labour is saved find their more efficient labour more demanded than before. Seamstresses, for instance, have perhaps in no case been injured, but have often gained wages before unthought of by the use of the sewing-machine, for which we are so much indebted to American inventors.

So it is a familiar rule of finance that the

inhabitant, is allowed for at about 12 cwts. per head of the population, and in that for 1903, at about 15 cwts. per head. The consumption of coal in the iron and steel industries, which was one-third of the entire home consumption in 1869, was only one-sixth of the whole in 1903.

(*Cf. Report of Coal Commission, 1871*: Report of Committee E, p. iv, and pp. 204-5, and *Final Report of Commission on Coal Supplies, 1904*, § 68.)

reduction of taxes and tolls leads to increased gross and sometimes even increased net revenues ; and it is a maxim of trade, that a low rate of profits, with the multiplied business it begets, is more profitable than a small business at a high rate of profit.

Now the same principles apply, with even greater force and distinctness, to the use of such a general agent as coal. It is the very economy of its use which leads to its extensive consumption. It has been so in the past, and it will be so in the future. Nor is it difficult to see how this paradox arises.

The number of tons of coal used in any branch of industry is the product of the number of separate works, and the average number of tons consumed in each. Now, if the quantity of coal used in a blast-furnace, for instance, be diminished in comparison with the yield, the profits of the trade will increase, new capital will be attracted, the price of pig-iron will fall, but the demand for it increase ; and eventually the greater number of furnaces will more than make up for the diminished consumption of each. And if such is not always the result within a single branch, it must be remembered that the progress of any branch of manufacture excites a new activity in most

other branches, and leads indirectly, if not directly, to increased inroads upon our seams of coal.¹

It needs but little reflection to see that the whole of our present vast industrial system, and its consequent consumption of coal, has chiefly arisen from successive measures of economy.

Civilisation, says Baron Liebig, is *the economy of power*, and our power is coal. It is the very economy of the use of coal that makes our industry what it is; and the more we render it efficient and economical, the more will our industry thrive, and our works of civilisation grow.

The steam-engine is the motive power of this country, and its history is a history of successive

¹ The argument that economy of fuel in the blast furnace means increased consumption of coal owing to the increase of demand for iron has been assailed as in conflict with experience. (*Cf.* for example, Mr. Mundella's paper and the discussion on it in the *Statistical Society's Journal* for 1878, a discussion in which Jevons took part.) Apart from the considerations covered by the final phrases of the above paragraph, it may be suggested that the conditions which bring about cheapness may distribute the enlarged demand among widely separated groups of producers. We cannot exclude other nations from the use of efficient processes. This point is one on which Jevons laid no little stress. The world's production of pig-iron increased from about 11,750,000 tons in 1869 to about 46,500,000 tons in 1903 under the influence of cheapness, the consumption of coal in iron and steel manufacture being probably about doubled in the interval. That the increased direct demand for coal did not fall on the coalfields of Great Britain is true, but does not destroy the general force of the argument advanced.

steps of economy. Savery recommended his engine for its cheap drawing of water and small charge of coals. But, as he allowed the steam to act straight upon the water, without the intervention of a piston, the loss of heat was tremendous. Practically, the cost of working kept it from coming into use; *it consumed no coal, because its rate of consumption was too high.*¹ Newcomen made the first step towards the future use of the engine by interposing a piston, rod, beam, and pump between the steam and water. It was asserted that mines formerly drowned out and abandoned might sometimes, *when coal was very cheap*, be profitably drained by his rude atmospheric engine. But when Brindley went to Wolverhampton, to inspect one of these engines, he formed the opinion "that, unless the consumption of coal could be reduced, the extended use of this steam-engine was not practicable, by reason of its dearness, as compared with the power of horses, wind, or air."²

Smeaton, the most philosophical of engineers, after a careful study of the atmospheric engine, succeeded in nearly doubling its efficiency. The engine had long been hanging on the verge of

¹ Farey, *Treatise on the Steam-Engine*, p. 117.

² Smiles' *Engineers*, vol. i, pp. 329, 330.

commercial possibility ; he brought it into successful use, and made it both possible and profitable. But in this branch of his art he willingly gave place to that even greater man, who, after long continued scientific and practical labours, made the steam-engine the agent of civilisation. I need hardly say that Watt's two chief inventions, of the condenser and the expansive mode of working, are simply two modes of economising heat. The double cylinder of Woolf, the method of surface-condensing, of super-heating, etc., are other inventions directed to economy of coal. To save the loss of heat in the boiler, and the loss of power by friction, are two other points of economy, to which numberless inventions are directed. And with the exception of contrivances, such as the crank, the governor, and the minor mechanism of an engine, necessary for regulating, transmitting, or modifying its power, it may be said that *the whole history of the steam-engine is one of economy.*

“ The economy of fuel is the secret of the economy of the steam-engine ; it is the fountain of its power, and the adopted measure of its effects. Whatever, therefore, conduces to increase the efficiency of coal, and to diminish the cost of its use, directly tends to augment the

value of the steam-engine, and to enlarge the field of its operations.”¹

The result of these efforts at economy is clearly exhibited in a table [showing the number of pounds of coal consumed by engines at different periods for each horse-power developed.

COAL CONSUMPTION PER HORSE-POWER PER HOUR²

	Lbs. of Coal
1769	30
1772	17·6
1825	10·0
1850	5·9
1875	2·5
1900	1·0]

In less than one hundred years, then, the efficiency of the engine has been increased at

¹ C. W. Williams, *The Combustion of Coal*, 1841, p. 9.

² For the two earlier dates the figures used are the same as those in Jevons' table given below. For the nineteenth century the figures are from a paper by Mr. W. M. McFarland in the *Engineering Magazine*, 1902, p. 215. "It will be understood," says this writer, "of course, that the figures are simply close approximations, and the years selected are for convenient periods." The results, too, are representative rather of the best practice of each period than of average ordinary experience. In Herman Hæder's *Handbook on the Steam Engine* (translated by H. H. P. Powles, third English edition, 1902, p. 4), the following figures are given :—

	Lbs. of Coal per h.p. per hour
Atmospheric engine. Savery, 1700	31
Low-pressure engine. Watt, 1768	8·8
High-pressure engine. Evans, 1804	6·7
Double-cylinder engine. Woolf, 1804	4·5
Compound engine. Elder, 1850-1891	2·25
Triple expansion engine, 1880-1891	1·76

Jevons gave the following table of "the work or duty, expressed

least tenfold ; and it need hardly be said that it is the cheapness of the power it affords that allows

by the number of pounds of water raised one foot high by the expenditure of a bushel (84 lbs.) of coal.

	Duty in lbs.
1769. Average of old atmospheric engine	5,590,000
1772. Smeaton's atmospheric engine	9,450,000
1776. Watt's improved engine	21,600,000
1779-1788. Watt's engine working expansively	26,600,000
1820. Engine improved by Cornish engineers	28,000,000
1830. Average duty of Cornish engines	43,350,000
1859. Average duty of Cornish engines (per 112 lbs.)	54,000,000
1859. Extreme duty of best engine (per 112 lbs.)	80,000,000"

The table is taken from Taylor's *Record of Mining*, p. 152, etc. The bushel of coal, which meant 84 lbs. in the days of Savery and Smeaton, represented 94 lbs. in *Lean's Monthly* duty records from which figures relating to Cornish engine performances from 1811 are taken. From July, 1856, the records are based on the number of hundredweights of coal consumed (*v.* Henry Davey, *The Principles, Construction and Application of Pumping Machinery*, London, 1900, pp. 17 and 20). The performances of the Cornish engines improved very little between 1830 and 1859. The best average results were obtained in 1843, when duties nearly double those of 1820 were recorded. By 1860 the average had fallen back to the level of 1830, and no recovery is noted between 1860 and 1870. For the purpose of showing the general course of progress of economy of coal used in steam-engines, such a table as that inserted in the text appeared preferable to an attempt to continue that of Jevons to the present date.

Some of the figures in Jevons' table represent average results obtained in practice, some exceptional results of the nature of experiments. Thus, the figure for 1776 represents a performance recorded in a letter of Watt to Smeaton. The working tests gave 18 to 19 in place of 21.6 million lbs. Davey (p. 14), referring to the figure for 1779-88, states that there is no record that so good a result was obtained in practice at that period, and that while the duty of the best engines in 1800 was said to be 20,000,000 lbs., the average duty in 1801 was only about 10,000,000 lbs., or little better than was attained a quarter of a century earlier. Mr. McFarland, in the article quoted above, says that "in ordinary practice simple engines rarely got a horse-power for as

us to draw rivers from our mines, to drive our coal-pits in spite of floods and quicksands, to drain our towns and lowlands, and to supply with water our highest places ; and, finally, to put in motion the great system of our machine labour, which may be said, as far as any comparison is possible, to enable us to do as much as all the inhabitants of the world with their unaided labours could accomplish but a few decades since.

Further improvements of the engine can only have the same result, of extending the use of such a powerful agent. It is usual with a certain

little as 3 lbs. of coal, very few compounds cost less than 2·5, while in ordinary average cruising it is probable the triple expansion engine gets a horse-power for 1·8 to 2·0 lbs. per hour."

A writer in *The Engineer* of June 14th, 1861, refers to "Watt's single-acting engines which, at the time of the expiration of his patent in 1800, burnt 10 lbs. of coal per horse-power per hour. A duty of fifty million foot pounds to 1 cwt. of coal, equal to nearly 4½ pounds of coal per *effective* horse-power per hour, is now a fair average ; whereas there have been engines of the same family which worked, year in and year out, with two pounds of coal for every 198,000 gallons of water lifted one foot."

Dealing with the average rates of coal consumption of all engines in use, Sir W. Armstrong stated in evidence before Committee B of the Coal Commission of 1871 (q. 262) : "As a general average, I should say 8 lbs. would be a fair estimate ; but I think that in ordinary high-pressure engines which are used in manufactories, the expenditure would generally be 10 lbs. per horse-power per hour." The recent Royal Commission on Coal Supplies reported that "it is generally agreed that the consumption of coal per indicated horse-power per hour is on an average about 5 lbs." (*Final Report*, § 70).

class of writers to depreciate science in regard to the steam-engine, and to treat this as a pure creation of practical sagacity. But just as the origin of the steam-engine may be traced to a scientific work, so it is now theory and experiment in their highest and latest developments, which give us a sure notion of the limits of the future improvement of the engine, and through what means it is to be aimed at.

“A well-constructed and properly working ordinary double-acting steam-engine,” wrote Rankine in 1854, “consumes about 4·00 lbs. of bituminous coal per horse-power per hour. A double-acting steam-engine, improved to the utmost probable extent, would use 2·50 lbs. of the same coal”; while “a theoretically perfect engine, working between such limits of temperature as are usual in steam-engines, would require only 1·86 lbs.”¹

But theory further points out, what practice has confirmed, that the work done by an engine for a certain expenditure of fuel is proportional to the difference of the temperatures at which steam enters and leaves the engine.² From this

¹ W. J. M. Rankine on the Air-Engine, *Report of the British Association*, 1854, p. 159.

² The greatest possible fraction of the total heat of combustion of the coal which could be turned into work, if all engine and

principle arises the economy of using high-pressure and super-heated steam; for we have, as it were, all the old force of the low-pressure and less-heated steam, with a great addition from the initial high pressure and the increased store of useful heat in the steam. The economy effected in this manner is wonderful. The very engines which had burned 12 or 14 lbs. of coal per horse-power-hour, when worked with steam at 4, 6, or 8 lbs. pressure, have been found to burn only $3\frac{1}{2}$ or 4 lbs. of coal per horse-power per hour when supplied with stronger boilers, and worked at steam-pressures from 30 to 70 lbs. per square inch.¹

Such simple changes as the shortening of the steam supply, the addition of a second cylinder, the felting of the boiler and steam-vessels, the enlarging of the boiler, the raising of the pressure, or the acceleration of the speed of travelling of an engine, are the simple means by which the self-same engine has often been made to give a manifold result.

boiler losses could be avoided, depends on this difference. Thus, with steam at a pressure of 200 lbs. per square inch, and a condenser temperature of 100° F., only one-third of the total heat generated by the combustion of the fuel could possibly be rendered available as mechanical work. An engine which, under these conditions, gives one-sixth of the total heat in the form of work reaches, therefore, one-half of the greatest possible efficiency. The measure of its perfection is one-half, rather than one-sixth.

¹ James Nasmyth, in Tooke's *History of Prices*, vol. vi, p. 533.

It is true that, as we go on improving, the margin for further improvement becomes narrower, and its attainment more difficult and costly. The improvement of the boiler mainly depends upon the amount of capital expenditure against current expenditure. For the efficiency of a boiler grows with the surface of water we can expose to absorb the heat of the fire; but the more we extend this surface, the less additional economy will an equal extension effect.

Many of the difficulties inherent in the steam-engine are absent in the *air-engine*, which presents a wide prospect of economy, as seen in the following numbers :—

	Actual consumption of Coal per horse-power per hour	Consumption of theoretically perfect engine
Sterling's air-engine	2'20 lbs.	0'73 lbs.
Ericsson's engine of 1852 . . .	2'80	0'82

"Sterling's engine," it is said, "as finally improved, was compact in its dimensions, easily worked, not liable to get out of order, and consumed less oil, and required fewer repairs, than any steam-engine; still, the advantages shown by that engine over steam-engines were not so great as to induce practical men to overcome their natural repugnance to exchange a long-tried method for a new one."¹

¹ W. J. M. Rankine, *British Association*, 1854, p. 159. A double-

[For the convenient production of power on a small scale, internal combustion engines offer many advantages over steam-engines. The economy effected in the utilisation of fuel is not confined to small installations. The losses of heat in the boiler of a steam-engine are avoided, the pressure on the piston being produced, not by expanding steam, but by the products of combustion of a gas or vapour, mixed with a suitable proportion of air, and burnt by explosion in the cylinder itself. When associated with the cheap fuel-gas known as producer gas, which can be obtained by the use of small coal and qualities of coal too poor to give satisfactory results in the furnace of a boiler, these engines afford a very economical, as well as convenient, source of power. The best known makers of such engines in this country "guarantee the effective production of a horse-power for a consumption of $\cdot 875$ to 1 lb. of coal used in the producer, or $\cdot 8$ to $\cdot 9$ lb. per indicated horse-power, according to the

acting Sterling engine of 50 indicated horse-power, used in 1843 at the Dundee foundry, consumed only 117 lbs. of coal per indicated horse-power per hour. In this type of engine, however, the results per indicated horse-power may not be a reliable indication of the requirements per actual horse-power realised (brake horse-power), tested by which standard the economy was far less than appears by the quoted figures (J. A. Ewing, *The Steam Engine and other Heat Engines*, Cambridge, 1899, p. 405).

quality of the coal, the size of the producer, and other conditions.”¹

For engines of small power, gas from some such source as a town gas-supply is needed, but for moderate amounts of power it becomes worth while to set up the plant required to make the producer gas. Extensive as has been the application of the gas-engine during the last two decades of the nineteenth century, its continued improvement in the future, and the provision of a fuel-gas by simple and economical processes, must add largely to the possibilities of its usefulness. Its use in the generation of electricity may enable that convenient form of energy to be applied to numerous purposes now ill-provided for or entirely neglected.]

But every such improvement of the engine, when effected, does but accelerate anew the con-

¹ Statement of Mr. W. J. Crossley, *Second Report of Commission on Coal Supplies*, vol. ii, p. 170. This statement goes further than the passage quoted, for it asserts that the consumption of coal has been got down to '68 lb. of coal per brake horse-power per hour. "To obtain a horse-power indicated in a gas-engine requires about 8,500 British thermal units to be burnt in the engine per hour." Thus 30 per cent. of the energy of the fuel is made available.

Tests, at the St. Louis Exposition in 1904, of various American coals for the manufacture of producer gas gave results as low as 1'03 lbs. of dry coal consumed in the producer per hour for each brake horse-power available for outside purposes (*Engineering Magazine*, May, 1905).

sumption of coal. Every branch of manufacture receives a fresh impulse—hand labour is still further replaced by mechanical labour, and greatly extended works can be undertaken which were not commercially possible by the use of the more costly steam-power.¹

What is true of economy in the engine is true of several other important, and many less important, instances of economy. The extraordinary increase of the iron trade is a trite example.

¹ Jevons enumerated, at this place, three great employments “which would grow beyond conception by a great improvement of the engine.” Of these, the third, steam navigation, that in which he expected “that the improvement will have most marked effects,” has been so fully developed that no further reference to it is needed. The other two were as follows :—“The pumping of liquid sewage out of our great towns, and its distribution over the country, is one mode which would return a clear profit of many millions a year. The steam-plough is a second instance. Its efficiency is beyond question, and the soil is said to be quickened by its irresistible tillage, as a fire is quickened by the poker. But it yet hangs upon the verge of commercial possibility, as did Stephenson’s locomotive engine, when he had got it to draw, but scarcely cheaper than horses. Taking the first and current costs into account, it is yet doubtful whether the steam-plough works as cheaply as the old horse-plough ; but James Watt, to the surprise of his contemporaries, asserted that steam-ploughing was possible ;* and Mr. Fairbairn, at the British Association in 1861, confessed his belief that many of those present would live to see the steam-plough in operation over the length and breadth of the land. Now, an improvement in the engine, reducing the cost of fuel, will turn the balance in favour of coal-power, and its common use in agriculture will be a certainty.”

* *Gentleman's Magazine*, 1819, part 2, p. 632.

"This rapid and great increase, shown in the last few years, has been, in some part, caused by the economy introduced through the use of the hot blast in smelting, a process which has materially lowered the cost of iron, and, therefore, has led to its employment for many purposes in which its use was previously unknown."¹ In fact, as shown in a subsequent chapter,² *the reduction of the consumption of coal, per ton of iron, to less than one-third of its former amount, was followed, in Scotland, by a tenfold total consumption, between the years 1830 and 1863, not to speak of the indirect effect of cheap iron in accelerating other coal-consuming branches of industry.*

Siemens' regenerative furnace is one very good example of economy in iron production. It is somewhat on the principle of the hot blast. The current is passed alternately in opposite directions through two brick chambers, between which lies the furnace. Much of the waste heat, on its way to the chimney, is absorbed by the bricks, and again given out, when the current is reversed, to the cool air on its way to the furnace. Much less fuel is required, in such a furnace, to maintain a given temperature, than if cold air were

¹ Porter's *Progress*, 1851, p. 575.

² Chap. xv.

allowed to flow directly into the fire. The application of such regenerative chambers to furnaces requires the investment of a large amount of capital; and *the question in such improvements, as in the case of the boiler, lies between a large initial investment and large current expenses.*

The utilisation of spare heat from a puddling or reheating furnace, by passing it through a steam-boiler; the saving of the waste gases of a blast-furnace, to heat the blast, or work the engines;¹ the employment of spare heat in salt pans; the use of small gas flames, or gas furnaces, where large coal fires were before used: such are a few of the very many modes in which coal may be greatly saved. In fact, there is hardly a single use of fuel in which a little care, ingenuity, or expenditure of capital may not make a considerable saving.

But no one must suppose that coal thus saved is spared—it is only saved from one use to be employed in others, and the profits gained soon lead to extended employment in many new forms.

¹ The following illustrates the importance of attention to this point of economy. "Wherever there is a demand for power, and cheap water power is not available, and blast furnaces are, the blast-furnace gas-engine power plant need fear no rival" (F. du P. Thomson, in *Engineering Magazine*, 1905, p. 260). These words, of course, contemplate a utilisation of the waste gases by other methods than those which Jevons had in mind.

The several branches of industry are closely interdependent, and the progress of any one leads to the progress of nearly all.

And if economy in the past has been the main source of our progress and growing consumption of coal, the same effect will follow from the same cause in the future. Economy multiplies the value and efficiency of our chief material ; it indefinitely increases our wealth and means of subsistence, and leads to an extension of our population, works, and commerce, which is gratifying in the present, but must lead to an earlier end. Economical inventions are what I should look forward to as likely to continue our rate of increasing consumption. Could we keep them to ourselves, indeed, they would enable us, for a time, to neutralise the evils of dearness when coal begins to get scarce, to keep up our accustomed efficiency, and push down our coal-shafts as before. But the end would only thus be hastened—the exhaustion of our seams more rapidly carried out.

Let us remember that we are dependent on the *comparative cheapness of fuel and motive power*. Now, comparative cheapness of fuel cannot be procured or retained by inventions and modes of economy which are as open to our commercial

competitors as to ourselves, which have in many cases been introduced by them, and are more readily adopted by versatile foreigners than by English manufacturers bound by custom and routine. Even our superior capital will not avail us against dear fuel, because nothing more readily flows abroad in search of profitable employment than capital. And if we are to uphold a world-wide freedom of intercourse, let us not deceive ourselves as to its natural results upon the material basis of our prosperity.

CHAPTER VIII

OF SUPPOSED SUBSTITUTES FOR COAL

A NOTION is very prevalent that in the continuous progress of science some substitute for coal will be found—some source of motive power as far surpassing steam as steam surpasses animal labour.

The popular scientific writer, Dr. Lardner, in the following passage of his *Treatise on the Steam Engine*, contributed to spread such notions—in him, as a scientific man, inexcusable.¹ “The enormous consumption of coals produced by the application of the steam-engine in the arts and manufactures, as well as to railways and navigation, has of late years excited the fears of many as to the possibility of the exhaustion of our coal-mines. Such apprehensions are, however, altogether groundless. If the present consumption of coal be estimated at sixteen millions of

¹ Lardner, *The Steam Engine explained and illustrated*, etc., 7th ed. 1840, p. 8.

tons annually, it is demonstrable that the coal-fields of this country would not be exhausted for many centuries.

“But in speculations like these, the probable, if not certain progress of improvement and discovery ought not to be overlooked; and we may safely pronounce that, long before such a period of time shall have rolled away, other and more powerful mechanical agents will supersede the use of coal. Philosophy already directs her finger at sources of inexhaustible power in the phenomena of electricity and magnetism. The alternate decomposition and recombination of water, by magnetism and electricity, has too close an analogy to the alternate processes of vapourisation and condensation, not to occur at once to every mind; the development of the gases from solid matter by the operation of the chemical affinities, and their subsequent condensation into the liquid form, has already been essayed as a source of power. In a word, the general state of physical science at the present moment, the vigour, activity, and sagacity with which researches in it are prosecuted in every civilised country, the increasing consideration in which scientific men are held, and the personal honours and rewards which begin to be conferred

upon them, all justify the expectation that we are on the eve of mechanical discoveries still greater than any which have yet appeared; and that the steam-engine itself, with the gigantic powers conferred upon it by the immortal Watt, will dwindle into insignificance in comparison with the energies of nature which are still to be revealed; and that the day will come when that machine, which is now extending the blessings of civilisation to the most remote skirts of the globe, will cease to have existence except in the page of history."

Such high-sounding phrases would mislead no scientific man at the present day;¹ but there is a large class of persons whose vague notions of the powers of nature lay them open to the adoption of paradoxical suggestions. The fallacious notions afloat on the subject of electricity especially are unconquerable. Electricity, in short, is to the present age what the perpetual motion was to an age not far removed. People are so astonished at the subtle manifestations of electric power, that they think the more miraculous effects they anticipate from it the more profound the appre-

¹ A pencilled marginal note at this point in the copy which Jevons was preparing for a new edition runs as follows :—"They are worthy only of a savant who proved that a steam-vessel could not cross the Atlantic."

ciation of its nature they show. But then they generally take that one step too much which the contrivers of the perpetual motion took—they treat electricity not only as a marvellous mode of distributing power, they treat it as a source of self-creating power.

The great advances which have been achieved in the mechanical theory of nature, in the course of the nineteenth century, have greatly cleared up our notions of force and energy. It has been rendered apparent that the universe, from a material point of view, is one great manifestation of a *constant aggregate of energy*. The motion of falling bodies, the motions of magnetic or electric attractions, the unseen agitation of heat, the vibration of light, the molecular changes of chemical action, and even the mysterious life-motions of plants and animals, all are but the several modes of greater or lesser motion.

These views lead us at once to look upon all machines and processes of manufacture as but the more or less efficient modes of transmuting and using energy. If we have energy in any one of its forms, as heat, light, chemical change, or mechanical motion, we can turn it, or may fairly hope to turn it, into any other of its forms. But to think of getting energy except from some

natural source is as absurd as to think of making iron or gold out of vacant space.

We must look abroad then to compare the known sources of energy. Some distinct sources are of inconsiderable importance, such as the fall of meteoric stones, the fall of rocks, or the heat derivable from sulphur and other native combustible substances. The internal heat of the earth, again, presents an immense store of energy, but being powerfully manifested only in the hot-spring or the volcano, it is not available to us.

The tides arising from the attractions of the sun, earth, and moon, present another source of power, which is, and often has been, used in one way or another, and shall be considered.

The remaining natural sources of energy are the complicated light, heat, chemical and magnetic influences of the sun's rays. The light, or chemical action, is the origin of organic fuel, in all its forms of wood, peat, bitumen, coal, etc.; while the heat occasions the motions of the winds and falling waters. The electricity of the air and the thunderstorm, and the electric currents of the earth, are probably secondary effects of the other influences. *Among these several manifestations of energy, our choice must, in all reasonable probability, be made.*

Now it will be easily seen that the resources of nature are almost unbounded, but that economy consists in discovering and picking out those almost infinitesimal portions which best serve our purpose. We disregard the abundant vegetation, and live upon the small grain of corn; we burn down the largest tree, that we may use its ashes; or we wash away ten thousand parts of rock, and sand, and gravel, that we may extract the particle of gold. Millions, too, live, and work, and die, in the accustomed grooves for the one Lee, or Savery, or Crompton, or Watt, who uses his minute personal contribution of labour to the best effect.

So material nature presents to us the aspect of one continuous waste of energy and matter beyond our control. The power we employ in the greatest engine is but an infinitesimal portion withdrawn from the immeasurable store of natural forces.¹ But *civilisation*, as Liebig said, *is the economy of power*, and consists in withdrawing and using our small fraction of energy in a happy mode and moment.

The rude forces of nature are too great for us,

¹ See *Economy of Manufactures*, § 17, *et passim*. In this exquisite work Mr. Babbage anticipates the modern doctrines of the relations of the natural forces.

as well as too slight. It is often all we can do to escape injury from them, instead of making them obey us. And while the sun annually showers down upon us about a thousand times as much heat-power as is contained in all the coal we raise annually; yet that thousandth part, being under perfect control, is a sufficient basis of all our economy and progress.

The first great requisite of motive power is, that *it shall be wholly at our command, to be exerted when and where and in what degree we desire*. The wind, for instance, as a direct motive power, is wholly inapplicable to a system of machine labour, for during a calm season the whole business of the country would be thrown out of gear. Before the era of steam-engines, windmills were tried for draining mines; "but though they were powerful machines, they were very irregular, so that in a long tract of calm weather the mines were drowned, and all the workmen thrown idle. From this cause, the contingent expenses of these machines were very great; besides, they were only applicable in open and elevated situations."

No possible concentration of windmills, again, would supply the power required in large factories or iron works. An ordinary windmill has the

power of about thirty-four men,¹ or at most, seven horses. Many ordinary factories would therefore require ten windmills to drive them; and the great Dowlais Ironworks, employing a total engine power of 7,308 horses,² would require no less than 1,000 large windmills!

In navigation the power of the wind is more applicable, as it is seldom wanting in the open sea, and in long voyages the chances are that the favourable will compensate the unfavourable winds. But in shorter voyages the uncertainty and delay of sailing vessels used to be intolerable. It is not a hundred years since passengers for Ireland or for the Continent had sometimes to wait for weeks until a contrary wind had blown itself out. Such uncertain delays dislocate business, and prevent it from proceeding in the rapid and machine-like manner which is necessary for economy. Hence the gradual substitution of steam for sailing vessels. In the steam boiler, indeed, we have the veritable bag of Æolus; and thus, though steam is a most costly power, it

¹ *Life of Telford*, Telford's Memorandum Book, p. 671. The increase of the power of windmills so as to develop as much as 60 horse-power from a single mill (cf. *Final Report of Commission on Coal Supplies*, 1905, q. 23651) has been more than matched by the increase of power needed in modern factories and works. The comparisons of the text have not, therefore, lost their force.

² Truran on the *Iron Manufacture of Great Britain*, p. 242.

is certain, and our sea captains have come to regard wind as a noxious disturbing influence. In a well-established and connected system of communications, there is little or no use, and often a good deal of harm, in reaching a place before the appointed time. Thus on a steamship little or no use is made of sails even when the wind is favourable and strong, and it cannot be said that there is any benefit to be derived from them equivalent to their trouble and cost. *It is certainty that is the highest benefit of steam communication.*

The regularity and rapidity of a steam vessel render it an economical mode of conveyance even for a heavy freight like coal. The first cost of a steam collier is greater than for sailing colliers of equal tonnage. But then capital invested in the steam vessel is many times as efficient as in the sailing vessel. A steam collier can receive her cargo of 1,200 tons at Newcastle in four hours, reach London in thirty-two hours, discharge by steam hydraulic machinery in ten hours, and return to Newcastle with water ballast within seventy-six hours for the round voyage. A single collier has been known to make fifty-seven voyages to London in one year, delivering 62,842 tons of coal with a crew of twenty-

one persons. To accomplish the same work with sailing colliers would require sixteen vessels and 144 hands.¹

The same necessity for regularity may be still more clearly seen in land conveyance. A *wind-waggon* would undoubtedly be the cheapest kind of conveyance if it would always go the right way. Simon Stevin invented such a carriage, which carried twenty-eight persons, and is said to have gone seven leagues an hour.² Sailing coal-waggons were tried by Sir Humphrey Mackworth at Neath about the end of the seventeenth century, and Waller eulogises these "new sailing waggons for the cheap carriage of his coal to the waterside, whereby one horse does the work of ten at all times ; but when any wind is stirring (which is seldom wanting near the sea), one man and a small sail do the work of twenty."³

Nearly a century later Richard Lovell Edgeworth spent forty years' labour in trying to bring wind carriages into use. But no ingenuity could prevent them from being uncertain : and their rapidity with a strong breeze was such, that, as was said of Stevin's carriage, "they seemed to

¹ C. M. Palmer, *Report of the British Association*, 1863, p. 697.

² See a curious account in the British Museum, under the name Stevin, 1652.

³ Smiles' *Engineers*, vol. iii, p. 73.

fly, rather than roll along the ground." Such rapidity not under full control must be in the highest degree dangerous.

"Nothing could at first sight have seemed more improbable than the success of the steam locomotive over the atmospheric locomotive. The power of the air, which was absolutely gratuitous, was proved to be capable of impelling railway carriages as effectually as the power of steam, generated by coals which were procured at a great cost, and were brought from a considerable distance. But the conditions under which the force of the atmosphere could be applied were so onerous that the invention ceased to present the character of an aid, and its use has consequently been discontinued."¹

It is the characteristic of certainty which led Brindley strongly to prefer canals to improved river navigations. Rivers he regarded as only fit to feed canals, and as being themselves subject to floods and droughts, he characterised them "as out of the power of art to remedy."² Many of

¹ *Plutology; or, the Theory of Efforts to satisfy Human Wants*, by W. E. Hearn, LL.D., Professor of Political Economy in the University of Melbourne, 1864, p. 199. This work appears to me both in soundness and originality the most advanced treatise on political economy which has appeared, and it should be familiar to every student of the science.

² Smiles' *Engineers*, vol. i, p. 458.

Brindley's finest engineering works on the Bridgewater Canal were directed to warding off the interference of river floods.¹ Yet even his great canal was subject to be frozen up in winter and to be let dry for repairs in summer, and we could not tolerate the inconvenience and loss which a stoppage of traffic would now occasion in our large and nicely-jointed system of trade.

Uncertainty will for ever render aërial conveyance a commercial impossibility. A balloon or aërial machine does not enjoy like a ship the reaction of a second medium. It is subject to the full influence of the wind. Thus, even if an aërial machine could be propelled by some internal power from fifty to a hundred miles an hour, it could not make head against a gale. To say nothing of the facts that balloon travelling must be dangerous, that it is really dependent on the use of fuel, and cannot, as far as we can yet see, ever be rendered practicable or cheap, *it is, beyond all this, subject to natural uncertainty necessarily precluding its general use.*

Atmospheric or terrestrial electricity has, no doubt, suggested itself to some as a source of

¹ As a later example, it may be noted that, in the plans for the construction of the Panama Canal, one of the greatest engineering difficulties is presented by the floods of the river Chagres.

power. The thunder-cloud, the aurora borealis, and the earth-current of the telegraphic wire, are natural manifestations of electric power, which might possibly be utilised. But such secondary forces are altogether inconsiderable in amount, compared with the forces of heat and wind, from which they doubtless arise. In fact, they are scarcely sensible, except during thunder, auroral or magnetic storms, when they become destructive, and interrupt our telegraphic communications. We should no more think of waiting for a magnetic storm to move our engines, than Brindley would have thought of waiting for a mountain torrent to float his canal boats. The first essential of a motive force is constancy; natural electricity, on the contrary, possesses all the characteristics of uncertainty and extreme irregularity, which are most opposed to utility.

We meet, however, a constant and manageable source of energy in water power. The water-wheel, or the turbine, possesses a natural tendency to uniformity of motion, even more perfect than that bestowed on the engine by Watt's "governor." Water power is, in this respect, the best motive power, and is sometimes used on this account, where a very delicate machine re-

quires to be driven at a perfectly constant rate. When an abundant natural fall of water is at hand, nothing can be cheaper or better than water power. But everything depends upon local circumstances. The occasional mountain torrent is simply destructive. Many streams and rivers only contain sufficient water half the year round, and costly reservoirs alone could keep up the summer supply. In flat countries no engineering art could procure any considerable supply of natural water power, and in very few places do we find water power free from occasional failure by drought.¹

The necessity, again, of carrying the work to the power, not the power to the work, is a disadvantage in water power, and wholly prevents that concentration of works in one neighbourhood which is highly advantageous to the perfection of our mechanical system. The cost of conveying raw materials and products to and from the mill often overbalances the cheapness of water power, with the possibility, too, of an occa-

¹ Professor G. Forbes has estimated that "if all the available water power in the United Kingdom were made use of . . . the total probable practical saving in coal . . . would be 1,200,000 tons per annum," with possible underestimate not "likely to amount to 500,000 tons per annum" (*Final Report of Royal Commission on Coal Supplies*, part x, p. 265).

sional scarcity of water during drought. [Though the power from large concentrated water powers can be transmitted for long distances electrically, this consideration is not applicable to the greater part of the water powers of the British Isles.]

It is usually possible, with more or less labour, to procure water power artificially, to store it up, and convey and expend it where we like. Those who are acquainted with Sir W. Armstrong's beautiful apparatus for working cranes, dock-gates, and performing other occasional services, will probably allow that the most perfect conceivable system of machine labour might be founded on hydraulic power. Imagine an indefinite number of windmills, tidal mills, and water-mills employed to pump water into a few immense reservoirs near our factory towns. Water power might thence be distributed and sold, as water is now sold for domestic purposes. Not only all large machines, but every crane, every lathe, every tool might be worked by water from a supply pipe, and in our houses a multitude of domestic operations, such as ventilation, washing, the turning of the spit, might be facilitated by water power.

The first suggestion of a system of storing and distributing power seems to be due to Denis

Papin, the French refugee engineer, the same who suggested the use of the steam-engine piston.¹ In the *Transactions of the Royal Society* for the year 1687² he described a method of *prolonging the action of water-wheels by drawing and forcing air through tubes*, which seems to involve the principle of the boring machines of the Mont Cenis tunnel, the compressed air coal-cutting machine, and pneumatic and hydraulic apparatus generally. And it was Bramah, a second French engineer, domiciled here, who first showed in practice the wonderful capabilities of hydraulic power. And so controllable, safe, clean, and irresistible is hydrostatic pressure, either of air or water, that, now our mechanical skill in construction is sufficiently advanced, it must come more and more into use. We might almost anticipate from its wide adoption a perfect Utopian system of machine labour, in which human labour would be restricted to the simple direction of the hydraulic pressure.

But before indulging in imaginary approximations to perfection, it is well to inquire into the several conditions of possibility. To the capabilities of hydrostatic pressure there is perhaps physically speaking scarcely a limit, but com-

¹ See p. 118.

² No. 186, p. 263, Jan. 1687.

mercially speaking our command of water power, or hydrostatic power, in whatever form, is nearly limited to our command of steam. It is steam that presents us with hydrostatic power in its most abundant and available form. Water power in uniform abundance is to be had, in this country at least, only through steam ; and *all experience points to the fact that, instead of water being a possible commercial substitute for steam, it is steam that from its first use has been a substitute for water power.*

A brief consideration of the history of the steam-engine will put this fact in the clearest light. Though water power had been in use since the time of the Romans, a great want was clearly felt in the seventeenth century of some new power, antithetical to water power, so to speak, and capable of overcoming it, so that drowned mines might be pumped dry, and water might be raised to furnish artificial water power, where a natural supply was not to be had. The earliest explicit patent for a new engine was directed to the raising of water,¹ and the "Exact and True Definition" of the Marquis of Worcester's engine clearly expressed a similar purpose.

¹ See the patent of 1631, in Rymer's *Fœdera*.

“There being indeed no place but either wanteth water, or is overburdened therewith . . . by this engine either defect is remediable.” Hence the Marquis calls his invention a “stupendous water commanding engine,” and truly regarded it as a new *primum mobile* which was to overcome the force of falling water.

His appreciation of the value of water power is shown by his remarkable motto :¹—

“Whosoever is master of weight is master of force,
Whosoever is master of water is master of both.”

“And consequently,” said he, “to him all forcible actions and achievements are easy, which are in any wise beneficial to, or for, mankind.”

Savery had no less correct and exalted notions of what his engine might accomplish by simply overcoming the gravity of water. It generated an universal motive power ; for he said, “I have only this to urge, that water in its fall from any determinate height, has simply a force answerable to, and equal to the force that raises it”;² and he hints at “what may yet be brought to work by a steady stream and the rotation, or

¹ *Harleian Miscellany*, vol. iv, p. 526.

² *Miner's Friend*, pp. 28, 29.

circular motion of a water-wheel," and "what use this engine may be put to in working of mills, especially where coals are cheap."

Now during the greater part of the eighteenth century the steam-engine did perform the duty alluded to; it did pump up water and furnish artificial water power for turning mills and winding coals from mines. At the Coalbrookdale Iron Works it accomplished an inestimable service by enabling Darby to maintain and increase the blast of his new coal furnaces, an atmospheric engine being used *to return the water from the lower to the higher mill-pond*.¹

Had not the introduction of the crank, fly-wheel, and governor by Watt, enabled us to communicate equable circular motion directly from a steam-engine to a machine, the water-wheel supplied with water by an engine would to this day be the source of motive power. As it is, of course steam power used directly is cheaper than steam power used indirectly. Water power is now only used where a natural fall is easily available. Such falls had in general become monopolised property from time immemorial, and naturally became the seats of factory labour, a century or more ago. But

¹ See chap. xv.

it was the steam-engine which alone could allow the growth of our factory system.¹ The water-wheel, moreover, has, by the continued exertions of our great engineers, from Smeaton down to Fairbairn, been carried near its mathematical maximum of efficiency, whereas the engine yet gives us only a fraction of the power it may be made to give. The improvement of the steam-engine has, in fact, caused it to be substituted successively in many mills before worked by water.

The predominance of steam over water is seen in many other instances. It is a steam-engine that is used to supply water power for Sir W. Armstrong's apparatus, as at the Liverpool and Birkenhead Docks. Again, it is only the steam-engine that can supply water for the manufacturing and domestic uses of our great towns like Wolverhampton and London. Our factories, print-works, sugar refineries, breweries, and other

¹ The increase of the use of steam power in textile factories in the United Kingdom is shown in the following official figures :—

Motive Horse Power

	Water	Steam	Total
1850	26,104	108,113	134,217
1856	23,724	137,713	161,437
1861	29,359	375,311	404,670
1868	29,830	337,851	367,681
1870	27,321	478,434	505,755

(*Miscellaneous Statistics of the United Kingdom*, part viii, p. 370.)

works, find it a matter of immense cost and difficulty to get a plentiful supply of water from wells and pumping engines, or from natural sources. And if we can hardly supply our boilers with water, how can we dream of ever using water, instead of steam, in the cylinder, and as the motive power?¹

The predominance of steam is further seen in its actual substitution for the windmill, or the tidal mill. Wind-cornmills still go on working until they are burnt down, or out of repair; they are then never rebuilt, but their work is transferred to steam-mills. Yet the grinding of corn is a work most suitable to the variable power of the wind. Again, if there is anything which could be cheaply done by wind, it is the raising of large masses of water where occasional irregularities are of no consequence, the rain and wind mostly coming together. Yet the windmills long employed to drain the Lincolnshire Fens, as practised in Holland, were at last superseded by powerful steam-engines, on the recommendation of Mr. Rennie.² Tidal mills are no novelty. One

¹ The use of water for minor purposes is not in conflict with the position taken in the text. Other considerations than the direct cost may influence the question, but for developing power on a large scale, steam retains its supremacy.

² Smiles' *Engineers*, vol. i, p. 67.

is mentioned in the first page and column of the *Domesday Book* as existing at Dover. A tidal pump was long moved by the current under Old London Bridge, and supplied the City with water. A tidal corn-mill, too, of very ingenious construction, subsequently existed at Woolwich.¹ Sir Robert Kane, in his *Industrial Resources of Ireland*,² supposed tidal mills to be capable of supplying motive power to Ireland.

The application of the tides to machine labour is rendered difficult on account of their variation from day to day. To gain a constant head of water always available we must either construct elaborate and costly high and low tide basins, or else we must use the variable tidal wheel to pump up water into a great reservoir. The estuary of the Dee is one of the places best adapted to give a vast tidal power, and an anonymous but apparently able engineer has calculated what power might be utilised there.³ He considered that the equivalent steam power might be had at a capital cost of £4,000,000, a sum wholly insufficient to provide the tidal works. Hence he concluded that the tidal scheme would be at least commercially impracticable, and he doubted

¹ Barlow's *Cyclopædia*.

² First edition, p. 105.

³ See the journal *Engineering*, 30th March, 1866, p. 195.

whether it would be at all possible, mechanically speaking, to construct embankments and tidal basins on loose sands.

And whatever schemes of this sort be proposed, we should remember that the tendency of tidal docks and reservoirs to silt up is an insuperable objection in cost. Engineers, from the time of Brindley, have constantly found that there is nothing more nearly beyond the remedy of art than the silting up of harbours, docks, and reservoirs. Constant dredging is necessary to maintain the access to the Liverpool and Birkenhead Docks, and a tidal mill and reservoir constructed on the north side of the Mersey about a century ago was soon abandoned for a similar reason.

It will, therefore, appear obvious that *if we are to have a water-power millennium of machine labour, which is physically possible, it must yet be by using steam as the ultimate source of power.*

To go on to other suggestions, we may notice the opinion that the electro-magnetic engine will some day supersede the steam-engine. Such an engine, however, must be worked by an electro-positive metallic element as the source of power. Now it is coal or fuel only by which we can smelt

ores and obtain the metal required for the engine, and it is demonstrable that we should get far more power by using coal directly under a steam-engine boiler than by using it to smelt metals for an electro-magnetic engine. After the exposure of the claims of such an engine by Baron Liebig,¹ I need not dwell upon it. The predominance of steam, too, is shown most clearly in the fact that the steam-engine is used conversely to turn dynamo-electric machines, and supply electricity for lighting and for power. And while mechanical energy is found to be the cheapest source of electricity, it is impossible that electricity should be the cheapest source of mechanical energy. [The improvement of the dynamo-electric machine, and its more and more extensive use, have been prominent features of recent advance in the application of science to industry. So much is this the case that our age is often designated the age of electricity, and there is no doubt that the future will witness a far more general use of electric energy than has yet taken place.] The dynamo is, indeed, in an eminent degree a convenient device for applying or concentrating force, but the force must ultimately be furnished by coal.

¹ *Letters on Chemistry*, No. 12.

Hitherto we have considered mechanical power only, but it is obvious that if coal were used up we should want some source of heat as well as of power. A favourite notion at one time was to employ wind, water, or tidal mills to turn magneto-electric machines, and by the current of electricity produced to decompose water, thus furnishing a continuous supply of artificial gaseous fuel. Such a plan was proposed in *The Times* during the discussion on the French Treaty. But an answer, attributed to Dr. Percy, of the School of Mines, soon appeared, showing the amount of fuel derivable to be inconsiderable. The waste of power must be vastly greater in such a process of transmutation than in the system of artificial water power which we have considered. Besides, if uniform experience is to be trusted, a steam-engine would be a much more economical means of turning the magneto-electric machines than either a wind, water, or tidal machine. We should therefore only use coal in a roundabout manner to generate a less valuable fuel. For the hydrogen gas generated, though in some instances valuable, would in general be immensely less convenient than coal. For equal weights, it gives about four times as much heat as coal, but hydrogen is so light that

for equal volumes it gives one five-thousandth part as much heat. To compress it in a small space would require more power than the combustion of the fuel itself would furnish, and gas companies do not find it convenient to compress their gas. Hydrogen, too, has so much higher a diffusive power than coal-gas, that it could hardly be retained in gasometers or ordinary pipes. Even the loss of coal-gas by leakage is said to be nearly twenty-five per cent.

Of course it is useless to think of substituting any other kind of fuel for coal. We cannot revert to timber fuel, for "nearly the entire surface of our island would be required to grow timber sufficient for the consumption of the iron manufacture alone."¹ And I have independently calculated, from the known produce of continental forests,² and the comparative heat-producing values of timber and coal,³ that forests of an extent two and a half times exceeding the whole area of the United Kingdom would be required to furnish even a theoretical equivalent for each hundred million tons of coal annually produced. Practically, however, there are incon-

¹ Taylor's *Archæology of the Coal Trade*, p. 176.

² Percy's *Metallurgy*, vol. i, pp. 71, 72.

³ Watt's *Chemical Dictionary*, Article *Fuel*.

veniences about the use of timber that would altogether prevent it from nourishing a large manufacturing system. Wood fuel is superior to coal in the single case of the iron smelting furnace ; but in most other uses, the greater bulk of wood, and the large areas of forest land over which it is spread, necessarily render it a costly and inefficient fuel compared with coal.

Peat, or turf, again, may no doubt be turned into fuel ; but, in spite of what has been said in its favour by Sir R. Kane,¹ all experience shows that it is inferior as regards cost and efficiency to coal. [As a substitute for coal in England, it could not be profitably employed at any considerable distance from the place of manufacture, until the time arrives when, with progressive exhaustion of our coal beds, coal has become a comparatively expensive source of power.]

Petroleum has, of late years, become the matter of a most extensive trade, and has been found admirably adapted for use in marine steam-engine boilers. It is undoubtedly superior to coal for many purposes, and is capable of replacing it. But then, *What is Petroleum but the Essence of Coal*, distilled from it by terrestrial or artificial heat ? Its natural supply is far more limited and

¹ *Industrial Resources of Ireland*, 1st ed., chap. ii.

uncertain than that of coal, and an artificial supply can only be had by the distillation of some kind of coal at considerable cost. To extend the use of petroleum, then, is only a new way of pushing the consumption of coal.¹ It is more likely to be an aggravation of the drain than a remedy.

Coal has all those characteristics which entitle it to be considered the best natural source of motive power. It is like a spring, wound up

¹ This is certainly true for countries not possessing natural springs or wells of petroleum. To the extent to which this country relies on imported supplies of fuel oils, it ceases to occupy the position of advantage, relative to other industrial countries, conferred by its extensive deposits of excellent and accessible coal.

The total of the world's production of petroleum in 1901 was stated by Dr. Boverton Redwood to be 22,000,000 tons (*Final Report of Commission on Coal Supplies*, § 94). The *Petroleum Review*, in May, 1905, gave the world's production of the preceding year as 28,577,900 tons. Accepting the fuel value of petroleum as fifty per cent greater than that of an equal weight of coal, this output would be able to replace barely 43,000,000 tons of coal, or, say five per cent of the world's coal production.

It might be considered necessary to add, to the enumeration of possible substitutes for coal, natural gas, especially in view of the discoveries near Heathfield in Sussex. The following remark of the general manager of the Pennsylvania Steel Company, in reference to the natural gas supply of the United States, seems to render it unnecessary to devote space to the possibility of replacing British coal by natural gas in any but a very slight degree.

"Of late years the supply of gas has been decreasing, and the demand has been met by the constant drilling of new wells in new territory. There is a limit to this method, and it would seem that before many years this fuel would cease to be a factor in the larger operations of a steel works." *The Manufacture and Properties of Iron and Steel*, by H. H. Campbell, 2nd edition, 1904, New York, p. 246.

during geological ages for us to let down. Just as in alluvial deposits of gold-dust we enjoy the labour of the natural forces which for ages were breaking down the quartz veins and washing out the gold ready for us, so in our seams of coal we have peculiar stores of energy collected from the sunbeams for us. Coal contains light and heat bottled up in the earth, as Stephenson said, for tens of thousands of years, and now again brought forth and made to work for human purposes.

The amount of power contained in coal is almost incredible. In burning a single pound of coal there is developed energy equivalent to that of 10,422,000 pounds weight falling one foot, and the actual useful work got from each pound of coal in a good steam-engine is that of 1,000,000 lbs. falling through a foot¹; that is to say, there is *spring* enough in coal to raise a million times its own weight a foot high. Or again, suppose a farmer to despatch a horse and cart to bring a ton of coals to work a portable engine, occupying four hours on the way. The power brought in the coal is 2,800 times the power expended in bringing it, and the amount of useful work

¹ This result would be given by an engine using about 2 lbs. of coal per horse-power per hour. The best engines of to-day could give twice as much.

actually got from it will probably exceed by 100 times or more that of the horse as employed in the cart. In coal we pre-eminently have, as the partner of Watt said, "what all the world wants—POWER. All things considered, it is not reasonable to suppose or expect that the power of coal will ever be superseded by anything better. It is the naturally best source of power, as air and water and gold and iron are, each for its own purposes, the most useful of substances, and such as will never be superseded.

Of course I do not deny that if our coal were gone, or nearly so, and of high price, we might find wind, water, or tidal mills, a profitable substitute for coal. But this would only be on the principle that half a loaf is better than no bread. It would not enable us to keep up our old efficiency, nor to compete with nations enjoying yet undiminished stores of fuel. And there is little doubt, too, that a century hence the average efficiency of steam-engines will be much greater than at present, turning the balance of economy so far the more in favour of those who then possess coal, and against those who have to resort to water or wind.

This is a point which I must insist upon as finally decisive of the question. *The progress of*

science, and the improvement in the arts, will tend to increase the supremacy of steam and coal. Any mechanist knows that the water-wheel and the windmill have been brought, by the exertion of our engineers, Brindley, Smeaton, Rennie, Telford, and Fairbairn, near to their mathematical limit of efficiency ; so that we can do little more than improve the mechanical construction, and gain some small percentage of additional power by reducing the friction of the machinery. The steam-engine, on the other hand, at least equally admits of improvement in mechanical details ; but beyond this, in the principles of heat and vapour, we see clearly the possibility of further increase in the efficiency of fuel. If there is anything certain in the progress of the arts and sciences, it is that this gain of power will be achieved. In short, the general course of science and improvement will only lead us the more to regret the limited extent of our coal resources.

But let us further remember that coal is now a pre-eminent gift in our actual possession, whereas if any wholly new source of power be some day discovered, we have no reason to suppose that our island will be as pre-eminently endowed with it as with coal.

Mr. Babbage has applied his rare genius to this question, and what he has once said is incapable of improvement. Passing over the period which this work considers, when coal will be scarce here and plentiful elsewhere, he has thrown his thoughts forward to the time when coal will be scarce everywhere. Heat, he thinks, may then be got from the hot springs of Ischia. "In Iceland," he continues,¹ "the sources of heat are still more plentiful; and their proximity to large masses of ice seems almost to point out the future destiny of that island. . . . In a future age *power* may become the staple commodity of the Icelanders."²

Power is at present our staple commodity, and

¹ *Economy of Manufactures*, 3rd ed. 1833, § 465.

² The ultimate exhaustion of the coal supplies of the world has been discussed by Lord Kelvin, who pointed out that the fuel would last as long as the air, without which it cannot be burned. He estimated that "there is not more than 340 million million tons of fuel on the earth." The 146 thousand million tons of coal estimated by the Argyll Commission as existing within 4,000 feet of depth in the United Kingdom "is approximately six-tenths of a ton per square metre of area of Great Britain. To burn it all would take one and eight-tenths of a ton of oxygen [per square metre], or within two-tenths of a ton of the whole oxygen of the atmosphere resting on Great Britain." Adding the estimated resources below 4,000 feet, "It may be considered as almost quite certain that Great Britain could not burn all its own coal with its own air," and the conclusion is that Great Britain is considerably more richly endowed with coal, in proportion to its area, than the rest of the world (British Association for the Advancement of Science, *Report* 1897, pp. 553-4).

Mr. Babbage clearly saw, more than seventy years ago, that with our coal *power* must pass from us.

Among the residual possibilities of unforeseen events, it is just possible that some day the sun-beams may be collected,¹ or that some source of energy now unknown may be detected. But such a discovery would simply destroy our peculiar industrial supremacy. The study of electricity has already been zealously cultivated on the Continent with this view—"England," it is said, "is to lose her superiority as a manufacturing country, inasmuch as her vast store of coals will no longer avail her as an economical source of motive power."² And while foreigners clearly see that the peculiar material energy of England depends on coal, we must not dwell in such a fool's paradise as to imagine we can do without coal what we do with it.

¹ As in the sun-engine reported to be operating successfully in California, in which an apparatus of mirrors concentrates the heat of the sun on a vessel which serves as a boiler.

It is obvious that such an appliance is not adapted for extensive use in Great Britain, whether or not it can be made effective in more favourable climates.

² Liebig's *Letters on Chemistry*, No. 12, p. 154.

CHAPTER IX

OF THE NATURAL LAW OF SOCIAL GROWTH

BEFORE proceeding with the discussion of this question we must understand clearly what we mean by the progress of a country. We must ascertain how that progress is to be measured, and when it may be called *uniform*.

Suppose it to be stated that in a certain country during one year the consumption of coal has increased by one million tons. The statement is almost useless. We learn from it that the country is progressing rather than going backwards, but this is all. We do not learn the rate at which it is progressing. If the previous consumption were only one million tons in a year, the increase would be enormous, for it would consist in doubling the consumption. With a previous consumption of ten million tons, the increase, being ten per cent, might still be called great. But on

the present consumption of England, amounting to 167 million tons, an increase of one million is not great, being only a fraction of one per cent.

Again, the population of England and Wales increased between 1811 and 1821 by 1,835,980 persons, and between 1891 and 1901 by 3,525,318¹ persons, but it increased eighteen for every hundred of the existing population in the former period, and only twelve for every hundred in the latter. Though the recent increase was of greater absolute, it was of less relative, amount; it was, truly speaking, *at a less rate*. We ought, in short, in statistical matters to treat all quantities relatively to each other, and we ought to cultivate the habit of so regarding them.

The reason is not far to seek. Each generation naturally imitates the earlier one, from which both its hereditary character and its education are drawn. The son takes after his father—the same in body and mind, in passion and in judgment. Individual variations of character and career are of course innumerable; but, on the average, it is true that the son is as the father. He marries at the same age, strives at the same success in business, to gain the same fortune, to rear and educate the same family. If all things then go on the same,

¹ Census of England and Wales, 1901, Summary Tables, p. 1.

if no deterioration, no new obstacle presents itself, a family that rears a double progeny of children may expect a fourfold progeny of grandchildren, and an eightfold progeny of great-grandchildren. And though this could not be expected to occur in a single family subject to every accident of life, it may be expected on the average of a great mass of cases.


There are few countries where the population has ever doubled by breeding in a single generation, but the same reasoning holds good of any other rate. We are about doubly as numerous as our grandfathers. If we are in other respects like them—equally vigorous and enterprising, and free from any new exterior obstacles—we may expect our grandchildren to be doubly as numerous as ourselves.

This is one way of stating the law that men, as well as all living creatures, tend to increase in an uniform geometrical ratio. An uniform rate of growth means an uniform ratio—an uniform percentage of increase—*uniform multiplication in equal periods*. The law is as true and necessary as a mathematical law. *If* children do as their fathers did, they must increase like them; if they do not, some change must have occurred in character or circumstances inwardly or outwardly.

Such is the principle of population as established by Malthus in his celebrated essay. Of the moral and social consequences he deduced from that principle I need say nothing at present. They have been accepted for the most part by political economists. But the statement *that living beings of the same nature and in the same circumstances multiply in the same geometrical ratio* is self-evident when the meaning of the words is once properly understood.

What is true of the mere number of the people may be expected to hold true of other elements of their condition. If our parents made a definite social advance, then, unless we are unworthy of our parents, or in different circumstances, we should make a similar advance. If our parents doubled their income, or doubled the use of iron, or doubled the agricultural produce of the country, then so ought we, unless we are changed either in character or circumstances.

But great care is here necessary. We are getting to the gist of the subject. Even if we do not change in inward character, yet the aggregate of our exterior circumstances, our *environment*, as Mr. Spencer expresses it, is usually changing. This is what Malthus argued. He said that, though our numbers *tend* to increase in uniform



ratio, we cannot expect the same to take place with the supply of food. We cannot double the produce of the soil, time after time, *ad infinitum*. When we want to double the produce of a field we cannot get it by simply doubling the labourers. Any quantity of capital, and labour, and skill may fail to do it, though discoveries from time to time do allow of a considerable increase. Yet the powers and capabilities of organic and inorganic nature always present this remarkable contrast. The former are always relative to the number of existing beings, and tend unceasingly to increase. But exterior nature presents a certain absolute and inexorable limit, uncertain and indefinable though that limit may be.

The whole question turns upon the application of these views to the consumption of coal. Our subsistence no longer depends upon our produce of corn. The momentous repeal of the Corn Laws throws us from corn upon coal. It marks, at any rate, the epoch when coal was finally recognised as the staple produce of the country; —it marks the ascendancy of the manufacturing interest, which is only another name for the development of the use of coal.

The application of the principle of geometrical progression, however, is a little complicated.

The quantity of coal consumed is really a quantity of two dimensions, the number of the people, and the average quantity consumed by each. Even if each person continued to use an invariable quantity of coal per annum, yet the total produce would evidently increase in the same ratio as the number of the people. But added to this is the fact that we do each of us on the average increase our consumption of coal from year to year. In round numbers, the population has about quadrupled since the beginning of the nineteenth century, but the consumption of coal has increased sixteenfold, and more. *The consumption per head of the population has therefore increased fourfold.*

Again, the quantity consumed by each individual is a composite quantity, increased either by multiplying the scale of former applications of coal, or finding wholly new applications. We cannot, indeed, always be doubling the length of our railways, the magnitude of our ships, and bridges, and factories. In every kind of enterprise we shall no doubt meet a natural limit of convenience, or commercial practicability, as we do in the cultivation of the land. I do not mean a fixed and impassable limit, but as it were an elastic limit, which we may push against a little further, but ever with increasing difficulty.

But the new applications of coal are of an unlimited character. In the command of energy, molecular and mechanical, we have the key to all the infinite varieties of change in place and kind of which nature is capable. Hardly any chemical or mechanical operation, perhaps, is quite impossible to us in a physical or scientific point of view, and invention consists in discovering those operations which are both useful and commercially possible. No *a priori* reason here presents itself why each generation should not use its resources of knowledge and material possessions to make as large a proportional advance as did the preceding generation.

And it cannot escape the attention of any observant person that our inventions and works do multiply in variety and scale of application. As Professor Hearn has ably explained in the chapter on Invention in his *Plutology*, each success assists the development of previous successes, and the achievement of new ones. None of our inventions can successfully stand alone—all are bound together in mutual dependence. The iron manufacture depends on the use of the steam-engine, and the steam-engine on the iron manufacture. Coal and iron are essential either in the supply of light or water, and both

these are needed in the development of our factory system. The advance of the mechanical arts gives us vast steam-hammers and mechanical tools, and these again enable us to undertake works of magnitude and difficulty before deemed insuperable. "The tendency of progress," says Sir William Armstrong,¹ "is to quicken progress, because every acquisition in science is so much vantage ground for fresh attainment. We may expect, therefore, to increase our speed as we struggle forward."

For once it would seem as if in fuel, as the source of universal power, we have found an unlimited means of extending our command over nature. Alas! No! The coal is itself limited in quantity—not absolutely, as regards us, but so that each year we gain our supplies with some increase of difficulty. There are unlimited novelties to make our own, *had we unlimited energy to use them.*

Such are the *a priori* principles of our progress. But I should be as ill-contented as any of my readers to rest the argument upon such theory alone. I shall appeal equally to experience, and show that some of the main branches

¹ *Resources of the three Northern Rivers*, quoted in the *Quarterly Journal of Science*, No. 2, p. 371.

of industry depending upon the use of coal have obeyed the law of uniform geometrical increase for long terms of years. I can show that, up to the year 1865,¹ we were in an unchecked course of discovery and growth—that old applications of coal have been extended, and yet admit of great extension, while new ones are continually being added. And I shall infer that continuance of the same course of extension may be expected in the absence of any extraordinary influence; that the consumption of coal will increase at a nearly constant rate until some check, some natural but perhaps elastic boundary of our efforts, is encountered.

For the present our cheap supplies of coal, and our skill in its employment, and the freedom of

¹ This date is here inserted, not with any purpose of indicating the date at which the "unchecked course . . . of growth" met a check, but as marking the date to which the proof, as offered in the second edition of this work by Jevons himself, extended. In his revision of this chapter, probably about fifteen years later, the words "up to the present" were left unchanged. It will be seen in chap. xii that for about thirty years ending 1904 the rate of increase of production of coal in Great Britain has been fairly constant, though at a figure substantially less than that of the decade ending 1865. Some of the difficulties of increasing depth of mines and increased cost of mining, referred to by Jevons in the passages immediately following, have been experienced already to some extent. In spite of this, the phraseology employed appears still sufficiently appropriate not to require recasting at the hands of the editor of this edition, and no change not indicated by Jevons himself has been made in the later pages of this chapter.

our commerce with other wider lands, render us independent of the limited agricultural area of these islands, and apparently take us out of the scope of Malthus' doctrine. We are growing rich and numerous upon a source of wealth of which the fertility does not yet apparently decrease with our demands upon it. Hence the uniform and extraordinary rate of growth which this country presents. We are like settlers spreading in a rich new country of which the boundaries are yet unknown and unfelt.

But then I must point out the painful fact that such a rate of growth will render our annual consumption of coal before long comparable with the total supply. In the increasing depth and difficulty of coal mining we shall meet that vague but inevitable limit which will stop our progress. We shall begin, as it were, to discover the further shore of our Black Indies. The wave of population will break upon that shore, and roll back upon itself. And as settlers, unable to choose in the far inland new and virgin soil of unexceeded fertility, will fall back upon that which is next best, and will advance their tillage up the mountain side, so we, unable to discover new coal-fields as shallow as before, must deepen our mines with pain and cost.

There is, moreover, this most serious and yet obvious difference to be noted. A farm, however far pushed, will under proper cultivation continue to yield for ever a constant crop. But in a mine there is no reproduction; the produce once pushed to the utmost will soon begin to fail and sink towards zero. *So far, then, as our wealth and progress depend upon the superior command of coal we must not only cease to progress as before—we must begin a retrograde career.*

CHAPTER X

OF THE GROWTH AND MIGRATIONS OF OUR POPULATION

It is in several ways essential to our inquiry to examine, briefly, the increase and movements of our population, and the extraordinary effects which the growing use of coal has exercised upon it.

Our examination must be restricted to England and Wales, or at most to Great Britain. Ireland, if referred to at all, must be contrasted with England in natural and social condition. *Practically and commercially* Ireland is devoid of coal. [Professor Hull's estimate of the total available coal in the island puts it at scarcely more than would suffice for a single year's consumption for the entire United Kingdom.] The total produce was 106,000 tons in 1904, and is on the decrease. For the most part the quality of the coal is inferior, and the cost of mining it great.

Ireland cannot raise a manufacturing system alongside of England when she has to buy from England the chief requisite of manufacturing industry. The manufactures of Ireland have been abolished by the steam-engines of England,¹ and it is a persistent but strange error of authors and statesmen to suppose that Ireland can still find wealth in imitation and rivalry with England. The industrial efforts of the Irish should be exerted in a *contrary* direction to those of England, and agriculture and handicraft employments in which fuel affords no aid will be their best resource. If it be found that such pursuits will not sustain an increasing population, we must learn to conform to the conditions under which we are placed; and when rightly viewed the continued exodus of the Irish people, by which a population of 8,196,597 persons in 1841 was reduced to 5,798,967 in 1861, [to 5,174,836 in 1881, and to 4,458,775 in 1901,] is a fact confirming, in the negative way, many conclusions to be drawn concerning the progress of our own population.

Scotland will be occasionally referred to. It exhibits the bright and dark features of English progress, intensified in degree. While the general

¹ H. Fairbairn, *Political Economy of Railroads*, 1836, p. 108.

rise of Scotch industry, especially in the cases of the Glasgow iron trade and the lowland agriculture, surpasses the highest instances of English progress, the poverty and distress of the Highland and sterile parts, and the emigration thence arising, exceed anything we have suffered in the agricultural parts of England. But the want of statistical data concerning Scotland and Ireland would generally oblige us to give our attention to England alone, were this not also desirable for the sake of simplicity.

The table on the opposite page exhibits the progress of the population of England and Wales for more than three centuries, according to the most reliable estimates and enumerations.

The estimates for the sixteenth, seventeenth, and eighteenth centuries, however carefully calculated from the registers of births, deaths, and marriages, and from other data, are not true to a nicety; but they afford at any rate conclusive evidence that in the first half of the eighteenth century the population was nearly stationary, and occasionally diminishing. About the middle of the century, it began to grow again; and the rate of growth rose until, in the beginning of the nineteenth century, it reached a height altogether unprecedented in the history of the country. In the period 1811-21 especially, we find the

POPULATION OF ENGLAND AND WALES

Year	Population	Numerical increase for ten years	Rate of increase per cent for ten years
1570	4,160,321 ¹		
1600	4,811,718	217,132	5 increase
1630	5,600,517	262,933	5 "
1670	5,773,646	43,282	1 "
1700	6,045,008	90,454	2 "
1701	6,121,525 ²		
1711	6,252,105	130,580	2 "
1721	6,252,750	645	0 "
1731	6,182,972	-69,778	1 decrease
1741	6,153,227	-29,745	0 "
1751	6,335,840	182,613	3 increase
1761	6,720,547	384,707	6 "
1771	7,153,494	432,947	6 "
1781	7,573,787	420,293	6 "
1791	8,255,617	681,830	9 "
1801	8,892,536 ³	636,919	11 "
1811	10,164,256	1,271,720	14 "
1821	12,000,236	1,835,980	18 "
1831	13,896,797	1,896,561	16 "
1841	15,914,148	2,007,351	14 "
1851	17,927,609	2,007,461	13 "
1861	20,066,224	2,138,615	12 "
1871	22,712,266	2,646,042	13 "
1881	25,974,439	3,262,173	14 "
1891	29,002,525	3,028,086	12 "
1901	32,527,843	3,525,318	12 "

¹ Preface to *Census Returns of 1841*, pp. 34-37.

² 1701-1791 including Army, etc., abroad: *Census of 1861, General Report*, p. 22. See the Diagram fronting the title-page.

³ 1801-1901 excluding Army, etc., abroad. In 1801-1831 the

increase as high as 18 per cent, or treble the rate which prevailed in the previous half century.

In passing I will draw attention to the fact that the ratios or rates per cent of increase show some approach to uniformity over considerable periods of time. The simple numerical increase of population presents no such uniformity, and in late times is thoroughly divergent. In fact *the arithmetic increase of the four years 1857-1861 was as great as that of the whole century, 1651-1751.*¹ It is clear, from the mere inspection of the table, that *the notion of an arithmetic series is wholly inapplicable to matters of population and statistics.* We must look to the ratio or proportional rate of increase, as measuring progress or marking the changes of condition of our population.

Looking now to the rates of increase after

Army at home and men on shore belonging to the Royal Navy or to the Merchant Service are also excluded. In computing the rates of increase between 1791 and 1801, and between 1831 and 1841, the figures for such groups have been either included or excluded in each of the years compared. Thus, including the Army, &c., abroad, the population in 1801 was 9,192,810, and it is this figure which gives an increase of 11 per cent. on 1791 (*Census of England and Wales*, 1901, Summary Tables, p. 1).

¹ *General Report upon the Census of 1861*, p. 22. The addition in the two years 1899-1901 was as great as that of the century named (cf. *Preliminary Report on the Census of 1901*, p. viii).

1821, we are at once struck by a very distinct and continuous decrease maintained for five consecutive decades. The rate of 18 per cent diminishes successively to 16, 14, 13, and 12 per cent. *There is an appearance of convergency—of a new approach to a stationary condition.*

[This appearance of convergency has not been maintained at the later dates shown in the table.] Properly examined, indeed, this appearance is found to be very deceptive. When necessary allowances are made, *our growth during the half-century in question is seen to have been one of increasing rapidity.*

In the first place, a nation is a very composite whole, of which each part may change at its own rate. Our population especially is divided into the distinct agricultural and manufacturing masses—contrasted as they are in every point of nature, history, and social condition. The one represents Old England in its maturity; the other, New England, the greater in numbers, yet still growing as in youth.

We may compare the condition of these two great portions by means of the rates of progress of some of the most purely agricultural and most purely manufacturing counties:—

INCREASE OF POPULATION PER CENT¹

Agricultural Counties	1801-11	1811-21	1821-31	1831-41	1841-51	1851-61	1861-71	1871-81	1881-91	1891-1901
Bucks . .	9	14	9	6	5	3	5	0	5	6
Cambs. . .	13	21	18	14	13	-5	6	-1	2	1
Devon . .	12	15	13	7	6	3	3	0	5	5
Dorset . .	9	16	10	10	5	2	4	-2	2	4
Hereford .	6	10	8	2	2	7	1	-3	-4	-1
Norfolk . .	7	18	13	6	7	-2	1	1	2	1
Somerset .	10	17	13	8	2	0	4	1	3	5
Suffolk . .	9	16	9	6	7	0	3	2	4	4
Westmorl.	12	12	7	3	3	4	7	-1	3	-3
Wilts . . .	4	14	8	8	-1	-2	3	1	2	3

INCREASE OF POPULATION PER CENT

Manufacturing Counties	1801-11	1811-21	1821-31	1831-41	1841-51	1851-61	1861-71	1871-81	1881-91	1891-1901
Durham . . .	10	17	24	29	27	30	35	27	17	17
Lancaster . .	22	27	27	24	22	20	16	23	14	12
Monmouth . .	35	22	29	36	17	11	12	8	20	16
Northumber- land . . }	9	15	11	12	14	13	13	12	17	19
Stafford . . .	21	17	18	24	20	23	15	14	10	14
Glamorgan . .	19	20	24	35	35	37	25	29	34	25

Comparing the above tables, we see that in the period 1811-21 both the agricultural and manufacturing populations were in a state of

¹ *Census of England and Wales, 1901, Summary Tables (Ancient Counties), p. 7.* The negative sign (-) indicates a decrease of population, as in the cases of Cambridge and Wiltshire.

rapid increase. To this is due the extraordinary general rate of increase of the population, namely eighteen per cent during those ten years. But the subsequent rapid decline of the agricultural rate shows how impossible it was for a growing population to find subsistence on the land. And when we remember the prevalence of pauperism during the period 1811-21 we shall be convinced that the increase of agricultural population which did occur was unsound and not warranted by any corresponding increase in the means of living.

The following numbers express the average sum contributed by each person in England and Wales to the legal support of the poor:¹—

	s.	d.
1801	9	1
1811	13	1
1821	10	7
1831	9	9
1841	6	0
1851	5	7
1861	5	10
1871	7	0
1881	6	3½
1891	6	0
1901	7	2

Some allowance ought to be made for the variation in the value of the currency, but the pres-

¹ Porter's *Progress*, 1851, p. 91, and *Annual Reports* of the Local Government Board.

sure of pauperism in the early years of the nineteenth century would still remain about double what it became after the middle of the century. And this pressure was chiefly felt in the agricultural counties. Mr. Porter, in his *Progress of the Nation*,¹ gave a table whence it clearly appeared "that the burthen of the poor's rate in proportion to the population is generally greatest in the most agricultural counties. Suffolk, Norfolk, Wiltshire, Oxfordshire, Buckinghamshire, Essex, and Cambridgeshire, all essentially agricultural, are the most heavily burthened with poor; while Lancashire, the West Riding of Yorkshire, Cheshire, Staffordshire, Nottinghamshire, and Derbyshire, which are of an opposite character, enjoy a comparative exemption from that burthen." This clearly marked difference prevents us from attributing the excessive pauperism of the time to the wars, or the high price of corn, which last circumstance ought to favour the agricultural, at the expense of the manufacturing population.

The laxness of the Poor-laws, the impetus communicated by the rise of our manufacturing and trading system, the demand for soldiers, and perhaps other causes, seem to have induced

¹ Ed. 1851, pp. 96-97.

throughout the United Kingdom, in the early part of the nineteenth century, habits of unrestricted marriage which, in the absence of any extraordinary outlet for the growing population, could only lead to poverty. In Ireland the result of an unsound but rapid growth of agricultural population was that extraordinary emigration which is not yet stopped. In the Scotch Highlands the result was hardly less deplorable, or the emigration less remarkable, though on a minor scale. The harshness of nature rather than the harshness of the landlords is the cause of this emigration, which is clearly shown in the following rates of progress and regress:—

INCREASE OR DECREASE OF POPULATION PER CENT ¹

Scotch Highland Counties	1801-11	1811-21	1821-31	1831-41	1841-51	1851-61	1861-71	1871-81	1881-91	1891-1901
Argyll . . .	6	12	4	-4	-9	-11	-5	1	-2	-1
Ross . . .	8	13	9	5	5	-2	-1	-3	-1	-3
Inverness . .	7	16	5	3	-1	-9	-1	3	-1	0
Sutherland .	2	1	7	-3	4	-2	-4	-4	-6	-2

It is interesting to compare the rates of progress in the highland counties with those

¹ *Census of Scotland, 1901, Preliminary Report*, pp. 15-18. The negative sign (—) indicates a decrease of population.

in counties where the coal and iron trades flourish :—

INCREASE OF POPULATION PER CENT

Scotch Manufacturing Counties	1801-11	1811-21	1821-31	1831-41	1841-51	1851-61	1861-71	1871-81	1881-91	1891-1901
Ayr. . .	23	23	14	13	15	5	1	8	4	12
Lanark .	29	28	30	34	24	19	21	18	16	21
Renfrew .	18	20	19	16	3	10	22	21	10	17

Now in England our agricultural population has received a check similar to that in the Scotch Highlands. No inconsiderable numbers have gone abroad, but in general the surplus country population has been drafted into the towns. Those nourished among sheep-pastured hills, or richly tilled fields, in the quiet village, or the lonely hut, are attracted to the crowded, squalid alleys, the busy workshop, or the gloomy mine.

Mr. Smiles has explained how the population of a hill-girt district, like Eskdale, is kept stationary from generation to generation. "Oh, they swarm off," said a native to him. "If they remained at home we should all be sunk in poverty, scrambling with each other among these hills for a bare living."¹

¹ *Lives of the Engineers*, vol. ii, p. 291.

It is indeed true, as remarked by Mr. Rickman,¹ that an increase of population "may be deemed a solid good, or a dreadful evil, according to the circumstances of the country in which it occurs. If a commensurate increase of food and of raiment can be produced by agriculture and by manufacture, an accession of consumers in the home market cannot but be beneficial to all parties; and the increase of population in such case may be deemed equally desirable in itself, and conducive to national strength and national prosperity."

The effects of an unwarranted growth of population are seen in the poverty of our own agricultural counties and in the wretchedness of Ireland and the Scotch Highlands.

It is our towns which alone afford the growing subsistence which is the warrant of an increment of population. They not only have room for their own native born, but engulf the best blood of the country districts. They afford that unlimited subsistence, which could alone enable our population to approach a constant geometrical rate of increase.

But it must not be supposed that our towns have maintained a constant rate of growth. I

¹ *Preliminary Observations to Population Abstracts*, 1822, p. xxx.

have chosen thirty of the most progressive and important English manufacturing towns, and summed up the number of their inhabitants.¹

¹ The list of the towns selected by Jevons is not available, and attempts to recover it have not been successful. Changes of area introduce some difficulty in long comparisons. Thus the figures given in the *Census Reports* for 1891 and 1901, as representing the population of certain of the towns in 1851 and 1861, are not precisely the same in the two reports. Hence it seems impossible to claim that the figures of earlier reports accurately represent the population decade by decade of the localities covered by a given list of urban designations to-day.

Using the figures of the *Census Report of 1901* (Summary Tables, pp. 102-3), the following shows the aggregate population of thirty English manufacturing towns, omitting London and sea-ports, and of seventeen seaport towns, not including London.

Year	Thirty manufacturing towns			Seventeen seaport towns		
	Population	Numerical increase in ten years	Increase per cent in ten years	Population	Numerical increase in ten years	Increase per cent in ten years
1851	2,221,000			1,052,000		
1861	2,682,000	461,000	21	1,315,000	263,000	25
1871	3,155,000	473,000	18	1,617,000	302,000	23
1881	3,778,000	623,000	20	1,983,000	366,000	22
1891	4,301,000	523,000	14	2,322,000	339,000	17
1901	4,789,000	488,000	11	2,680,000	358,000	15

In considering the reduction of the rates of growth, both in this table itself, and as compared with that in the text, it must be remembered that the figures, in many cases, fail to include large suburban populations, and that a great part of the reduction in rate of growth may be assigned to this failure of the later figures to represent the whole populations of the urban aggregation fully comprised in the figures for earlier dates. The higher rates of growth in towns dependent on shipping and shipbuilding, as compared with manufacturing proper, are worthy of notice.

MANUFACTURING TOWNS (NOT INCLUDING
LONDON)

Year	Population	Numerical increase in ten years	Rate of increase per cent in ten years
1801	623,000		
1811	763,000	140,000	22
1821	991,000	228,000	30
1831	1,352,000	361,000	36
1841	1,763,000	411,000	30
1851	2,220,000	457,000	26
1861	2,679,000	459,000	21

Such numbers alone give us an adequate notion of our powers of growth. Our manufacturing population more than quadrupled itself in sixty years; it multiplied at a rate equivalent to doubling in twenty-eight years. When the new is thus viewed apart from the old, our growth is seen to have been that rather of a new colony than of an ancient settled country whose history runs back 2,000 years. And when it is considered that this country and the busy towns in question have been sending forth the hundreds of thousands of emigrants who populate America, Australia, and Africa, I assert, without fear of contradiction, that the annals of the newest and most flourishing settlements afford nothing so truly astonishing as our growth. England enjoys the stable society, the refinements and comforts,

the intellectual and historical renown which belong to an ancient, mature, and honourable monarchy. But she joins the good new to the good old in a manner elsewhere unknown. In our spreading towns, in our factories and fleets, not to speak of our arts and sciences, our yet living literature, and our constitution still perhaps changing for the better, we see the great work which is given into our care to carry on in moderation for the good of ourselves, our posterity, and the world.

But, to return, it will be seen that the rate of progress of our town population dropped from thirty-six per cent in 1821-31 to twenty-one per cent in 1851-61. Is not this an indication that even our town population is overrunning its means of subsistence, and that we are now converging to a stationary condition? This is far from being true as yet;¹ but in any case our

¹ Jevons added here, "The rates of increase will probably not continue falling." The footnote on p. 214 seems to contradict this anticipation. How far the reason there indicated for the fall suffices to account for the entire reduction cannot be known with accuracy. The modern means of locomotion are facilitating concentration for working purposes at the same time that a considerable dispersion for purposes of residence occurs. Some look forward to a dispersion for working purposes as well. Now that more than three-fourths of the entire population is found in urban districts, it is clear that their high rate of growth cannot be maintained for much longer by immigration from the rural districts.

industry is divergent ; and the more so, the more nearly we regard it in its first spring. It is the high rate of progress maintained by Durham and Glamorgan that most truly represents the progress of our national industry. The growth of the populations of those counties has been already shown, but the steady progress of our great northern coal trade is still more clearly shown in the following accounts of the united populations of the five great coal towns, Newcastle, Gateshead, Tynemouth, South Shields, and Sunderland.¹

NORTHERN COAL TOWNS

Year	Population	Numerical increase in ten years	Rate of increase per cent in ten years
1801	90,825		
1811	99,889	9,064	10
1821	125,128	25,239	25
1831	151,487	26,359	21
1841	192,283	40,796	27
1851	236,216	43,933	23
1861	293,707	57,491	24
1871	359,655	65,948	22
1881	428,733	69,078	14
1891	528,657	99,924	23
1901	619,922	91,265	17

¹ Jevons' figures for 1851 and 1861 have been replaced by those given in the report of the Census of 1901 (Summary Tables, pp. 102-3), with which they were not quite identical.

London, too, a kind of great resultant and measure of the rest of the kingdom, held a nearly constant rate for the first three-quarters of the nineteenth century—

POPULATION OF LONDON¹

Year	Population of London	Numerical increase in ten years	Rate of increase per cent in ten years
1801	959,310		
1811	1,139,355	180,045	19
1821	1,379,543	240,188	21
1831	1,655,582	276,039	20
1841	1,949,277	293,695	18
1851	2,363,341	414,064	21
1861	2,808,494	445,153	19
1871	3,261,396	452,902	16
1881	3,830,297	568,901	17
1891	4,228,317	398,020	10
1901	4,536,541	308,224	7

¹ Even as late as 1881, this table shows the “nearly constant” rate noted by Jevons. The small increases of the last two decades may be compared with the following, which gives the population of Greater London—the Metropolitan Police District.

Year	Population of Greater London	Numerical increase in ten years	Rate of increase per cent in ten years
1861	3,322,720		
1871	3,885,641	662,921	21
1881	4,766,661	881,020	23
1891	5,633,806	867,145	18
1901	6,580,616	946,810	17

This table shows that the population of the Registration County

The appearance of convergency which our population as a whole presented forty years ago was due to emigration. And this emigration was not a mere adventitious and disturbing circumstance. It was an integral part—the complement of our general development. The more we grow at home upon our mineral resources and manufacturing skill, the greater demands we make for food and raw materials. And it is to a great extent our demand which raises wages in our American, Australian, and African settlements to rates that attract our population abroad. The discoveries of gold have added only an accidental and temporary attraction from time to time.

Modern Britain does not and could not stand alone. It is united on the one hand to ancient agricultural Britain, and on the other hand to the modern agricultural nations of our stock, which are growing in several continents. Of the same language and manners, and bound together in the same real interests of trade, Britain and

of London has become entirely inadequate as an index to the growth of the real London. It confirms the suggestion that apparent failure of cities to maintain the former rate of increase is largely due to the development of suburbs, more and more distant from the centre, from decade to decade. The high rate of increase of population in urban sanitary districts of from 50,000 to 100,000 inhabitants in each of the last two intercensal periods, namely, 23 per cent, may also be noted in this connection.

her colonial offspring must be regarded for the present as a single whole. Our own agricultural area being essentially limited, the offspring of the agricultural population must find employment either in our towns or abroad. And the growth of our towns requires a corresponding growth of our foreign agricultural settlements.

But it must not be supposed that the emigration from England [here in question, namely, that of the fifties and sixties,] was caused by internal pressure.¹ It arose rather from the external allurements which the colonial settlements offer in high wages, independence, and a certain charm of novelty and adventure not to be overlooked. The Irish emigration of 1847, indeed, was caused by internal pressure, and is to be contrasted to that still going on, and which is due to a positive attraction exercised upon the Irish by American prosperity. So the gold discoveries formed attractions which greatly accelerated English emigration, and aided the development of colonies now so important to our trade.

When once planted in almost boundless areas

¹ The statement that "it must not be supposed that emigration from England is caused by internal pressure" is probably nearly, if not quite, as true at the beginning of the twentieth century as it was forty years ago. In the interval a period has been passed through when it was not entirely true.

of rich country, like those of North America, Australia, and South Africa, population is free to multiply at a new rate, and to manifest its geometrical tendency, relieved of the checks which Malthus showed to be a usual restraint.

But the important result to us is the secondary effect of foreign British population in trading with the centres of manufacturing industry, and stimulating the growth of our wealth and numbers at home. Food and raw materials are poured upon us from abroad, and our subsistence is gained by returning manufactures and articles of refinement of an equal value. Provided our skill, our capital, but, above all, our motive power, coal, be equal to the continuous drain, there is no pitch of material wealth and greatness to which our towns might not attain, when thus supplied from our foreign agricultural settlements with the other elements of subsistence. For the present, it would seem that our home resources are unweakened, and equal to any probable demands.

Hence it is that, in our most crowded towns, we have, in the development of our manufacturing and coal-consuming system, means of subsistence which for the present remove Malthusian checks to increase. Whether our children stay at home,

or whether they go abroad, there is the same addition of useful labour, in fields of undiminished fertility, and the same inducements to a future continued multiplication.

The proof that this was the true state of affairs—that the greatly increased emigration of the fifties was not due to poverty and pressure at home, but rather to attractions abroad—that our increase of population was rather under than above the increasing means of subsistence—may be found in many gratifying facts concerning our wealth, comfort, and contentment ; but it is most strikingly shown in our marriage-registers. Poverty and superfluity of population would tend to restrain marriage, and free emigration would then, at the most, allow the continuance of the usual rate of marriage. Malthus, Ricardo, and other economists of the same period, were too much inclined to regard this as the normal state of society. Population seemed to them always full to the brim, so that each ship-load taken to the colonies would no more tend to empty the country, than a bucketful of water would tend to empty the ever-running fountain from which it is drawn. They could not bring themselves to imagine such a state of things in this country, that one man

should not stand in another's way, and that men, rather than subsistence, should be lacking. But that this country, [in the third quarter of the nineteenth century,] did make some approach to such a happy condition, is conclusively shown by the extraordinary spread of marriage then recorded.

"Marriages express the hopes and fears of the country. They go on at all seasons, and at all times; but prudence makes them fluctuate, so that the more and the less indicate the feelings with which the great body of the people regard their prospects in the world."¹ Every year of depressed trade and distress leaves its mark upon the returns of the Registrar-General, in the shape of diminished marriage; and every period of prosperity has a contrary effect. The returns, in consequence, are in no slight degree irregular; but, treating the numbers of marriages in periods of ten years, we get the results shown on the following page. The very considerable rise in the marriage rate is a fact of the utmost significance. The rise in the decade 1851-60 is all the more remarkable when compared with the low rate of increase of persons of marriageable age, as shown on p. 230.

¹ Quarterly Report of the Registrar-General, 1849.

MARRIAGES IN ENGLAND AND WALES

	Number of marriages	Numerical increase	Rate of increase per cent
1801-10	832,151		
1811-20	910,434	78,283	10
1821-30	1,052,095	141,661	15
1831-40	1,179,615	127,520	12
1841-50	1,354,988	175,373	15
1851-60	1,600,596	245,608	18
1861-70	1,769,624	169,028	11
1871-80	1,960,146	190,522	11
1881-90	2,047,428	87,282	5
1891-1900	2,394,105	346,677	17

In stating the marriage returns for the quarter ending September, 1865, the Registrar-General says: "The rate was much above the average. Weddings were more rife than they were in the previous summer, or in the summer of any year since registration began. This implies that the great body of the people were prosperous."

The increasing frequency of marriage presents a strong contrast to the failing rate of increase of the total population in the fifties. It shows conclusively that no such thing as an internal check to population in England existed at that time, and that Nature was taking its appropriate means to remedy the drain from outward attractions.¹

¹ The increase of marriages in the last decade of the nineteenth

Striking confirmatory evidence of the increasing frequency of marriage in the decade 1851-61 is derived from a comparison of the returns of the censuses concerning the conjugal condition of the people. It is found that the number of married persons increased 16 per cent between 1851 and 1861, or 4 per cent more than the general population; while the unmarried women of the age 20-40 years increased but little, and the unmarried men of the same age scarcely at all. The numbers are as follows:—¹

	Husbands	Wives
1851	2,958,564	3,015,634
1861	3,428,443	3,488,952
Increase	469,879	473,318
Rate of increase 16 per cent		16 per cent

	Bachelors	Spinsters
1851	1,198,050	1,168,386
1861	1,201,576	1,229,051
Increase	3,526	60,665
Rate of increase $\frac{3}{10}$ per cent		5 per cent

century, especially when contrasted with the comparative stagnation of marriages in the eighties, offers a similar testimony to the renewed confidence of the people in their prosperity.

¹ The figures for 1891 and 1901 are:

	Husbands	Wives
1891	4,851,548	4,916,649
1901	5,611,381	5,717,537
Increase	759,833	800,888
Rate of increase. 16 per cent		16 per cent

The increase of married persons at a rate 4 per cent greater than that of the entire population does not arise in this case from a check in the increase of bachelors and spinsters. Compared with the preceding decade, such a check is discernible, but the following

To complete this chapter, it would be desirable to present such accounts of the number of emigrants from England as would quantitatively prove emigration to have been that check to our population which we have considered it; but statistics are here deficient. Accounts of the number of emigrants since 1814 have been

table shows that the unmarried population at marriageable ages was still increasing faster than the general population.

Census Year	Of 100,000 males over 15 years of age			Of 100,000 females over 15 years of age		
	Unmarried	Married	Widowed	Unmarried	Married	Widowed
1851	41,103	52,924	5,973	38,539	50,399	11,062
1861	38,783	55,400	5,817	36,892	51,860	11,248
1871	38,402	55,869	5,729	36,136	52,234	11,630
1881	39,180	55,324	5,496	36,738	51,638	11,624
1891	40,580	54,020	5,400	38,665	49,920	11,415
1901	41,111	53,629	5,260	39,548	49,632	10,820

The fact is that the reduced mortality of the later decades of the nineteenth century, affecting especially the younger part of the population, say up to 25 years of age, gives so many more survivals, from a given number of births, than formerly that the increase at the marriageable ages has been at a rate about 50 per cent above the general rate of increase of the population in the decade 1891-1901, the population at ages 20-40 having increased by 19·5 per cent as compared with 12·2 per cent increase of the total population. In the preceding decade the rates of increase were 14·9 for those aged 20-40 compared with 11·65 for the population at large. The younger marriages and consequent more numerous children of 30 to 40 years ago have yielded a relatively large population of adults. When Jevons wrote the average age of marriage was still falling. It has recently been rising. It may be noted that the marriage rates of the years 1897-1902 were higher than any since 1876.

published ; but unfortunately no record of the nationality of the emigrants has been preserved. The large and fluctuating amounts of Irish and Scotch emigration render the accounts [up to the middle of the century] quite inapplicable to England ; but from the accounts, such as they are, I form the following table of emigration to the several parts of the world :—

EMIGRATION FROM THE UNITED KINGDOM

Period of Years	United States	North American Colonies	Australasian Colonies	Elsewhere	Total
1815-20	50,359	70,438	—	2,731	123,528
1821-30	99,801	139,269	8,935	1,805	249,810
1831-40	308,247	322,485	67,882	4,536	703,150
1841-50	1,094,556	429,044	127,124	34,168	1,684,892
1851-60	1,495,243	235,285	506,802	49,875	2,287,205
1861-70	1,132,626	130,310	267,358	41,535	1,572,029
1871-80	1,087,372	177,976	303,367	110,204	1,678,919
1881-90	1,713,953	301,922	372,744	169,916	2,558,535
1891-200	1,145,904	186,976	127,681	282,229	1,742,790
Total	8,128,061	1,993,605	1,781,893	696,999	12,600,858

Statistics of the immigration into the United States¹ enable us to gain some notion of the increase of English emigration apart from that of the Irish and Scotch [in the years preceding the

¹ Bromwell on Immigration, p. 176.

gathering of English statistics of the nationality of emigrants]. In the American accounts, indeed, the nationality of the larger part of the immigrants is not stated; but if we divide the number of the undistinguished immigrants, in periods of ten years, in the proportion of the numbers of those whose birthplace is distinguished, we get the following probable numbers of immigrants to the United States, whose birthplace was in England or Wales :—¹

	Persons.
1821-30	25,365
1831-40	55,676
1841-50	175,253
1851-55	203,508

¹ Since the beginning of 1853 the nationality of emigrants has been registered in our Custom-house accounts; and the estimate of the Census Commissioners (Census of 1861, Population Tables, vol. i, p. xxxii), together with the later returns on the same subject (Census of England and Wales, 1901, Preliminary Report, p. 138), afford the following :—

EMIGRANTS OF BRITISH NATIONALITY

Intercensal period	English ¹	Scotch and Irish	Total British
1851-61	640,316	1,414,262	2,054,578
1861-71	649,742	1,024,852	1,674,594
1871-81	996,038	701,681	1,697,719
1881-91	1,572,717	1,020,509	2,593,226
1891-1901	1,110,584	653,107	1,763,691

From 1876 the record of inward passengers from places out of Europe shows how many of these were of British nationality. In the five years 1876-80, the inward movement reached nearly 40

Emigrants are chiefly young men and women. The following figures give the proportional numbers of immigrants at New York, and the other ports of entry in the United States, for three intervals of age :—¹

Years of Age	
9—15	22
15—30	50
30—45	28 ²

In short, three out of four emigrants are marriageable, or recently married.

The effect of emigration upon the ages of our population is strikingly shown in the following numbers, which express the rates of increase per cent between 1851 and 1861, of the numbers of persons in England and Wales between the ages stated :—³

per cent of the strength of the outward movement. In the decade 1881-90 it was about one-third, and in the decade 1891-1900 nearly 60 per cent of the emigration. In these figures English are not separated from Scotch and Irish.

¹ *Abstract of Seventh Census of the United States*, p. 14.

² Including, in the American authority, "the small number at older ages."

The later accounts do not make the division at 30 years of age, but show separately those over 40. The proportion under 15 fell to 16 per cent in 1891-1900, while 9 per cent were over 40 years of age, a smaller figure than in either of the two preceding decades.

³ *Census*, 1861, Appendix to General Report, p. 111.

The following table shows more precisely the ages affected by emigration in 1851-61 than the figures of the text, and shows that

Age	Rate of increase per cent
0—20 years	12'0
20—40 „	9'5
40—60 „	16'0
60—80 „	14'0
80—100 „	5'8

The low rate of increase for the ages 20—40 years is very remarkable, and these numbers alone prove that our population, but for the emigration going on, would have increased at the rate of 14 or 15 per cent instead of 12 per cent.

It is in strict accordance with the known principles of population, that the great gap in the procreative powers of the population, caused by

the emigration preceding 1851, as well as that of 1851—61, was concerned in producing the figures shown :—

Rates of Increase per cent

Age	1841-51	1851-61	1861-71	1871-81	1881-91	1891-1901
0-15	10'58	12'53	14'71	15'44	7'43	3'67
15-25	8'85	9'88	11'24	16'49	14'81	13'75
25-35	12'09	7'62	13'01	13'56	15'40	20'06
35-55	16'93	14'90	11'54	11'94	13'91	18'41
55-	19'46	14'34	14'92	12'71	11'27	14'24
All ages	12'65	11'90	13'21	14'36	11'65	12'17

The figures for the youngest group are remarkable and deserve study. A detailed examination would be out of place here. It may be noted that the low figure for the last intercensal period is due largely to the falling off in births in the eighties and early nineties. For ages under 5 years the last intercensal interval shows a more rapid advance than the preceding.

The exceptional nature of the movement of 1841-61 is shown by the table.

so large a subtraction of marriageable persons, should be filled by an unusual spread of marriage among those who remain ; and the extent to which this took place has already been stated. But are there no serious reflections that should occur to us, when made acquainted with such facts ? Should we forget that [these facts demonstrate the attainment of] the highest state of progress and prosperity that a country can look to enjoy ? A multiplying population, with a constant void for it to fill ; a growing revenue, with lessened taxation ; accumulating capital, with rising profits and interest. *This is a union of happy conditions which hardly any country before enjoyed, and which no country can long expect to enjoy.*¹

It is in such a period that a population becomes accustomed to early marriage, the easy acquirement of a livelihood, the habit of looking for a rise in the social scale, and the enjoyment of leisure and luxuries. Nothing can be more desirable than such a state of things as long as it

¹ How soon the rate of progress would be interrupted, Jevons did not foresee. So far as it goes, the diminished rate of advance of the last quarter of the nineteenth century, though not necessarily the evidence of a continual diminution in the future rate of progress, serves but to illustrate and enforce the warning that our present prosperity is not to be expected to endure indefinitely.

is possible. It is the very happiness of civilisation. But nothing is more grievous than the forcible change of such habits, and the disappointment of the hopes they inspire.

Now population, when it grows, moves with a certain uniform impetus, like a body in motion ; and uniform progress of population, as I have fully explained before, is multiplication in a uniform ratio. But long-continued progress in such a manner is altogether impossible—it must outstrip all physical conditions and bounds ; and the longer it continues, the more severely must the ultimate check be felt. I do not hesitate to say, therefore, that the rapid growth of our great towns, gratifying as it is in the present, is a matter of very serious concern as regards the future. *I do not say that the failure of our coal-mines will be the only possible check.* Changes here, or in other parts of the world, may, even before the failure of our mines, reduce us to a stationary condition, and bring upon us at an earlier period the sufferings and dangers incident to our position. But such a grievous change, if it does not come before, must come when our mines have reached a certain depth.

CHAPTER XI

OF THE CHANGE AND PROGRESS OF OUR INDUSTRY

OUR rapid but one-sided progress may be shown not only in its effects upon the numbers of the population, but also in the kind and extent of our industry.

In the second half of the eighteenth century our population, previously stationary, began to grow at a growing rate. When we consider that at this period the steam-engine was coming into use, that Arkwright's cotton machinery was invented, that the smelting of iron with coal was immensely increasing the abundance of that valuable metal, we cannot hesitate to connect these events as cause and effect. It was a period of commercial revolution. It was then we began that development of our inventions and our coal resources which is still going on. It was

from 1770 to 1780, as Briavoinne thinks, that the commercial revolution took a determined character.¹

The history of British industry and trade may be divided into two periods, the first reaching backward from about the middle of the eighteenth century to the earliest times, and the latter reaching forward to the present and the future. These two periods are contrary in character. In the earlier period Britain was a rude, half-cultivated country, abounding in corn, and wool, and meat, and timber, and exporting the rough but valuable materials of manufacture. Our people, though with no small share of poetic and philosophic genius, were unskilful and unhandy; better in the arts of war than those of peace; on the whole learners, rather than teachers.

But as the second period grew upon us many things changed. Instead of learners we became teachers; instead of exporters of raw materials we became importers; instead of importers of manufactured articles we became exporters. What we had exported we began by degrees

¹ M. N. Briavoinne, *De l'Industrie en Belgique*, Bruxelles, 1839, p. 197.

to import; and what we had imported we began to export.

It is interesting to observe the reversal which then occurred in several of our ancient trades. Wool had been for a long time esteemed the staple produce of the country. We raised the raw material in plenty, but were so unskilful in its manufacture, that all the Acts of Parliament that could be devised, all the arts and watchfulness of the revenue officer, could not prevent it being "run" for the manufacturers of France and Holland. No efforts of the legislature could enable us to compete with foreigners, and mistaken restrictions only contributed to keep the whole country stationary. But when once our manufacturing ingenuity took its natural rise, no more was heard of the "running of wool," and we have since become by far the first and largest woollen manufacturers, consuming not only our own raw wool, but as much as we can buy in Australia, New Zealand, South Africa, South America, and elsewhere.

Again, we had, during the early part of the eighteenth century, imported quantities of fine cotton goods from India, and great was the indignation of Gee and other commercial writers

at this "finger labour" being allowed to interfere with our home industry. No exclusion of such Indian cottons could have promoted the invention of cotton-spinning machinery, which is rather due to the general advance of our skill in mechanical construction. But it is curious to reflect upon the different state of things now, and the enormous quantities of cotton we [and other countries] not only draw from India but return to it in a manufactured state.¹

Corn had been, next to wool, the most esteemed produce of the kingdom. When our population was not one-fifth of its present amount we were able to raise enough for our own use, with a margin over in plentiful years. This margin the Dutch and French merchants readily purchased from us and stored up, often selling it back to us again in periods of dearth. But as corn is not a material of manufacture, its export was regarded very favourably, as bringing treasure into the country, and the whole kingdom looked upon the system of bounties and protective duties, established in 1670, as a piece of skilful political economy. But no sooner had

¹ Of late years, Indian cotton has gone mainly to countries other than Britain.

our population, about 1761 or 1771, begun to increase than our imports of wheat exceeded our exports, and the inward movement of corn was accelerated by the reduction of the protective duties to a nominal amount. Our dependence on foreign corn, however, increased so rapidly, and was so odious to the general feelings of the country, that a restrictive Act was readily passed in 1791. This was the first of the series of Corn Laws which sixty years ago led to so severe a struggle. The effect of restriction is seen in the stationary amount of imports between 1791 and 1830, the increased demands of the population being met by the enclosure of land, and the improvement of tillage. But the necessary result of pushing a very limited country like England to its greatest agricultural capabilities is a comparative rise of the price of food, compared with other articles, and compared with the food of other countries. Thus naturally arose the great Corn Law Question. These facts are apparent in the following table of the average exports and imports of wheat and wheat-meal, expressed in the equivalent amount of grain, during periods of ten years, in the last two centuries.

	Average Annual Exports of Wheat. Quarters	Average Annual Imports of Wheat. Quarters
1701-10	107,116	217
1711-20	112,020	4
1721-30	115,779	11,513
1731-40	290,512	1,307
1741-50	378,452	110
1751-60	272,883	16,229
1761-70	203,365	96,728
1771-80	101,739	130,423
1781-90	110,197	174,728
1791-1800	82,178	568,896
1801-10	37,738	596,087
1811-20	40,087	540,111
1821-30	79,510	560,314
1831-40	157,852	1,077,370
1841-50	66,285	2,892,094
1851-60	128,505	5,031,266
1861-70	189,842	8,391,539
1871-80	403,556	13,277,250
1881-90	288,223	18,092,697
1891-1900	334,745	22,464,357
1901-4	306,018	25,899,918

The exports, it is seen, attained their highest amount about the middle of the eighteenth century, but were never large.¹ Our imports are now increasing beyond all bounds, and even low prices do not stop the influx.² With the

¹ The exports of British and foreign wheat and wheat-meal during 1871-80 exceeded those of any previous decade, largely on account of the exceptional movement of the year 1871, during the Franco-Prussian war. Between 1881 and 1889 a change was made in the estimated yield of flour from wheat.

² The price of 40s. per quarter was named by Jevons here, a price obviously regarded, at the time he wrote, as excessively low. In 1864 the *Gazette Average* price of British wheat was 40s. 2d. Thirty years later it was 22s. 10d., though it was not till 1884 that

above we may contrast the average annual quantities of wheat sold in the several market towns of England and Wales, in the under-mentioned periods :—

	Quarters of Wheat
1815-20	1,119,959
1821-30	2,271,858
1831-40	3,675,134
1841-50	4,012,652
1842-51	5,114,176
1852-61	4,849,130

The returns for the last two periods are given separately because they refer to a larger number of market towns than the previous returns. As the quantities sold do not include by any means the whole of what is grown or used, we cannot draw any accurate conclusions as to the amount of our subsistence; but it clearly appears that our production of wheat has passed its highest point and is declining.¹

it fell below the price of 1864. By 1904 it had reached 28s. 4d., a figure which, though above that of some recent years, is yet lower than that of any year before 1893.

¹ The changes in the number of towns from which returns of sales are obtained have made the record of market sales of even less use, as indicating the fluctuations in home supplies, than if the basis had been unchanged. Inasmuch as, for later years, official estimates of the British crop of wheat are available, no further reference to the recorded market sales of wheat need be made than that they have continued to testify, as far as their evidence has value, to the decline of the home production of wheat. The following table traces the progressive decline of the British wheat crop for half a century. For the first thirty years, the estimates of

Such an extraordinary change in the source of subsistence of the country cannot but be accompanied by many secondary changes. Human requirements are various, and arranged in a scale of subordination. A plentiful supply of corn, creating population, creates also a demand for animal food, for dairy produce, for vegetables and fruit, the home production of which is naturally protected by the cost of carriage. Few or no farmers or landowners, then, who would promptly submit to the necessary changes of culture, could suffer any loss from the influx of foreign corn.

Lawes and Gilbert (cf. *Journal of the Statistical Society*, 1880, and the table in Broomhall's *Corn Trade Year Book* for 1897, p. 80) supply the data, and from 1884 onwards the crop estimates of the Board of Agriculture.

Years. Sept. 1 to Aug. 31	Average Crop. Quarters of Wheat
1852-3 to 1861-2	13,784,000
1862-3 to 1871-2	13,884,000
1872-3 to 1881-2	10,338,000
1882-3 to 1891-2	9,607,000
1892-3 to 1901-2	6,952,000

Probable limits to the average crop in the first half of the century are indicated by the method employed by Porter (*Progress of the Nation*, ed. 1851, p. 143), who considers what addition to the supplies shown by records of foreign trade would be needed to afford an average consumption per inhabitant of six bushels, or of eight bushels. Between these limits the actual consumption probably lay. We thus find—

The home production needed to give a supply of—		
	6 bushels per head.	8 bushels per head.
1801-10	8,226,000 quarters	11,169,000 quarters
1811-20	9,662,000 „	13,036,000 „
1821-30	11,064,000 „	14,930,000 „
1831-40	12,224,000 „	16,628,000 „
1841-49	12,106,000 „	17,004,000 „

This view was urged, in 1845, previous to the repeal of the Corn Laws, in Mr. T. C. Banfield's very excellent Lectures on the Organisation of Labour : " The farmer and the landlord," he said,¹ " are the parties most interested in the rejection of our present Corn Laws, which make wheat a profitable crop at the expense of every other. They ought to be clamorous for their repeal ; for no one can deny that cheapness of corn will increase the demand for every other article of agricultural produce." Similar views had been previously stated in a pamphlet by my father on the subject of the Corn Laws.² And no anticipations could have been more thoroughly fulfilled.

In spite of the vast importations, and the very low price to which corn fell both in 1850-1 and 1862-5, we had few complaints of the farmers' or the landlords' ruin.³ Agriculturists

¹ Page 53.

² *The Prosperity of the Landholders not dependant on the Corn Laws*, by Thomas Jevons, 1840, pp. 7-11.

³ For a dozen years after Jevons wrote this, it continued to be true. As already noted (p. 238) the price of wheat was maintained at a high level for an even longer term of years. The inflation of wheat prices from 1866 to 1874 would check the progress of adaptation to new methods to which Jevons refers on the following page. That adaptation has certainly not been pushed as far and as fast as Jevons hoped. We derive, as is well known, very large supplies of dairy produce from Denmark, where there have been effected just such changes in agricultural methods as are named in the text as likely to save the British farmer from ruin.

were either prosperous, or patient to an extent not to be looked for in human nature. But the fact is, that the substitution of new crops and kinds of culture had been going on very extensively, rendering the price of corn no longer the measure of the farmer's profit.

Of course such changes must be expected to continue with the growth of our population and consumption, until only the richest of our valley lands bear wheat, while the rest of the kingdom is given up to grazing, or to sheep-walks, dairy-farms, and market-gardens. Under our present system of free-trade, the farmer will find his best advantage, not in clinging to old traditions and customs, but in trying to apprehend the tendencies of the time and select those new kinds of culture which will give the best money return.

One extraordinary result of the current changes in our old industry was disclosed by the census of 1861. *It is a positive decrease of our agricultural population,*¹ [a decrease which continued

¹ See the able investigation by Frederick Purdy, Esq., of the Statistical Department of the Poor Law Board, *On the Decrease of the Agricultural Population, 1851-61*, British Association, 1863, p. 157; *Journal of the Statistical Society*, September, 1864, p. 388.

[The continued decrease in our agricultural population has been the subject of memoirs, too numerous to attempt to detail, published during the last twenty-five or thirty years.]

to be manifested progressively at subsequent censuses].

PERSONS EMPLOYED IN AGRICULTURE ¹

1851	1,904,687
1861	1,803,049
1871	1,423,854
1881	1,199,827
1891	1,099,572
1901	988,340

The decrease of agricultural population is partly due to the less labour required in grazing than in tillage. But the employment of horse, water, or steam power in many field operations, as well as in thrashing, chopping, churning, etc., has greatly contributed to the same result. The economy of labour in agriculture affords in this country little or no compensation to the labourer in the extension of employment, because the area of land is limited and already fully occupied. Labour saved is rendered superfluous. It is this that keeps agricultural wages so low; and as steam-power is more and more used upon a farm, the number of labourers will continue to decrease. The only relief for the consequent poverty of the labourer, beyond a poor-house allowance, is migration into a manufacturing town or a prosperous colony.

¹ *British and Foreign Trade and Industry*, Cd. 1761, 1903, p. 363.

In either case the emigrant contributes directly or indirectly to develop our new system of industry, and to render more complete the overbalancing of our ancient agricultural system. Such facts, having been disclosed by the census, are patent to all ; but we cannot too often have brought to our notice *the profound changes they indicate in our social and industrial condition.*

When we turn from agriculture to our mechanical and newer arts, the contrast is indeed strong, both as regards the numbers employed and the amounts of their products. But the subject is a trite one ; every newspaper, book, and parliamentary return is full of it : factories and works, crowded docks and laden waggons are the material proofs of our progress.

[The remainder of the chapter, devoted to setting forth the remarkable rate of progress of manufacturing industry in England for a long period previous to the original publication of *The Coal Question*, has been left [without the changes of phraseology, aimed at making it applicable to the present time, which have been attempted in the earlier part. The constant repetition of phrases, burdening the text with the reiterated reminder that the argument as to the rate of progress was not intended to apply to the entire nineteenth century, seemed less desirable than requesting the reader to bear in mind that the references in the text to the present apply to about 1865, not to 1905, in these few pages. The check in the rate of progress, which occurred in less than twenty years after the publication of Jevons' argument, is indicated in footnotes extending his tables to the present time.]

I shall, therefore, give my attention to the *rate of our progress*, and show that *our trade and manufactures are being developed without apparent bounds in a geometric, not an arithmetic series—by multiplication, not by mere addition—and by multiplication always in a high and often in a continuously rising ratio.*

Next after coal, the production of which we shall consider in the next chapter, iron is the material basis of our power. It is the bone and sinews of our labouring system. Political writers have correctly treated the invention of the coal-blast furnace as that which has most contributed to our material wealth. Without it the steam-engine, the spinning-jenny, the power-loom, the gas and water-pipe, the iron vessel, the bridge, the railway—in fact, each one of our most important works—would be impracticable from the want and cost of material. The production of iron, the material of all our machinery, is the best measure of our wealth and power; and the following statement shows that, from the time when the charcoal bloomary and forge gave place to the coke blast-furnace, the production of iron in England has advanced at a rate alike extraordinary in rapidity and constancy :—

PRODUCTION OF PIG IRON

Year	Pig iron produced Tons	Average increase in ten years Tons	Average annual rate of increase per cent	Rate as for ten years
1740	17,350			
1788	68,300	10,620	3	33
1796	125,079	70,980	8	113
1806	258,206	133,130	7	107
1825	581,367	170,084	4	53
1839	1,243,680	473,081	6	72
1847	1,999,608	944,910	6	81
1854	3,069,838 ¹	1,528,900	6	84
1864	4,767,951 ¹	1,698,113	5	55

¹ *Mineral Statistics*. The amounts for previous years are estimates collected from several well-known works. They are set forth in Scrivenor's work on the Iron Trade. (Cf. *Midland Mining Commission, First Report*, p. xvi; *Report of Coal Commission, 1871, Committee E*, p. 60; *Commission on Depression of Trade, Memorandum* by Sir Lowthian Bell, *Second Report*, part i, p. 320. The writer last-named states that the earlier figures are based on calculations relating to furnaces built, no allowance being made for those out of blast.) The production in later years has been as follows :—

Year	Pig-iron produced Tons	Average increase in ten years Tons	Average annual rate of increase per cent	Rate as for ten years
1854	3,069,838			
1860	3,826,750	1,261,520	4	44
1870	5,963,510	2,136,760	5	56
1880	7,749,230	1,785,720	3	30
1890	7,904,214	154,984	0	2
1900	8,959,691	1,055,477	1	13

There has been, as the table shows, no restoration of the higher rates of increase, though some advance in the annual addition to output was the result of the spurt of trade about 1870.

It is evident that an arithmetical law of increase is totally inapplicable to the above numbers, since the yearly addition increases continuously from little more than 1,000 tons to 170,000 tons, the recent yearly addition. The ratio of increase, on the contrary, has only varied from 3 to 8 per cent. per annum. In the last period, indeed, 1854-64, we observe a fall in the rate, probably temporary, and due to the partial loss of the American trade, in consequence of the enactment of the Morrill tariff.

The same temporary check to the iron trade is more apparent in the following account:—

“EXPORT OF PIG IRON”¹

Year	Tons of pig iron exported	Increase	Rate per cent of increase as for ten years
1801	1,583		
1812	4,066	2,483	136
1821	4,484	418	12
1831	12,444	7,960	177
1841	85,866	73,422	590
1851	201,264	115,398	134
1861	388,004	186,740	93

Our export iron trade commenced but little previous to the beginning of the nineteenth

¹ The exports of pig and puddled iron, of British manufacture, in later years, were :—

century, so that a generation hardly yet passed away saw its rise. Within a period of sixty years the trade, as regards crude iron only, has been multiplied 245-fold. It is in vain to prophesy how much it may yet in future years be further multiplied. Prodigious resources are now being applied to the extension of the iron manufacture, and the present activity of the trade leads us to suppose that any recent dulness will be amply compensated. A single company, that of the Ebbw Vale Iron Works, managed by Mr. Abraham Darby, a descendant of the founder of our iron manufacture, holds 16,306 acres of land, employs more than 15,000 labourers, representing a population of 50,000 persons, produces 130,000 tons of pig iron annually, *with a capability of producing*

Year	Tons of pig iron exported	Increase or decrease	Rate per cent of increase or decrease in ten years
1871	1,057,458	669,454	172
1881	1,482,354	424,896	40
1891	840,055	-642,299	-43
1901	839,182	-873	0

The sign (—) indicates decrease.

The renewed progress of the iron trade shortly after the date of Jevons' latest figures is here more clearly shown. The falling off in the export of the cruder forms of iron has been a natural accompaniment of the development of the higher branches of the industry.

180,000 *tons*, or ten times as much as the whole produce of the country in 1740.¹ But we must almost tremble when we hear that this single company raises 850,000 tons of coal annually, and with a comparatively small outlay are prepared to increase the yield to a million and a half of tons ! Expanding as it does, the iron manufacture must soon burn out the vitals of the country, and it is possible that there are those now living who will see the end of the export of crude iron ; so rapid is the development of the trade that its rise and decline may perhaps be compassed by two lifetimes.

The consumption of timber, as Mr. Porter remarked,² exhibits forcibly the comparative progress of industry. The following table exhibits the quantities of timber, "eight inches square and upwards," of colonial and foreign growth, consumed in the United Kingdom in the years 1801 to 1841, and the total cubic contents of

¹ There is no need to detail the larger figures of production of iron and steel, and of consumption of coal, of the great firms, and consolidations of firms, of the beginning of the twentieth century. The point—of the drain on coal resources which is consequent on the development of the iron trade—is sufficiently illustrated by the figures of forty years ago (cf. also chap. xv). The figures of the preceding table go far to bear out the anticipation of a cessation of crude iron export.

² *Progress of the Nation* 1851, p. 578.

all timber imported in the years 1843, 1851, and 1861 :—

Year	Quantity of Timber Loads	Rate of increase per cent in ten years
1801	161,869	
1811	279,048	72
1821	416,765	49
1831	546,078	31
1841	745,158	36
Year	Total Imports Loads	Rate of increase per cent as for ten years
1843	1,317,645	
1851	2,111,777	80
1861	3,039,503	44

The extraordinary increase between 1843 and 1851 is due to the partial repeal of the timber duties in 1847 and 1848. The more recent rate of 44 per cent is but little below the average rate (50 per cent) obtaining since the beginning of the century.¹

The amount of cotton consumed is a measure of one of the largest branches of our manufacturing system. Excluding from view the extraordinary disturbance in that trade during the

¹ Since 1861 the course of the import timber trade has been as follows :—

Year	Total imports Loads	Rate of increase per cent in ten years
1871	{ 4,358,719 } * 4,600,633	43
1881	5,664,061	23
1891	6,759,739	19
1901	9,193,934	21

* In 1871 timber, sawn, split, etc., unenumerated, was returned for the first time by quantity as well as by value in the trade accounts. The second figure, for comparison with later dates, includes this new item. Furniture, hardwood and veneers, and house frames, fittings, and joiners' work are not included in any of the figures given above.

American Civil War, the following numbers exhibit its rate of progress :—

IMPORTS OF COTTON ¹

Year	Quantity of Cotton imported Pounds	Increase in ten years Pounds	Rate of increase per cent as for ten years
1785	17,992,882		
1790	31,447,605	26,909,446	206
1801	54,203,433	20,687,116	64
1811	90,309,668	36,106,235	67
1821	137,401,549	47,091,881	52
1831	273,249,653	135,848,104	99
1841	437,093,631	163,843,978	60
1851	757,379,749	320,276,118	73
1860	1,390,938,752	633,559,003	96

¹ The imports represented sufficiently well the consumption of cotton up to the early forties. That ceased to be the case subsequently. The following table exhibits the consumption of cotton in the United Kingdom, according to the well-known estimates of Mr. Ellison. Instead of single years, the averages of three consecutive years at decennial intervals are compared.

Middle year o. triennium	Consumption of cotton. Millions of pounds	Increase in ten years. Millions of pounds	Rate of increase per cent in ten years
1820	112'9		
1830	243'2	130'3	115
1840	426'2	183'0	75
1850	625'7	199'5	47
1860	1,022'5	396'8	63
1870	1,073'5	51'0	5
1880	1,328'4	254'9	24
1890	1,618'8	290'4	22
1900	1,674'9	56'1	4

No single branch of production can give an adequate measure of the general growth, because our manufactures not only expand in the case of each article, but also branch out into new kinds of work ever becoming more diverse and elaborate. Let us consider the attempts that have been made to estimate the general aggregate of our exchanges.

For a century and a half the amounts of our imports and exports were expressed according to a tariff of invariable prices fixed in 1694. The *official values* thus obtained have no claim whatever to be considered the real values of the commodities imported or exported, and only furnish a convenient criterion of the increase and decrease of the *aggregate quantity of goods*. The official account of the value of imports from the beginning of the eighteenth century is as follows :—¹

¹ *First Report of the Commissioners of Customs*, 1857, p. 108 (and Porter's Tables for the later years). See the diagram fronting the title-page, in which the divergent character of our progress is shown to the eye by curves representing the numbers of the population, the official value of our imports, and the vend of coal from Newcastle. [The computation of the official value of imports continued to be made to the year 1869. The figures for 1861-69 show an average official value of imports £189,678,967, the increase on the period 1851-60 being at the rate of 49 per cent. in ten years.]

TOTAL VALUE OF IMPORTS

Period of Years	Average official value of imports	Increase	Rate of increase per cent in ten years
	£	£	
1701-10	4,267,464		
1711-20	5,318,450	1,050,986	25
1721-30	6,621,725	1,303,275	25
1731-40	6,992,010	370,285	6
1741-50	6,784,409	-207,601 ¹	-3 ¹
1751-60	7,826,441	1,042,032	15
1761-70	10,025,235	2,198,794	28
1771-80	10,684,426	659,191	7
1781-90	13,543,418	2,858,992	27
1791-1800	20,660,760	7,117,342	53
1801-10	28,809,778 ²	8,149,018	39
1811-20	30,864,670	2,054,892	7
1821-30	39,661,123	8,796,453	29
1831-40	53,487,465	13,826,342	35
1841-50	79,192,806	25,705,341	48
1851-60	130,134,946	50,942,140	64

Low rates of progress varied by retrogression prevailed throughout the greater part of the eighteenth century. Before its termination occurred a great burst of trade, only brought temporarily to a stand by the great Continental wars. Starting from the Peace we observe *a continuous acceleration in the rate of multiplication of our aggregate*

¹ Decrease.

² M'Culloch's *Account of the British Empire*; Darton's *Tables*, p. 30.

imports, the most recent rate being the highest known.

In the year 1855 the system of official values was abandoned in favour of real values. These values are computed in the Statistical Department of the Board of Trade from the actual prices of the commodities as given in mercantile price lists, or furnished by the principal mercantile firms. But the increase of our imports from 1854 to 1864, as measured by their real ascertained values, is even more surprising.¹

Year.	Real value of imports. £	Increase. £	Rate per cent of increase in ten years.
1854 . .	152,389,853 . .		
1864 . .	274,952,172 . .	122,562,319	80

We have accounts of the declared real value of exports from about the commencement of the nineteenth century.

¹ Following the same plan as with the official values of imports we obtain the following series of figures of real values. It may be noted that, from 1870, the system of computed values was in its turn abandoned for that of declared values.

Period of Years	Average value of imports	Increase in ten years	Rate of increase per cent in ten years
	£	£	
1854-60	172,945,365		
1861-70	270,203,020	119,393,635 *	69 *
1871-80	371,358,532	101,155,512	37
1881-90	394,597,657	23,239,125	6
1891-1900	446,045,110	51,447,453	13
1901-05	541,859,958	132,126,017 *	30 *

* As for ten years.

TOTAL VALUE OF EXPORTS¹
(British and Irish Produce)

Period of Years	Average annual declared value of exports	Increase in ten years	Rate of increase per cent in ten years
	£	£	
1801-10	40,737,970		
1811-20	41,484,461	746,491	2
1821-30	36,600,536	-4,883,925 *	-12 *
1831-40	45,144,407	8,543,871	23
1841-50	57,381,293	12,236,886	27
1851-60	106,513,673	49,132,380	86

* Decrease.

After 1860 the amount of our exports was greatly influenced by the revolution in the cotton trade, but a great expansion quickly followed the shrinkage due to the interruption in the supply of that important staple.

The stationary or retrograde condition of our exports, as expressed by the real value, in the earlier part of this century, has been attributed

¹ The later figures of Exports of British and Irish Produce are :—

Period of years	Average annual declared value of exports	Increase in ten years	Rate of increase per cent in ten years
	£	£	
1861-70	166,107,975	59,594,302	56
1871-80	220,448,558	54,340,583	33
1881-90	234,306,947	13,858,389	6
1891-1900	238,046,951	3,740,004	2
1901-05	291,158,333 *	73,331,192 †	31 †

* Exclusive of value of new ships, first returned in 1899.

† As for ten years.

to the restrictive influence of the Corn Laws. But the official values, and other statements of quantities of commodities examined in previous pages, negative this notion. It was due rather to the great fall of prices which was proceeding from about the year 1810 until about 1851. Allowing for the change of prices it may be said, I believe, that the progress of our trade was slow during the great wars, rapid and constant from the Peace to the accomplishment of Free Trade, and greatly accelerated since that event.

The rise of our commerce is strikingly seen in the continuous growth of the port of Liverpool, which soon will be the greatest of all emporiums of trade. The dock accounts extend over a century, giving the number and, since 1800, the tonnage of vessels charged with dock-dues.

The numbers in the table opposite are not so regular as those we might get by taking decennial averages, and yet the rate of multiplication of Liverpool as a port has only varied in a century from 20 to 89 per cent.¹

Accounts of the shipping of the whole kingdom are available from the beginning of the nineteenth century. From them we get the

¹ The following table, prepared from the *Accounts of the Mersey Docks and Harbour Board for the year ending 1st July, 1905*,

PORT OF LIVERPOOL

Year	Number of ships	Tonnage of ships	Rate of increase per cent in ten years
1761	1,319		
1771	2,087	...	58 of ships.
1781	2,512	...	20 "
1791	4,045	...	61 "
1801	5,060	459,719	25 "
1811	5,616	611,190	33 of tonnage.
1821	7,810	839,848	37 "
1831	12,537	1,592,436	89 "
1841	16,108	2,425,461	52 "
1851	21,071	3,737,666	54 "
1861	21,095	4,977,272	33 "

extraordinary results shown on the following page.

Multiplication at a growing rate! So far is our shipping industry from increasing in an

pp. 25-27, shows the progress of Liverpool shipping by decennial intervals during the nineteenth century.

Period of Years	Average annual tonnage	Rate of increase per cent in ten years	Period of Years	Average annual tonnage	Rate of increase per cent in ten years
1801-10	539,314	—	1861-70	5,154,809	20
1811-20	671,892	25	1871-80	6,793,036	33
1821-30	1,171,297	74	1881-90	8,702,984	28
1831-40	1,872,136	60	1891-1900	10,919,808	25
1841-50	2,985,373	59	1901-05	14,423,445	45*
1851-60	4,257,003	43	* Rate as for ten years		

TONNAGE OF BRITISH PORTS ¹

Period of years	Average annual tonnage of ships entering and clearing	Increase	Rate per cent of increase in ten years
	Tons	Tons	
1801-10	3,467,157		
1811-20	4,203,613	736,456	21
1821-30	5,059,522	855,909	20
1831-40	7,175,081	2,115,559	42
1841-50	11,704,796	4,529,715	63
1851-60	20,233,049	8,528,253	73

arithmetical series only, that even a geometrical series does not adequately express its rapid expansion. *The very rate of multiplication progresses.*

But it is the expansion of our ocean steam marine which most fitly represents our mechanical

¹ The figures for later dates are :—

Period of years	Average annual tonnage of ships entering and clearing	Increase	Rate per cent of increase in ten years
	Tons	Tons	
1861-70	30,522,132	10,289,083	51
1871-80	48,555,725	18,033,593	59
1881-90	65,565,248	17,009,523	35
1891-1900	84,931,999	19,366,751	30

These figures of tonnage do not include the coasting trade. The yearly figures show some recovery in the rate of progress at the latest dates.

resources, our commercial requirements, and our maritime supremacy. The following are the amounts of tonnage of steam-vessels belonging to the United Kingdom, beginning with the decennial period following the introduction of steamboats in 1814 :—

BRITISH STEAM VESSELS ¹

Year	Tonnage	Increase of tonnage	Rate of increase per cent in ten years
1821	10,534		
1831	37,445	26,911	256
1841	95,687	58,242	156
1851	186,687	91,000	95
1861	506,308	319,621	171

If we pass over the early period when steam-vessels were quite a novelty, we find that their increase, always extraordinary, has been more rapid even proportionally speaking in the ten years ending in 1861 than in twenty previous

¹ The figures for later dates are :—

Year	Tonnage	Increase of tonnage	Rate of increase per cent in ten years
1871	1,319,612	813,304	161
1881	3,003,938	1,684,376	128
1891	5,307,204	2,303,216	77
1901	7,617,793	2,310,589	44

years. And the extreme success and prosperity of the iron ship-building trade at the present time is the sure indication of the future extension of steam navigation.

When we consider that the system of ocean steam communication is very largely in our hands and supported upon our coal, our pride at its possession must be mingled with anxiety at the enormous drain it directly and indirectly creates upon our coal-mines.

CHAPTER XII

OF OUR CONSUMPTION OF COAL

IN the last three chapters I have tried to make apparent, both from principle and fact, that a nation tends to develop itself by multiplication rather than addition—in a geometrical rather than an arithmetical series. And though such continuous multiplication is seldom long possible, owing to the material limits of subsistence, I have given sufficient numbers to prove that up to the present time (1865) our growth is unchecked by any such limits, and is proceeding at uniform or rising rates of multiplication.

Now while the iron, cotton, mercantile, and other chief branches of our industry thus progress, it is obvious that our consumption of coal must similarly progress in a geometrical series. This, however, is matter of inference only be-

cause until lately the total quantities of coal consumed were quite unknown.

We can trace the progress of the consumption of coal in previous centuries with some accuracy by means of the accounts of the Newcastle and London Coal Trade, which used to be, far more even than it now is, the largest branch of the trade. The total quantities of coal shipped from Newcastle and the neighbouring ports were as follows :¹—

VEND OF COAL FROM NEWCASTLE

Year	Vend from the Newcastle Coal- field	Increase as for fifty years	Rate of increase per cent as for fifty years
	Tons	Tons	
1609	251,764		
1660	537,000	279,643	110
1700	650,000	141,250	27
1750	1,193,467	543,467	84
1800	2,520,075	1,326,608	111
1864	18,349,867 ²	12,367,025	372

The progressive consumption of London for two centuries is seen in the following figures :—

¹ T. J. Taylor, *Archæology of the Coal Trade*, pp. 177 and 204, in *Memoirs of the British Archæological Association*, 1858. See also the diagram facing p. vii. (Plate I).

² Including 7,562,963 tons of railway-borne coal.

COAL IMPORTED INTO LONDON¹

Year	Total quantity of coal imported into London	Increase in fifty years, or as for fifty years	Rate per cent of increase as for fifty years
	Tons	Tons	
1650	216,000		
1700	428,100	212,100	98
1750	688,700	260,600	61
1800	1,099,000	410,300	60
1850	3,638,883	2,539,883	231
1865	5,909,940	7,570,190	404

We see that it is almost impossible to compare the last with previous centuries, and that *the rate of multiplication is in recent years many times as great as during preceding centuries, and is rapidly*

¹ The progress of the London coal trade to the end of the nineteenth century is shown in the following table, which also shows the steps of progress in slightly greater detail than the table in the text.

Year	Total quantity of coal imported into London	Increase in twenty-five years	Rate per cent of increase in twenty-five years
	Tons	Tons	
1775	857,802	169,102	25
1800	1,281,823	424,021	49
1825	1,921,091	639,268	50
1850	3,638,883	1,717,792	89
1875	8,214,357	4,575,474	126
1900	15,746,003	7,531,646	92

The figure for 1800 used here differs from that in the text. It is quoted by Committee E of the Coal Commission of 1871 (*Report*, p. 24) from the *Epitome of the Progress of the Trade in Coal to London*, by J. R. Scott.

*advancing up to the latest returns.*¹ The simple numerical increase is now almost indefinitely greater than it used to be.

As to the total quantity of coal consumed in the whole kingdom the most erroneous notions were entertained even in 1854. Writers on Statistics and the Coal Trade made what they called *Estimates*, by adding together the sea-borne, and a few other known quantities of coal, and then making a liberal allowance *ad libitum* for the rest.

The variations in the estimates made by different authors may be judged from the following statement :²—

	Tons.
R. C. Taylor, <i>Statistics of Coal</i> , 1848 ³ . . .	31,500,000
Braithwaite Poole, <i>Statistics of British Commerce</i> , 1852	34,000,000
J. R. McCulloch, 1854 ⁴	38,400,000
T. Y. Hall, <i>A Treatise on the Extent and probable Duration of the Northern Coal-field</i> , 1854	56,550,000
The same, quoting "a particularly careful writer on the subject of the Coal Trade" .	52,000,000
Joseph Dickinson, Inspector of Coal Mines, in his <i>Report</i> , 1853	54,000,000

¹ The increase in the half-century following 1850 being 333 per cent, the substitution of the figures of 1900 for those of 1865 in the table would not contradict the statement of the text.

² *Mineral Statistics for 1855*, Introd., p. vi.

³ The estimate is for "about 1845-6" (*loc. cit.* p. xvii).

⁴ *Statistical Account*, vol. i, p. 599. This later estimate is substituted for the one given in the *Mineral Statistics*.

In 1854 was begun the system of Mining Records¹ and Statistical Inquiry, recommended by Mr. Sopwith with reference to our present subject, and carried into practice by Mr. Robert Hunt, with the assistance of the Government Inspectors of Coal Mines, and the voluntary co-operation of the Carrying and Mining Companies. The following are the amounts of coal ascertained to have been raised from our coal-mines :—²

Year.	Tons.
1854	64,661,401
1855	61,453,079
1856	66,645,450
1857	65,394,707
1858	65,008,649
1859	71,979,765
1860	80,042,698
1861	83,635,214
1862	81,638,338
1863	86,292,215
Total 726,751,516	

Since the first edition of this work was published it has been found that the returns from South Staffordshire were under-estimated, owing to a misapprehension of the size of the Staffordshire ton and boat-load.

¹ Proposed long ago by Mr. Chapman. See Holmes, *Treatise on the Coal Mines of Durham and Northumberland*, London, 1816, p. 218.

² *Statistical Abstract for the United Kingdom*, 1864, p. 91.

The correct amounts of coal produced during the years 1861–1864 are as follows :—

Year.	Tons.
1861	85,635,214
1862	83,638,338
1863	88,292,515
1864	92,787,873

By adopting the new numbers I might slightly strengthen my conclusions, but I do not think it worth while to make the necessary alterations.¹

The quantity of small coals consumed upon the colliery waste-heaps is not included in the above, and is unknown. Mr. Atkinson, inspector of the coal-mines of Durham, south of the Wear, estimated the waste in his district in 1860 at 2,404,215 tons ; but Mr. Dunn, inspector for Cumberland, Northumberland, and the rest of Durham, considered the waste in his district to be only 834,117 tons.² The discrepancy of these estimates is so great and obvious that there appeared in the *Mineral Statistics for 1862*³ the following note :—“The amount of coals burnt or wasted at pits has been so differently represented, and appears such an uncertain although very large quantity, that it is for the present

¹ For a consideration of the production in later years, see note at end of chapter.

² *Mineral Statistics for 1860*, p. 99.

³ P. 68.

omitted." We may conjecture it to be at least five millions of tons in the whole. But the uncertainty does not affect our subject much, because before long this deplorable waste of coal must come to a natural end.

We see that without considering the waste the lowest of the amounts of coal consumed (1854-1863) exceeds, by eight millions of tons, the largest previous estimate of our consumption, that of Mr. T. Y. Hall, writing in 1854; while the estimates of Poole, McCulloch, and R. C. Taylor are hardly more than half the true amount. With such facts before us we cannot place much credit in previous estimates, but I give such as I have met with.¹

Year.		Tons.
1819.	R. C. Taylor, <i>Statistics of Coal</i>	13,000,000
1829.	Mr. Hugh Taylor, evidence before Committee of House of Lords	15,580,000
1833.	J. Marshall, <i>Digest of Parl. Accounts</i> , p. 237 .	17,000,000
1840.	J. R. McCulloch, <i>Dictionary of Commerce</i> . .	30,000,000
1845.	Ditto	34,600,000

I much prefer to reject all such estimates, and argue only upon the undoubted returns of the Mining Record Office, given on p. 265. We of

¹ The following additional estimates, quoted by Mr. Mundella in a paper read before the Statistical Society in 1878 (cf. *Journal*, p. 109), further illustrate the variety and confusion of early estimates. Figures for the eighteenth century, quoted by Mr.

course regard, not the average annual arithmetic increase of coal consumption between 1854 and 1863, which is 2,403,424 tons, but *the average ratio or rate per cent of increase, which is found by logarithmic calculation to be 3·26 per cent.* That is to say, the consumption of each year, one with another, exceeded that of the previous year as 103·26 exceeds 100.

We cannot help perceiving, however, that the consumption of coal is variable, and dependent upon the fluctuating activity of trade. The year 1854 presents a maximum; for the consumption falls off next year from $64\frac{1}{2}$ millions to $61\frac{1}{2}$, and suffers no great increase until 1859. There is then a very rapid rise up to a second maximum in 1861. We are uncertain when the consumption will again reach a maximum, and under these circumstances *it is better to compare the* Mundella, appear to be merely four times the vend from Newcastle in the corresponding years.

Year.	Tons.
1803. Mr. Buddle's evidence before House of Lords	10,808,046
1816. Statistics and calculations of Samuel Salt	27,020,115
„ Report of deputation from the Wear	15,634,729
1829. Mr. Hugh Taylor (apparently with addition of exports) foreign and correction of exports to Ireland) . . . }	16,034,799
1839. J. R. McCulloch	31,024,417
Henry T. de la Beche	36,000,000
1846. J. Emerson Tennant	36,400,000

To which may be added—

1855. J. R. McCulloch	58,200,000
---------------------------------	------------

Most of these estimates are referred to in the report of Committee E of the 1871 Coal Commission (*Report*, pp. 46, 61, 62).

consumption of the two years of maxima, 1854 and 1861, assuming that they are years of a certain correspondent activity. The average rate of increase in the interval is 3·7 per cent, and the comparison of the years 1854 and 1864 would give almost exactly the same result; but in our succeeding calculations I will assume that the *average annual rate of growth of our coal consumption is $3\frac{1}{2}$ per cent—or the ratio of growth is that of 103·5 to 100.*

This is equivalent to a growth in ten years of 41 per cent, or in fifty years of 458 per cent, or $5\frac{1}{2}$ -fold.

Such are the critical numbers of our inquiry.

If we assume the consumption of coal to have grown to its present (1863) amount, at the uniform rate of $3\frac{1}{2}$ per cent, and calculate its former probable amounts backwards, we find no accordance with former estimates, of the error of which we were already well assured (p. 267).

Year.	Estimated amount.	Calculated amount.
1819	13,000,000	18,993,000
1829	15,580,000	26,792,000
1833	17,000,000	30,744,000
1840	30,000,000	39,115,000
1845	34,600,000	46,456,000

But it is worthy of notice that Mr. Hull, when briefly reviewing the consumption of coal, con-

jectured the true amount probably not to exceed 10 million tons at the beginning of the century, and to be about 36 million tons in 1840.¹ Now these estimates agree well with the amounts we should arrive at from our assumed rate of growth.

Year.	Hull's conjecture.	Calculated amount.
1801	10,000,000	10,225,000
1840	36,000,000	39,115,000

The following are the calculated probable amounts of coal used at decennial intervals as far back as it is safe to assume that the present high rate of progress existed ; that is, to the time of the introduction of Watt's engine, the pit-coal iron furnace, and the cotton factory :—

Year.	Probable consumption. Tons.
1781	5,139,000
1791	7,249,000
1801	10,225,000
1811	14,424,000
1821	20,346,000
1831	28,700,000
1841	40,484,000
1851	57,107,000

If we take the consumption of 1852 and 1853 as the same as that of 1851, and the consumption in each period of ten years as uniformly the same

¹ *The Coal Fields of Great Britain*, 2nd ed., pp. 28, 236. The estimate quoted by Mr. Mundella and the Committee of the 1871 Commission as that of de la Beche is apparently the same as that here assigned by Jevons to Mr. Hull. It is quoted by the Commission from the *Report on the Geology of Cornwall, Devon and West Somerset*, 1839.

as that of the first year, we easily get the following :¹—

	Tons of coal.
Probable consumption, 1781-1853	1,436,991,000
Actual consumption, 1854-1863	726,751,516
Total consumption, 1781-1863 . .	<u>2,163,742,516</u>

We cannot but be struck by the fact that *the consumption of the last ten years is half as great as that of the previous seventy-two years!* But we gain little notion from the above of the total quantity of coal already burnt or wasted in these

¹ The estimate of Committee E of the 1871 Commission was that the average annual production of coal during the first half of the nineteenth century was 40 millions of tons, and the aggregate of coal extracted in the half-century, 2,000 million tons (*Report*, p. 61). They gave, as the production of 1800, 10,080,300 tons, thus substantially agreeing with the figure arrived at by Jevons. They estimated that, from 1660 to 1800, the production was 700 million tons, and, between 1500 and 1660, not less than an average of one million tons yearly, thus obtaining an estimate of output, for three centuries preceding 1800, of 850,000,000 tons (*Report*, p. 32). The aggregate production of 1854-69 was 1,343,723,705 tons (*Report*, p. 66).

The recent Commission's report shows the aggregate production of 1870-1904 to have been 5,927,340,291 tons (*Final Report*, part xi. p. 81).

The average output of 1801-50, as computed by Jevons, was only about 22 million tons, as compared with the estimate of 40 millions by the Commission.

In order to arrive at an average of 40 millions, beginning with 10 and ending with a figure which would lead up to the actual output returned for 1854, it would be necessary to assume, early in the century, a rate of increase in production much above $3\frac{1}{2}$ per cent per annum, followed by a slower rate as the middle of the century was approached. There seems no adequate reason for assuming that the most rapid increase occurred early in the century.

islands. An incalculable waste of coal has been going on throughout the period reviewed, both as regards the slack burnt at the pit-mouth, and the many times greater quantity of small or large coal left behind in the pit by prodigal modes of mining, which coal cannot for the most part be recovered. And then previous to 1781 there had been a very considerable and more stationary consumption of coal, especially in Northumberland, Staffordshire, and at Whitehaven, during four or five centuries.

But let us now approach the main point of our inquiry, and follow the future probable consumption of coal. Assuming the present rate of growth, $3\frac{1}{2}$ per cent per annum, to hold, it is easy to calculate the amounts of coal to be consumed in the undermentioned years, starting from the actual consumption of 1861 :¹—

In the year	Consumption at the assumed rate of increase.		
1861	83·6	millions of tons.	
1871	117·9	"	"
1881	166·3	"	"
1891	234·7	"	"
1901	331·0	"	"
1911	466·9	"	"
1921	658·6	"	"
1931	929·0	"	"
1941	1,310·5	"	"
1951	1,848·6	"	"
1961	2,607·5	"	"

¹ These numbers are represented to the eye in the diagram

The total aggregate consumption of the period of 110 years, 1861-1970, would be 102,704,000,000 tons.¹ Or, if it be objected that 1861 was a year of maximum consumption, we may reduce the above sum in the proportion of 83·6 millions to 80 millions, the average consumption of the five years 1859-63. We thus get 98,281,000,000 tons; or, in round numbers, we may say, always hypothetically,—*If our consumption of coal continue to multiply for 110 years at the same rate as hitherto, the total amount of coal consumed in the interval will be one hundred thousand millions of tons.*

We now turn to compare this *imaginary* consumption of coal with Mr. Hull's estimate of the available coal in Britain, viz., *eighty-three thousand millions of tons within a depth of 4,000 feet.*²

facing page vii. For a consideration of the relation of the above table to actual experience as to production in the forty years since this book was written, see note at the end of the chapter (p. 279).

¹ The sum of the geometrical series, in millions of tons,

$$83\cdot6 \left\{ 1 + 1\cdot035 + (1\cdot035)^2 + \dots + (1\cdot035)^{109} \right\}$$

or, which is exactly the same, the value of the definite integral

$$\int_0^{110} 82\cdot17(1\cdot035)^t dt$$

in which the constant 82·17 has been determined so that

$$\int_0^1 82\cdot17(1\cdot035)^t dt = 83\cdot6.$$

² See pp. 24-28.

Even though Mr. Hull's estimate be greatly under the true amount, we cannot but allow that —*Rather more than a century of our present progress would exhaust our mines to the depth of 4,000 feet, or 1,500 feet deeper than our present deepest mine.*

I have given reasons for believing that if all our coal were brought from an average depth of some 2,000 feet,¹ our manufacturers would have to contend with a doubled price of fuel. If the average depth were increased to 4,000 feet, a further great but unknown rise in the cost of fuel must be the consequence.

But I am far from asserting, from these figures, that our coal-fields will be wrought to a depth of 4,000 feet in little more than a century.

I draw the conclusion that I think any one would draw, that *we cannot long maintain our present rate of increase of consumption ; that we can never advance to the higher amounts of consumption supposed. But this only means that the check to our progress must become perceptible within a century from the present time ; that the cost of fuel must rise, perhaps within a lifetime, to a rate injurious to our commercial and manufacturing supremacy ; and the conclusion is inevit-*

¹ See p. 87

able, that our present happy progressive condition is a thing of limited duration.

I may here notice that the exact amount of our stock of coal is not the matter of chief moment. The reader who thoroughly apprehends the natural law of growth, or multiplication in social affairs, will see that the absolute quantity of coal rather defines the height of wealth to which we shall rise than the period during which we shall enjoy either the growth or the climax of prosperity. For; as the multiplication of our numbers and works proceeds at a constant rate, the numerical additions, as we have fully seen in many statistical illustrations, constantly grow. Ultimately the simple addition to our consumption in twenty or thirty years will become of moment compared with our total stores. The addition to our population in four years now (1865) is as great as the whole increase of the century 1651-1751, and the increase of coal consumption between 1859 and 1862 is equal to the probable annual consumption at the beginning of this century. It is on this account that I attach less importance than might be thought right to an exact estimate of the coal existing in Great Britain. Were our coal half as abundant again as Mr. Hull states, the effect would only be

to defer the climax of our growth perhaps for one generation. And I repeat, *the absolute amount of coal in the country rather affects the height to which we shall rise than the time for which we shall enjoy the happy prosperity of progress.*

Suppose our progress to be checked within half a century, yet by that time our consumption will probably be three or four times what it now is; there is nothing impossible or improbable in this; it is a moderate supposition, considering that our consumption has increased eight-fold in the last sixty years. But how shortened and darkened will the prospects of the country appear, with mines already deep, fuel dear, and yet a high rate of consumption to keep up if we are not to retrograde.

Doubts have been expressed by Mr. Vivian, Mr. Hull, and others, as to whether the number of our mining population and the area of our coal-fields will admit of any further great extension of our yield. It is said that underground hands must be born and bred to the occupation of coal-mining; and if we consider that many children of miners may be induced to emigrate, or to avoid their fathers' occupation on account

of its hardship and danger, there may be a positive lack of hands. Facts utterly negative such a notion. The Census returns show the number of coal-miners to have been—¹

In 1851	183,389
And in 1861	246,613

The increase is at the rate of 34·4 per cent in ten years, or about 3 per cent per annum, which accords well with the rate of increase of coal raised, if we remember that the use of machinery, and the increased investment of capital in coal-mining, enlists greater resources and involves greater cost than is expressed in the mere number of miners.

The notion, again, that there is anything in the area or condition of our coal-fields to prevent a present extension of the yield is completely

¹ The Board of Trade Memoranda, etc., on British and Foreign Trade and Industry (Cd. 1761), gives the following numbers of males engaged in coal-mining (p. 363).

1851	189,647	1881	380,471
1861	266,820	1891	515,877
1871	311,792	1901	646,279

The classification of occupations which afforded the numbers in the text would appear to differ in some minor degree, negligible for the present purpose, from that which yields the series just quoted. The slowest growth in these numbers occurred, it will be noted, between 1861 and 1871. In the interval 1881–91 the increase again exceeded one-third.

contradicted by accounts of the number of collieries existing in the United Kingdom.¹

Year.	Number of collieries.
1854	2,397
1855	2,613
1856	2,829
1857	2,867
1858	2,958
1859	2,949
1860	3,009
1861	3,025
1862	3,088
1863	3,180
1864	3,268

The general increase is at the rate of 36 per cent in ten years, or 3·1 per cent per annum. Nearly the same average rate of increase is shown in the number of pits in the Northumberland and Durham coal-field, which were 41 in number in 1799² and 289 in 1864.

¹ Mineral Statistics, *passim*. The table of numbers of collieries in the United Kingdom, quoted by Committee E of the 1871 Commission (*Report*, p. 65) from the Mineral Statistics, includes a considerably larger number of collieries in 1854 and 1855 than the table in the text shows. The figures of the Commission show an increase of 31 per cent in the ten years 1854-64. The number of collieries reported for 1875 was 4,501, the highest number for any year. The number has fallen back to about the figure reached when Jevons wrote, but the decrease of the number of collieries at work has not brought with it a diminished output in proportion. Deeper shafts need larger outputs to make them paying investments. For this and other reasons, modern collieries are larger than those of 1865.

² P. Cooper, *Mining Journal*, Jan. 21, 1865.

If we consider that new pits opened are deeper and larger concerns than the old pits laid in, and capable of much larger yields, we must allow that the coal-owners, at least, both expect and are prepared to meet a largely increased demand for a good many years to come. But we should remember that the more rapid and continued our present expansion, the shorter must be its continuance.

NOTE ON THE REALISED INCREASE OF COAL CONSUMPTION

The comparison of the amounts which, as shown by Jevons' calculations, would need to be produced in order to maintain the rate of increase at $3\frac{1}{2}$ per cent per annum, with the actual production at the beginning of the twentieth century, shows that the check to the continued uniform progress which he declared must come within a century at most, has made itself felt much sooner. It has been maintained that a progressive diminution in the rate of increase of production is demonstrated, and Mr. R. Price-Williams laid elaborate calculations before each of the Royal Commissions, based on this assumption. The rate of increase has, however, not diminished

continuously, but appears to be in process of recovery after a depression. Thus, taking the output of the last five decennia, we find—

Period of Years	Average annual production of coal	Increase in ten years	Average rate of increase per cent per annum
	Tons	Tons	
1855-64	76,428,198		
1865-74	112,140,110	35,711,912	3·90
1875-84	145,009,287	32,869,177	2·60
1885-94	172,732,526	27,723,239	1·76
1895-1904	214,337,139	41,604,613	2·18

Here decennial averages are taken, so as to avoid the risk of comparing a year of advancing prosperity with a year of declining activity, and the rate of increase obtained by Jevons from the comparison of single years is even exceeded. Apparently the rate of increase fell off by about one-third in each decennium, thus producing a rate of progress even less than that given by an arithmetical progression. But the decline has not been maintained, and the facts of the last thirty years suggest rather a rate rising and falling rhythmically, and fluctuating about a level which is itself not declining with such certainty as to justify calculations as to the rate at which it declines, and the time at which the production,

one year with another, will cease to increase. The following indicates the present level of the average rate of annual increase of coal output :

	Tons.
Average production, 1874-84 . . .	143,334,816
„ „ 1894-1904 . . .	211,968,083
Increase in twenty years . . .	68,633,267
Rate of increase per cent per annum . . .	1.975

A rate of 2 per cent per annum will therefore agree closely with the average results of the last thirty years, and, inasmuch as the last ten years of the thirty show a higher rate of increase over the preceding ten years than 2 per cent per annum, we cannot confidently predict that a lower rate will be found in the immediate future.

But the force of the argument set forth by Jevons, to show that the rate of $3\frac{1}{2}$ per cent per annum could not be maintained for even a century, is practically undiminished when applied to the lower rate of 2 per cent, which has been the average of recent experience. His warnings have been put aside, because a mistaken impression was encouraged, by some who might have been expected to appreciate his point accurately, that it was bound up with a prophecy that the consumption of coal would reach certain large figures contained in the present chapter. In reality he argued that those figures could not be

reached so far as concerned the more distant future, though he was unable to discern the changes which would prevent the attainment of those connected in his table with the dates of the nearer future. He ventured on something resembling a forecast of what would, as well as of what could not, happen, when he referred to the output of half a century later being three or four times as great as at the date of writing (p. 276). An annual increase of 2·22 per cent per annum would give a production trebled in fifty years. It would thus seem to be clear that he did not look for the maintenance of the rate of $3\frac{1}{2}$ per cent for even the greater part of half a century.

Let us see how his method applies to the modified rate of 2 per cent, or, rather, of $2\frac{1}{2}$ per cent in ten years, the equivalent of 1·975 per cent per annum. Take, as starting point, the figure of 145 million tons, the average output of the ten years 1875-84, and we obtain the following:

For the ten years ending	The average yearly production at the assumed rate of increase would be	
1884	145·0	millions of tons.
1894	176·2	„ „
1904	214·1	„ „
1914	260·1	„ „
1924	316·0	„ „
1934	383·9	„ „
1944	466·5	„ „
1954	566·8	„ „

The figure 176·2 compares with the actual 172·7, in a decade including the year 1893, when the output fell some twenty million tons below the normal. The figure 214·1 compares with the realised 214·3. A century hence, at this rate, the average annual output would be 1,500 million tons. The table shows that the attainment of figures of output, which may be at once declared impossible, does not depend on the selection of the rate of $3\frac{1}{2}$ per cent, but on the maintenance of a steady geometrical progression. At 2 per cent per annum advance, the output of the half century ending 1954 would be 19,933 million tons, and of the succeeding half century 52,776 million tons, together 72,709 million tons. With an estimated store of 140,000 million tons in proved and unproved coal-fields at depths down to 4,000 feet, it is sufficiently clear that a rate of progress which would exhaust more than the half of this store in a century cannot be long maintained. It may be readily admitted that the period of the introduction of the steamship, and such improvement of the steam-engine as permitted its ever widening application in industry, was a period when an unusual rate of increase in coal consumption might be expected. A rate somewhat below that attained at such a period

might not signify a cessation of such prosperity as accompanied its high rate. But can any contention of equal force be set forth in reference to the comparison of the future with the present? Must not the inevitable slackening of the rate of increase of our coal consumption involve either a decrease of national prosperity, or a change in the nature of the industries on the domination of which in our national life that prosperity has been built up?

CHAPTER XIII

OF THE EXPORT AND IMPORT OF COAL

It has been suggested by many random thinkers that when our coal is done here, we may import it as we import so many other raw materials from abroad. "I can conceive," says one writer, "the coal-fields of this country so far exhausted that the daughter in her maturity shall be able to pay back to the mother more than she herself received. May we not look forward to a time when those 'water-lanes' which both dis sever and unite the old and new world, shall be trod by keels laden with the coal produce of America for the ports of Britain? and in such a traffic there will be abundant use for vessels as capacious and swift as the *Great Eastern*."

I am sorry to say that the least acquaintance with the principles of trade, and the particular circumstances of our trade, furnishes a complete negative to all such notions. *While the export*

of coal is a vast and growing branch of our trade, a reversal of the trade, and a future return current of coal, is a commercial impossibility and absurdity.

But why, it may be asked, can we now export millions of tons of coal, and distribute them to all the ports of the globe, and yet cannot hope to bring back our lost riches in the improved vessels of the future? We have been able to reverse the woollen, linen, and cotton trades; to import the copper and tin and lead¹ ores, which we used to draw from our own veins; to buy our supplies of food—wheat, dairy produce, butcher's meat, and eggs from abroad; and, even in such a bulky material as timber, to replace our own oak and elm and beech by the deal and pine, mahogany and teak, of distant forests. If by our manufacturing skill we can thus successively reverse every great trade, buying raw materials with finished goods, instead of finished goods with raw materials, why not also reverse the coal-trade? Is not Free Trade the sheet anchor that will never fail us? Unfortunately not. *There is a false step of analogy in such reasoning.* Mark what accompanies the reversal of each branch of

¹ And, more recently, iron ores as well in large and increasing quantities.

commerce—it is the increased employment of coal, and coal-driven labour at home, in the smelting-furnace or the factory. *The reversal of every other branch of trade is the work of coal, and the coal-trade cannot reverse itself.* And the facts which may be adduced concerning the coal-export trade so strikingly illustrate the importance of our coal-mines to our maritime and commercial position that I shall give, at some length, arguments which demonstrate, more than sufficiently, the impossibility of importing coal.

Trade is manifestly reciprocal, and free trade only allows the development of any peculiar excellence, or advantage, and the exchange of the products for those more easily procured elsewhere. One most peculiar advantage is the power which coal, skilfully used, places at our disposal. It is our last great resource—the one kind of wealth by the sufficient employment of which we might reverse every other trade, draw every other material from abroad until the kingdom was one immense Manchester, or one expanse of “Black Country.” But take away that resource, and our expectations from free trade must be of a very minor character. “Easy access to the raw material,” said Mr. Glad-

stone, "and abundant supplies of fuel, lead to the creation of manufactures. Put these two conditions together, and you have the combination which makes South Lancashire a busy manufacturing county, with the great town of Liverpool behind it." But observe that the fuel of South Lancashire is a condition as well as the raw material from abroad.

The truth is that the presence of coal as well as other raw materials in Pennsylvania, Prussia, or New South Wales, or its discovery in Brazil or elsewhere, must result in making the whole cost of freight a premium upon establishing the system of coal-supported industry on the spot. Even the narrow seas of St. George's and the English Channels are impassable by coal-driven industry. Ireland, especially Dublin, has drawn coal from Whitehaven time out of mind, for domestic purposes and local manufactures. But the practical non-existence of coal-mines in Ireland has rendered it impossible for any branch of manufacture consuming much coal to exist there. If a work paid at all in Ireland, there must be a margin of profit in transferring the work to an English coal-field. Similarly, it is explained in a very able Report¹ upon the coal-

¹ *Situation de l'Industrie Houillère en 1859*, p. 8.

trade of France in 1859, that no great branch of coal-consuming industry could ever arise in France upon English coal.

"We cannot expect," says the reporter, M. Rouher, "to make foreign coal the basis of a great branch of industry. Coal is a cumbersome commodity, and its cost is doubled or tripled by lading and unlading, and conveying it 100 or 200 miles. To demand coal from England and compete with the products raised upon English coal-fields is manifestly to place ourselves in an inferiority. About two tons and a half of coal, for instance, are required to produce one ton of cast iron. It is much easier to draw our cast iron direct from Glasgow, than to transport a weight of coal two and a half times greater. It requires two or three tons of coal to convert cast iron into wrought iron; that is to say, five tons at least are needed to make wrought iron from the ore. It is most economical, then, to demand from England the finished article."

No one will properly understand the trade in coal who forgets that coal is the most bulky and weighty of all commodities. In this, as in other respects, it stands wholly by itself. No other commodity at all approaches it in the vast quantity required, and it is even said that the weight

of coal carried over English railways is double the weight of all other merchandise put together.¹ The cost of carriage is the main element of price everywhere except in the coal-field, or its close neighbourhood. The best coal is *put on board* at Newcastle for 9s. or 10s. per ton. Before it reaches France [its value is increased by one-half]; to the Mediterranean ports, Genoa, or [Marseilles, to Alexandria or the ports of the Baltic, the freight amounts ordinarily to 5s. or 6s. per ton. In the ports of Brazil or Argentina, the value of Welsh coal is about the double of its cost when shipped,] while in some remote parts of the world coal cannot be purchased for less than £3 or £3 10s. per ton.

To go back to the suggestion with which we started, that our coal supplies will some time be imported from America, let us consider that about 1,200 colliers, [each carrying 10,000 tons of coal, and making a voyage out and home every month,] would be required to maintain our present (1905) supplies only. [The entire tonnage of our mercantile marine would scarcely suffice for the trade, while the entries of shipping at our ports, due to this trade alone, would raise the figures of entries in our oversea trade to treble their present total

¹ *Situation de l'Industrie Houillère en 1859*, p. 53.

from] every part of the world. The cost of such an enormous fleet would be the weight acting against us and in favour of American industry. And as all the colliers, railways, and canals cannot supply London with coal much under 17s per ton, it is extravagant to suppose that coal could reach us from America for less. Our industry would then have to contend with fuel, its all-important food, *three or four times as dear as it now is in England and America.*

The complete commercial absurdity of the supposition renders any more accurate calculations superfluous.

But it is asked, How is a large export trade of coal possible, if an import trade is commercially impossible? This export trade is far the most weighty and widespread trade in the world. [Though it is carried on most actively with the countries of Europe, it extends to the Pacific as well as the Atlantic coast of America, it reaches South Africa, and extends across the Indian Ocean to Singapore and eastward to China and Japan.]

In short, excluding some of the extremely distant North Pacific ports, it may be said that British coal is bought and consumed in every considerable port in the world. It competes on

equal terms and gives the price to native coal or other fuel, in nearly all maritime parts of the world.¹ This extraordinary fact is partly due to the unrivalled excellence of Newcastle and Welsh steam-coals, and the cheapness with which they can be put on board ship. But *it is mainly due to the fact that coal is carried as ballast, or makeweight, and is subject to the low rates of back-carriage.*

The subject of the variation of freights and their influence on the currents of trade is a very curious one, but has been so overlooked by writers on trade and economy, that I may be pardoned giving a few illustrations of its nature and importance.

Whether the mode of conveyance be by vessel, canal-boat, waggon, carriage, or pack-horse, the vehicle is always required to return back to the place whence it started. The whole gains of a trip must on the average pay all expenses and leave a margin for profit, but it is immaterial

¹ The development of local sources of supply in Australia and New Zealand, India and Japan, has reduced the importance of the British coal trade in the regions affected by these supplies. If we understand by competing on equal terms a competition in which price is duly related to quality, the lapse of forty years has not destroyed the truth of the statement in the text. For purposes for which quality is a consideration subordinate to price, British coal has had to yield the field to native supplies, or supplies from near-by sources.

whether the necessary fare or freight-charges be paid on the whole or any part of the journey. Usually, a hackney coach, post-chaise, or canal-boat starts full, upon its outward trip, without calculating upon any return fare. In hackney-coach regulations the return fare is usually fixed at half the chief fare, but in the case of post-chaises, canal-boats, and perhaps some other conveyances, the return fare is usually the perquisite of the drivers. In the old mode of pack-horse conveyance the same was probably the case.

The advantage of gaining something by a return journey is so obvious that journeys are often planned to allow of profitable return freights. For instance, in the days of pack-horse conveyance, Sir Francis Willoughby built Wollaton Hall, in 1580, of stone brought on horseback from Ancaster in Lincolnshire, thirty-five miles away, but it was arranged that the trains of pack-horses should load back with coal, which was taken in exchange for the stone. And when efforts were made at the beginning of the nineteenth century to bring Staffordshire coal to London in order to destroy the previous monopoly of the northern coal-owners, it was expected that the expense of canal conveyance

would be reduced by the back-carriage of manure from London thirty or forty miles up the country, and of flints all the way from Harefield to the Potteries.¹

The railway tolls on goods traffic, again, are not fixed at an uniform rate per ton or per cubic foot, as might seem most fair and simple, but are adjusted in a complicated tariff so as to encourage as large a traffic as possible and give the best return. And one chief principle of this is to encourage back-traffic by low or almost nominal rates. Trucks carrying various materials into towns may be used to carry manures and refuse out. Waggons carrying coals in one direction may carry back ores, slates, bricks, building-stone, flints, limestone, etc.

But it is in oversea conveyance that we find the most important instances of the arrangement of freights.

In the year 1325 a vessel is recorded to have brought corn from France to Newcastle and to have returned laden with coal. This is one of the earliest notices of the coal trade, but it furnishes the exact type of what it has ever since been, a simple exchange of cargoes. And King Charles seems to have been intelligently aware

¹ *Second Report on the Coal Trade*, 1800, p. 22.

of the reciprocal nature of the coal trade when at Oxford, in November, 1643, he wrote to the Marquis of Newcastle to send a vessel full of coals to Holland and get much-needed arms in return.¹

The following is perhaps the most remarkable example of an exchange of freight :—"In Cornwall there exist mines of copper and of tin, but none of coal. The copper ore, which requires the largest quantity of fuel for its reduction, is conveyed by ships to the coal-fields of Wales, and is smelted at Swansea, whilst the vessels which convey it take back cargoes of coal to supply the steam-engines for draining the mines, and to smelt the tin, which requires a much less quantity of fuel for that purpose."² In this way the copper-smelting trade has been carried across an arm of the sea and settled in a place where there is no copper ore, by the joint attraction of cheap fuel and gratuitous carriage. Vessels must have conveyed coals to the Cornish engines whether they brought back ores or not, and to carry coals for copper smelting, too, would require a second fleet of vessels.

The whole coasting trade of the British coasts

¹ Brand's *History of Newcastle*, vol. ii, p. 286.

² Babbage in *Barlow's Cyclopædia*, 1851, p. 55.

is, and always has been, greatly dependent on coal.¹ Coasters going to any point of the coast to bring away slates, stone, lime, agricultural produce, etc., go out from Liverpool, Cardiff, the Clyde, Newcastle, or other large ports, with a cargo of coals, which everywhere meets a ready sale. Double freights are thus ensured.

In many cases a more complicated circle of traffic is established. Vessels bringing iron from Cardiff to Liverpool, on its way to America, often go on with Lancashire coal to Ulverston, and return to Cardiff with the hæmatite ores required for mixture with the Welsh argillaceous ores. Vessels, again, carrying slates or stone to Bristol from the Welsh quarries often take steam-coal to Liverpool and return to the Welsh coast with bituminous coal for household use, the difference of quality being sufficient to establish an exchange trade. By such natural arrangements, not only are the great currents of industrial traffic bound together into one

¹ In the early seventies the amount of coal shipped coastwise by sea was almost as great as that shipped abroad. In 1903 between 19 and 20 million tons of coal were shipped coastwise from ports in the United Kingdom, the total clearances with cargoes coastwise being about 31 million tons. These figures show how large the relative importance of coal in coastwise traffic still remains. Inclusive of bunker coal, the coastwise coal trade is now of about one-third the magnitude of the foreign coal trade.

profitable whole, but coal is supplied cheaply to all parts of the coast, where it is landed at the nearest convenient place to a village, or group of villages, and retailed from a central coal-yard. The household coal, with smith's small coal, culm for lime-burning, draining-tiles, and a few other articles, form the only common and general coasting cargoes. On the other hand, whenever there is a great preponderance of freight in one direction, the shipping must necessarily return empty, like the railway coal-waggon from London. The sailing or steam colliers which supply the London market not only have no outward freight as a usual thing, but they have to purchase ballast in the Thames and discharge it in the Tyne. The ballast-wharves of the Tyne are often mentioned in the very early history of Newcastle, and the heaps of gravel, and stones, and rubbish drawn from the ships have grown from those days to these.¹

"To carry on the coasting trade in coal to London, 10,000 tons of gravel are weekly supplied in the Thames, and establishments in the North are actually paid for discharging and conveying it to a convenient place of deposit."²

¹ The introduction of the system of water ballast has, of course, modified the growth of ballast-heaps.

² Dunn on the *Winning and Working of Coal Mines*, p. 338.

At one period of his life, George Stephenson was brakesman to the fixed engine which hauled up the ballast upon the heap, "a monstrous accumulation of earth, chalk, and Thames mud, already laid there to form a puzzle for future antiquarians."¹ And Stephenson often earned extra wages in the evening by taking a turn at heaving the ballast out of the collier vessels, while his engine was taken in charge by his friend Fairbairn.

In the foreign trade the influence of freights is far more distinct and important. A ship is often chartered for a specific voyage out and home, freight being provided both ways; but more commonly the homeward freight is the chief object the British shipowner aims at, and he sends the ship out often at a loss upon the outward passage, depending upon the captain or foreign agents to find a profitable home cargo. This important circumstance concerning the shipping and trading interests has often been alluded to, in pamphlets, speeches, or parliamentary reports. Dr. Buckland, for instance, thus explained the curious fact that Netherland coal was exported to America and avoided France, so much in want of it for her manufactures, by

¹ Smiles' *Lives of the Engineers*, vol. iii, pp. 38-41.

attributing it to the want of back-carriage.¹ Mr. T. Y. Hall, again, stated clearly :—"The owners of vessels trading between England and France find that coal answers the purpose of ballast when other goods cannot be obtained at remunerative freights."² But the most distinct statement is in a pamphlet called forth by Sir Robert Peel's proposal, in 1842, to revive the export tax on coal.³

"The proposed duty would produce also an

¹ *Report on the Coal Trade*, 1830.

² *Trans. N. of England Institute of Mining Engineers*, vol. vi, p. 106.

³ *Observations on the proposed Duties on the Exportation of Coals*, London, 1842, pp. 14, 15.

Similarly, an American report, referring to the effect of the Russian import duty on coal, states :—

"Russia being an agricultural country and exporting its bread-stuffs is losing on its agricultural exports, because the high tariff is causing high freight rates from Russia to foreign ports, since foreign merchant vessels have to arrive in ballast and thus charge high return freights from Russian ports. A comparison of rates from Odessa to England and Argentine ports to England shows that, whereas rates for wheat from the Russian port are ranging between 3·0 and 4·6 cents per pood, the rates for Argentine ports are between 2·2 and 3·0 cents per pood, the reason being that English imports and exports to and from Argentina are more evenly balanced than those to and from Russia. As a matter of fact, the number of vessels which entered the port of Odessa with cargoes during the year 1897 was but 46 per cent of the total number of vessels arrived, whereas, in the case of Argentina, the proportion was 70 per cent. It is natural then that freight rates on Russian wheat are higher than those on Argentine wheat" (*Coal Trade of the United States, Monthly Summary of Commerce and Finance of the United States*, Sept. 1902, p. 728).

indirect but injurious effect upon the importation of the raw materials of manufactures into this country at the lowest cost. It is well known that most of these articles are of a bulky nature ; it is important to reduce the expense of freight upon them, and this the present facility for exporting coal secures to a considerable degree, being an article that provides an outward freight to a ship. This is peculiarly illustrated in the Baltic, from whence tallow, hemp, flax, and timber, articles of low value but great bulk, constitute the objects of imports, while our principal articles of export are indigo, cochineal, dyes, drugs, gums, &c., articles of great value but small bulk ; so that it is necessary to have some compensating article of low value for our own exportation, to equalise and reduce the rate of freight. The same reasoning applies to our imports from the Mediterranean, and indeed most places of our intercourse from whence we derive our raw materials ; while the export of common goods, such as anchors, chains, and other heavy commodities, of which whole cargoes can never be made up, has materially increased at Newcastle and Sunderland since the facility of shipment of coal by exporting ships has been provided."

In British trade, especially under the present free-trade policy, there is a great preponderance of homeward cargoes. Our imports consist of bulky raw materials and food. Nearly the whole of the corn, fruits, live stock, provisions, sugar, coffee, tea, tobacco, spirits, are consumed here. Timber, hemp, guano, hides, bones, with dye and tan materials, such as logwood, indigo, valonia, are either consumed here, or contribute little to the bulk of our exports. Cotton, silk, wool, and flax are either used up in this country, or returned of a smaller bulk. Our exports of cast and wrought iron, hardwares, and general manufactures are rather heavy than bulky, and of a far higher value than the imports proportionally to the bulk. A large part of our shipping would thus have to leave our ports half empty, or in ballast, unless there were some makeweight or natural supply of bulky cargo as back-carriage.¹

Salt to some extent supplies the Liverpool shipowners with outward cargo, and it is re-

¹ It is interesting to note that the proportion of tonnage clearing in ballast is at present about the same as forty years ago. Thus, comparing the figures for 1864, which Jevons may be supposed to have had in mind, with the latest return, we have :—

Total tonnage cleared from ports in the United Kingdom in the oversea trade—

	Total cleared. Tons.	With cargoes. Tons.	In ballast. Tons.
1864	13,689,498	12,172,774	1,516,724
1904	54,571,476	48,466,364	6,105,112

markable that the tenth Earl of Dundonald, a man as ingenious and energetic as the late Earl, clearly foresaw the value of the salt trade in this respect, and urged its extension upon the nation in an able pamphlet¹ of the year 1785. Though the Northern nations then drew their salt from Spain, Portugal, or Sardinia, he held that "salt may become a great article of export trade from this country" to Flanders, Holland, part of Germany, Prussia, Norway, Denmark, Sweden, and Russia, because two-thirds of the outward-going vessels to some of these countries sail in ballast, making their freight upon their homeward voyage, and it was not to be doubted that they would rather accept half freights which, however small, are a clear gain, than incur the cost of ballast. Our export of salt exactly fulfils the purpose explained by the Earl, but on a more extensive scale than he could possibly have anticipated. In 1861 about 700,000 tons of salt were exported from England, by far the largest part of which comes down the Weaver from the Cheshire works to Liverpool, and is there shipped.²

¹ *The Present State of the Manufacture of Salt Explained*, by the Earl of Dundonald : London, 1785.

² Braithwaite Poole, *On the Commerce of Liverpool*, 1854, p. 33. The export of salt had fallen somewhat by the beginning of the

There is a curious relation, too, between the earthenware manufacture and the shipping interest of the Western ports. From early times, indeed, the Staffordshire earthenware trade has presented a remarkable instance of the arrangement of freights. The materials of earthenware, fuel, flintstones, and clay are never found together, like the materials of the iron manufacture; the finished earthenware, too, is of so bulky a nature when packed in crates, that a large part of its cost depends upon the cost of conveyance. Proximity to a coal-field is the first requisite of a pottery; proximity to a market the next requisite. Both these requisites are combined in the Staffordshire potteries. In the days of pack-horse conveyance their central position was of great importance, because the pack-horses, which brought the flints and clay from the nearest ports, could be used to carry and distribute the crockery slung in crates over the horses' backs. The flints were brought from the chalk districts of the south-east of England, by sea to Hull, and thence

twentieth century. In the five years 1900-4 it averaged a little under 600,000 tons. In evidence before the U.S. Industrial Commission in 1900, salt imported into the United States was referred to as "the English surplus product, which is shipped here as ballast. Salt comes from Liverpool to Savannah at an average rate of 75 cents (3s.) per ton of 2,240 pounds" (*Report of the Industrial Commission*, vol. xiii, Review of Evidence, p. xxx.).

up the Trent as far as possible ; while the clay came from Devonshire and Cornwall, either by the Severn as far as Bewdley, or up the Mersey and Weaver to Winsford.¹

In later days, the early opening of canal communication and the commercial proximity of the potteries to Liverpool have been of the highest importance to both. So much iron and other heavy articles are shipped at Liverpool, that the shipowners need some light, bulky article to fill up the higher parts of the ships' holds. A considerable part of the produce of the Staffordshire potteries, accordingly, goes to Liverpool, the export of crockery being stimulated by the favourable freights offered. And such is the demand for crockery at the port, that several attempts have been made to attract the manufacture itself to Liverpool or Birkenhead. Further, the Clyde shipowners, having a great superfluity of heavy iron cargoes, and experiencing a like want of light freight to complete the loading of their ships, have actually attempted to create a pottery manufacture about Glasgow with that purpose.²

At Liverpool, indeed, the whole products of

¹ Smiles' *Engineers*, vol. i, p. 447.

² Hearn's *Plutology*, p. 310, quoting *Journal of the Statistical Society*, vol. xx, p. 134.

the Lancashire factories, the earthenware and hardware of Staffordshire, the iron of South Wales, added to the salt of Cheshire, furnish a large mass of outward cargo, and the export of coal has hitherto been of minor importance. But with the progress of trade, that port will receive such immense masses inwards, that outward cargoes of coal will come more into demand. In 1850, Mr. William Laird urged the suitability of Liverpool for the export of coal, and there cannot be a doubt that in the natural progress of our trade, coal-staiths at Liverpool or Runcorn, supplied by direct lines from the South Lancashire field, will ship great amounts of coal ballast.¹

At other ports coal is, and long has been, an inestimable benefit to the shipowners. It is destructive to their profits to keep a vessel long in port waiting for cargo, and it is worse to send her off in ballast. Where there are coal-staiths, however, she can be loaded and dispatched in a day or two, with a cargo that will at least pay expenses, and find a ready sale in any part of the world. It is on this principle that the Great

¹ The anticipation here expressed has not advanced towards realisation in forty years, the export of coal from Liverpool and Runcorn remaining about the same in amount. Large amounts of bunker-coal, exceeding by four- or five-fold the coal shipped as cargo, are now shipped from the Mersey.

Central Railway are developing Grimsby as a port. Just in proportion, it is found, as they offer outward cargoes of coal can they induce vessels to resort to the port with their inward cargoes.

It is in the rates of freight that we can best study the relative demand and supply of cargo. A want of outward cargo causes shipowners to bid for what is to be had, and reduce their prices of freight accordingly. Were there no ballast cargo like coal available, the outward rates must become quite nominal, until it would be profitable to send bricks, flagstones, and paving stones on long sea voyages. But the fact that coal may always be shipped establishes a certain minimum rate of freight depending upon the price at which we can compete with foreign coal or other fuel, and force a trade so essential to our shipowners.¹

¹ The development of the steamship during the past forty years has resulted in such marked alterations, both in the general level of freight rates and in the currents of trade, that the striking illustrations given by Jevons in support of his general thesis have no close relation to present-day conditions, and they have been omitted in this edition. In general, it is still true that coal is conveyed at very low rates, as return freight, to places which offer opportunities for obtaining a profitable homeward cargo. Such differences in freight-rates as were illustrated by the quotations of 20s. to Bombay, 30s. to Aden, and 50s. to Suez have vanished. In these cases the opening of the Suez Canal has produced new

In the course of freight rates we may detect many effects of demand and supply, as well as a general confirmation of the facts stated. Thus the outward freight to Bombay [early in 1904 was

conditions. The rates to eastern and western Mediterranean ports do not differ very much, and the rates to Aden and Bombay are nearly the same. The differences of rates due to the greater facility for procuring a return cargo at one than at another of ports not very far distant from each other is no longer measured in shillings per ton, but in pence, and when differences are thus small it is a matter of some difficulty to assign them to one special cause, unless the general course of freights over a long period be studied rather than such isolated quotations as served the purpose in 1865.

Contrasts of homeward rates with outward coal freights can still be found without difficulty. Two such are given in the text, and to these another may be added. On February 18th, 1905, the *Times* reported an outward rate of 10s. for coals to the west coast of America. On the 6th of the same month, the homeward rate from nitrate ports was quoted at 21s. 3d., while on the date of the above-quoted outward rate 30s. was quoted for early shipments.

In illustration of the differences of homeward rates to coal ports and to other ports, the rates from Alexandria, quoted in *Fairplay* at the beginning of June, 1905, may be taken, namely, to London 7s., to Hull 6s. 6d., though part of the difference may be due to differences of charges on shipping in the two ports.

The development of the coalfields of Australia, Japan, India and British Columbia has largely modified the importance of our shipments of coal to points where supplies from these sources compete with British coal. Thus, on the west coast of South America, the competition of Australian coal is severe; in California the coal from British Columbia, as well as that from Australia, competes both with British coal and with the coal of Chili and of Washington respectively.

Another point of considerable importance in particular trades is that, low as coal freights are, modern ships can be built so as to be operated economically in the carriage of coal alone, any homeward freight being a source of additional profit. In these cases, an

10s. 6*d.* per ton, the homeward freight being 13s. in January and 16s. in February. Later in the year the homeward rate advanced to 19s., and, with the improvement in the homeward rate, the outward rate declined rapidly, reaching 6s. per ton.

Similarly, the outward rates to the River Plate were about 6s. 6*d.* to 7s. 6*d.* for most of the year 1904, the homeward freight being 21s. in January and 18s. to 19s. in the later months of the year. For a short time in the middle of the year the homeward rate fell to 15s., and the outward rate went up to 8s. 3*d.*

These quotations show the effect on outward coal freights of the varying facilities for procuring a homeward cargo which follow the course of the seasons. The ease with which our coal competes

argument which depends on the assumption of ballast-rates for the carriage of coal will, of course, not apply.

The conceptions on which Jevons dwelt in this connection will be found applicable to important lines of trade elsewhere. Thus the vessels which carry iron-ore from the Lake Superior ports to ports on Lake Erie may find a return cargo of coal to the upper lake ports. Some of the railroads, too, find it profitable to carry coal westward in the cars which have, on their eastward journey, been filled with the grain of the west. We thus find the principle, which Jevons illustrated by an exchange of wheat and coal between New York and British ports, illustrated in the movement of the same commodities within the United States, though the development of the coal-fields of the Eastern States has put an end to the purchases of British coal on the Atlantic seaboard.

in foreign markets varies in like fashion, as illustrated by the following. "In the San Francisco market the coals of the world compete, and the relative importance of this or that source varies from year to year in accordance with somewhat complex laws of supply. Foreign coal enters this port chiefly as ballast in tramp steamers seeking grain cargoes, so that the condition of the wheat export trade has a direct bearing upon the coal imports." ¹]

It would be difficult to over-estimate the benefits the trade in coal has conferred upon us. Writers for some centuries back have been unanimous in regarding the Newcastle collier fleet as the nursery of our seamen. The "Newcastle voyage is . . . if not the onely, yet the especiall nursery and schoole of seamen: For, as it is the chiefest, so it is the gentlest, and most open to landmen." ² And no one could better have expressed than the writer of the above the way in which an Englishman regards a ship. "As concerning ships, it is that which every one knoweth, and can say, they are our weapons, they are our ornaments, they are our strength, they are our pleasures, they are our

¹ 22nd *Annual Report of the U.S. Geological Survey*, 1900-1901, part iii, p. 481.

² *The Trades' Increase*, p. 25.

defence, they are our profit; the subject by them is made rich, the kingdom through them strong; the Prince in them is mighty; in a word by them in a manner we live, the kingdom is, the king reigneth.”¹

Another able anonymous writer, in arguing against the old 5s. tax upon sea-borne coal, expresses similar views, his chief purpose being “to show how pernicious this tax upon coal is to Trade and Navigation, the safety and glory of England.”²

“The collier trade is the true parent and support of our navigation.”

“The collier fleet,” he says again,³ “is the great body of the shipping of England, and all our other trades are served by detachments from it. Our East country, Norway, and a great part of the West Indian fleet, are but parts of the collier fleet; from which they may depart one or two voyages in the year, as the contingency of the market abroad, or a chance freight at home offers. From which as soon as performed, they return again into the collier trade; that is, indeed, the refuge, as well as the nursery of our

¹ *The Trades' Increase*, p. 2.

² *The Mischief of the Five-Shilling Tax upon Coal*. London, 1699, p. 3.

³ *Ibid.*, p. 5.

navigation." But in the following he expresses still more exactly the part that coal now plays in our coasting and foreign shipping. "It's the collier trade alone that affords constant work to the navigation of England. It is there that every idle ship and every idle saylor are sure never to want a voyage or a berth to Newcastle." ¹

"The collier trade is the most huge and bulky trade that possibly can be managed, and therefore in its nature most proper, above all others, to employ not only vast numbers of people upon it, but to afford continual work for them. All our other trades are by fits and starts. Ships and sailors must have constant work." ²

And the French so clearly perceived forty years ago the maritime advantages this trade gives that they attributed to us the policy of promoting exportation.

"The English Government uses every possible means to stimulate an exportation which contributes powerfully to its maritime preponderance without hurting its industrial preponderance." ³

And the Newcastle manufacturers were and are well aware of the advantages they enjoy.

¹ *The Mischief of the Five-Shilling Tax upon Coal.* London, 1699, p. 5. ² *Ibid.*, p. 6. ³ *Situation de l'Ind.* etc., p. 27.

"The ready communication," they said in a memorial more than half a century ago, "which has been obtained with foreign ports, by means of the numerous vessels employed in the exportation of coals, has greatly facilitated the sale of the various articles manufactured by your memorialists, and has consequently increased the value of property employed in manufactures in this district."¹

Our exports of coal now amount to [nearly fifty] million tons in a year, the sale of which in foreign ports must return fully [sixteen] millions sterling to our coalowners, and [ten or twelve] millions in the shape of freight to our shipowners. To prohibit this trade would therefore be to incur a burden equal to the income tax at its worst. And though the greater part of this burden would be borne by the community in general as the consumers of foreign produce, it would be inflicted through that branch of our industry, our navigation, which is truly the safety and glory of England.

But on the other hand we cannot look upon our growing exports without anxiety. The following numbers show the extraordinary rate of growth since the repeal of the export tax.

¹ Memorial of the Manufacturers of the Tyne, of iron, lead, glass, rope, alkali, sail-cloth, etc. (1842?).

EXPORT OF COAL.¹

Year	Amount of coal exported	Duty per ton on coal exported to foreign countries	Rate of increase per cent of exports in ten years
	Tons	<i>s. d.</i>	
1821	260,314	{ In British ships 10 0 In foreign ships 12 0	
1831	508,697	{ In British ships 3 4 In foreign ships 6 8	95
1841	1,848,294	10s. per cent	263
1851	3,468,545	0 0	88
1861	7,855,115	0 0	126
1871	12,549,874	0 0	60
1881	19,174,753	0 0	53
1891	30,356,328	0 0	58
1901	42,684,752	0 0	14

Our exports were more than trebled in the ten years 1831-41 under a temporary repeal of the duty, and more than doubled themselves in the ten years following the complete repeal in 1850.

[The subsequent increase has far more than kept pace with the increase in production. In the middle of the nineteenth century the exports were about one-tenth of the annual output of our mines. At the end of the century nearly one-fifth of the output was sent abroad, in addition to a large and rapidly increasing amount supplied as bunker-coal to ships engaged in our foreign trade.]

¹ See also note at the end of the chapter. The export duty was removed in 1834, as regards most countries, under reciprocity agreements. It was restored in 1842 at a reduced rate, and repealed in 1845 for shipments in British ships, and in 1850 entirely.

No one can doubt that the extension of our commerce and the growth of Continental industry will demand a continued increase of exports.

“Independent of the superiority of the article, the freights of vessels from our shores are getting so low, and the distance between Great Britain and the coast of France is so short, that we shall always be able to have the advantage over Belgian and even French coal in the sea-port towns.”¹

And the inevitable progress of free trade will ever increase the tendency to export coal. As we subsist more and more upon foreign corn, meat, sugar, rice, coffee, tea, fruit, etc., and work more and more on foreign timber, ores, cotton, silk, wool, dye-woods, oils, seeds, etc., while returning the costly and elaborate products of our steam-driven factories, there must be an ever-growing surplus of inward freights and a corresponding demand for outward ballast freights.²

¹ At the date of the original publication of *The Coal Question*, France was importing about 4 million tons of coal yearly from Belgium, about 1,250,000 or a little more from Great Britain, and an equal amount from Prussia and Bavaria. In the last year or two the French imports have been, in round figures, from Belgium 5 million tons, from Great Britain 7 million tons, and from Germany 2 million tons annually.

² In a very instructive paper read before the Statistical Society in 1903, Mr. D. A. Thomas quotes the following estimates given to the Chamber of Shipping by Mr. Williamson, of Liverpool, as to

Our foreign coal trade has been, is, and will be an integral and essential part of our system. It is the alpha and omega of our trade. As it was the earliest nursery of our seamen, so it is now their especial support, and it bids fair to hasten us to an early end. It makes our limited fields the common property of the sea-coast inhabitants of all countries. The Newcastle mines are almost as high a benefit to the French, Dutch, Prussian, Danish, Norwegian, Russian, Spanish, and Italian coast-towns, as to our own. And foreigners not unnaturally think we are simple enough in thus lending ourselves to them. "It has often been repeated, for some time past, that there is one simple means of competing with England in her manufactures. It is to buy her coal from her, and England has lent herself to this design by developing and facilitating her exportation of coal in every possible way."¹

the relative weight of imports, exports, and coal exports, as follows :—

Year	Weight of imports	Weight of exports including coal	Weight of exports other than coal
	Tons	Tons	Tons
1869	12,776,000	15,891,000	3,000,000
1880	24,359,000	30,944,000	7,325,000
1890	29,793,000	46,752,000	8,525,000
1898	37,137,000	55,481,000	7,670,000

(*Journal of the Royal Statistical Society*, vol. lxi., 1903, p. 455.)

¹ *Situation de l'Industrie Houillère en 1859.*

The extraordinary progress of our steam marine was noticed in a previous chapter. Its close connection with the export trade in coal cannot escape attention. Our lines of steam-vessels create a demand for coal at the most distant and widely extended points of the globe ; while low outward freights enable coal to be sent cheaply to those points. Accordingly, as long as Britain maintains her present commercial and maritime position, not only the continental and other sea-coasts, in most parts of the world, but also the greater part of the steam-vessels plying on every sea, will draw their supplies from those seaboard coal-fields of Newcastle, South Wales, the Clyde, and the Mersey, which, taken as a whole, in the various quality of their fuel, in their facilities of shipment, and their supply of over-sea freight, are wholly unrivalled by any other coal-fields.

The absurdity of the notion of this country importing coals on any large scale will now be apparent. The fact that we now export large quantities of coal, instead of showing the possibility of a return current, shows its commercial impossibility. The coal exported acts as a make-weight, to remedy in some degree the one-sided character of our trade. Coal is to us that one great raw

material which balances the whole mass of the other raw materials we import, and which we pay for either by coal in its crude form, or by manufactures which represent a greater or less quantity of coal consumed in the steam-engine or the smelting furnace. To import coal as well as other raw materials would be against the essentially reciprocal nature of trade.¹ The weight of our inward cargoes would be multiplied many times, and but little weight left for outward carriage; almost every influence which now acts, and for centuries has acted, in favour of our maritime and manufacturing success would then act against it,

¹ A recent discussion of the question of American exports of coal to Europe contains the following:—"The real question at issue then is not merely that of comparative cost of production, but the combined cost of producing and shipping the coal to the foreign port. And it must be said that in this respect Great Britain possesses a great advantage over this country, and this is, that whereas the weight and bulk of articles exported from this country are much larger than the weight and bulk of imports to this country, exactly the opposite is true in the case of Great Britain. Since there is no reason to expect in the near future a reversal in that relation, the advantage of the British shipper of coal over his American competitor under normal conditions becomes quite patent. Even with the present excess of exports numerous vessels arrive in ballast at American ports; the addition of coal exports would merely add to this number. Considerable exports of coal are more likely to be made in the near future from southern ports, where coal may be used as additional or complementary cargo for vessels used in the transportation of cotton." *The Coal Trade of the United States*, in *Monthly Summary of Commerce and Finance of the U.S.*, Sept. 1902, p. 728.

and it would be arrogance and folly indeed to suppose that even Britain can carry forward her industry in spite of nature, and in the want of every material condition. In our successes hitherto it is to nature we owe at least as much as to our own energies.

NOTE ON THE STATISTICS OF COAL EXPORTS.

The Table on p. 313 traces the export of coal and coke by the use of the figures of single years at decennial intervals. In recent official publications an adjusted figure is compiled, differing

Period of years	Average amount of coal exported	Rate of increase per cent in ten years or as for ten years
1816-24	Tons 258,528	
1825-34	461,047	84
1835-44	1,472,967	219
1845-54	3,271,131	122
1855-64	7,405,363	126
1865-74	11,774,201	59
1875-84	18,577,204	58
1885-94	28,513,136	53
1895-1904	41,814,476	47

from the simple weight of coal exported by the allowance made for the fact that coke represents a weight of coal about two-thirds greater than

itself, and by deducting one-tenth from the weight of patent fuel exported, to allow for other materials than coal contained in it. The table on the opposite page is made up on this basis.

If we include bunker coal, the figures for the last three decennia become :—

Period of years	Average shipments of coal	Rate of increase per cent in ten years
1875-84	Tons 23,343,985	68 ¹
1885-94	36,289,179	55
1895-1904	54,591,463	50

¹ As the record of bunker-coal begins only in 1873, this figure is obtained by estimating the bunker-coals shipped in the years 1865-72 to bear the same proportion to the tonnage of steam shipping cleared from British ports as in the years 1875-84. This makes the average amount of bunker-coal shipped in 1865-74 about 2,100,000 tons per annum. It may be noted that, were it estimated at as high a figure as 3 million tons, the rate of increase would be 58 per cent, as in the preceding table. To obtain this last result, fully 60 per cent must be added to the estimate actually used for shipments of bunker-coal during 1865-72.

CHAPTER XIV

ON THE COMPARATIVE COAL RESOURCES OF DIFFERENT COUNTRIES

It is essential to our inquiry to view the several coal-producing countries comparatively. Thus only can we gain a true notion of our singular position, [and of the changes which are in progress.]

The following statement gives the amounts of coal raised about the years 1858-1860, in the chief coal-producing countries :—

	Annual production Tons
Great Britain, 1860	80,042,698
United States	14,333,922 ¹
British American Possessions	1,500,000 ²
New South Wales	250,000
Prussia, Saxony, etc.	12,000,000
Belgium	8,900,000
France	7,900,000
Russian Empire (estimated)	1,500,000
Austria	1,162,900
Spain	300,000
Japan, China, Borneo, etc. (estimated)	2,000,000

¹ *Reports respecting Coal*, 1866, p. 147.

² Hull, *Coal-fields of Great Britain*, 2nd ed., p. 29; and *Situation de l'Ind.*, etc., p. 111, quoting a report of M. Gonot, Ingénieur en chef

Of a total produce of 130 millions of tons, 96 millions were produced by nations of British origin and language, and 80 millions were produced in Great Britain itself.

Of the chief material agent of modern civilization, three parts out of five, or 60 per cent, were in the use of Great Britain; and nearly three parts out of four, or 75 per cent, were in the use of Anglo-Saxon nations.

The reader must form for himself, if he can, an adequate notion of the stimulus which the possession of such a mighty power gave to our race.

[The progress of the coal output in the principal coal-producing countries, and of the total production of the world, is indicated in the Table on the following page.¹

Though the coal production of Great Britain has nearly trebled in the course of the forty-three years between the date dealt with in the preceding *des Mines du Hainaut*, 1858. [The estimate of the output of British America is very much too high. On the other hand, the output of New South Wales in 1860 was stated about 50 per cent higher than the above figure in the Report of Committee E of the 1871 Commission. The figures of the table appear not to include lignite.]

¹ See also end of chapter. The figures are those given by *The Colliery Guardian*, and printed in the *Coal Commission's Final Report*, part xi, pp. 48-9. Some slight changes have been made on the basis of later corrected figures for 1903. Lignite is included in these figures.

Table and the latest date referred to in the Table below, the proportion of the entire world's production which is raised in this country has fallen from 60 per cent to 27 per cent. The proportion of the whole which is controlled by Anglo-Saxon nations, though not maintained at the high figure of three-fourths, has been about two-thirds of the whole at each of the dates for which figures are quoted.

	Annual Production Thousands of tons (2,240 lbs.)		
	1875	1889	1903
Great Britain	133,306	176,917	230,334
United States	46,686	126,098	319,068
British North America .	929	2,373	7,140
Australasia	1,362 ¹	4,544	8,535
India	648	2,045	7,438
Germany	47,756	83,614	159,846
France	16,686	23,915	34,345
Belgium	14,771	19,552	23,529
Russia	1,674	6,107	17,522
Austria-Hungary . . .	12,854	24,923	39,528
Total world's output . .	<u>277,531</u>	<u>474,230</u>	<u>863,650]</u>

Let us compare the amounts with the comparative stores of coal existing in the several countries which have been explored. The actual quantities of coal, indeed, are almost wholly unknown; we can only compare the supposed areas of the coal-fields. This has been done by Professor Rogers, in the following statement :—²

¹ Not including New Zealand.

² *Edinburgh Review*, vol. cxi, 1860, p. 88.

	Area of Coal Lands in square miles
United States	196,650
British North American Possessions .	7,530
Great Britain	5,400
France	984
Prussia	960
Belgium	510
Bohemia	400
Westphalia	380
Spain	200
Russia	100
Saxony	30

[The progress of knowledge of the mineral resources of all parts of the world is seen by comparing Professor Rogers' figures with those of M. Ed. Lozé, which, with the substitution of official figures for the United States and Canada, are as follows :—¹

	Square miles.
China	232,500
United States	335,000
Canada	97,200
India	35,000
New South Wales	24,000
Russia in Europe	20,000
United Kingdom	12,000
Spain	5,500
Japan	5,000
France	2,500
Austria-Hungary	1,800
Germany	1,700
Belgium	500
Total	<u>772,700</u>]

¹ *Final Report of Royal Commission on Coal Supplies*, part xi, p. 34. Lozé, whose estimate was made in 1901, gives 200,000 square miles for the United States, and 65,000 square miles for Canada.

Such estimates, indeed, can pretend to no accuracy, and the area of a coal-field is but slight measure of its value. We can only learn from the statement that [judged by their area], our English coal-fields are more important than those of any European country [except Russia], but that the North American coal-fields almost indefinitely surpass ours in extent, and, it may be added, in contents.

[Calculations of the coal contents of the coal-fields of some of the principal countries have been made. In 1893, there were published the results of calculations made for the Prussian Government by R. Nasse. At the end of 1904, Herr Oskar Simmersbach reviewed the results of deep borings in recent years in Germany, and of additions to knowledge of mineral resources elsewhere, and the Table on the following page shows the relation of the results of these two writers to each other.

From these figures it would appear that the relative preponderance of the coal resources of the United States is much less than the comparison of figures of area suggests. For the most part, however, the available contents of the coal-fields of the United States can, as yet, be hardly more than guessed at. Reference will be made later

on to the evidence of the abundance and easy accessibility of these resources.¹

AVAILABLE COAL RESOURCES OF PRINCIPAL
COUNTRIES
(Millions of Tons)

	Nasse 1893 ²	Simmersbach 1904 ³
United States. . .	684,000	681,000
Germany	112,000	415,300
United Kingdom .	198,000	193,000
France	18,000	19,000
Belgium.	15,000	20,000
Austria-Hungary .	17,000	17,000
Russia	—	40,000

The Russian coal-fields, though more extensive than our own, appear to be far inferior in contents, whether we consider quantity, quality, or accessibility. In Europe, the only country whose coal resources are of similar extent to our own is Germany. Direct comparison of the estimates of the tonnage of available coal in the two countries is rendered difficult by the fact that the limits of depth to which the estimates apply are not the same for both. At depths not exceed-

¹ Pp. 346-351.

² *Final Report of Royal Commission on Coal Supplies*, part xi, p. 34.

³ *Stahl und Eisen*, 24 Jahrgang, Nr. 23, Dec. 1st, 1904. *Die Steinkohlenvorräte der Erde*, pp. 1347-59. The figures for the United Kingdom are based on the Report of the 1871 Commission. The Report of the Allerton Commission supplies a figure 147,000 to be substituted for the 193,000 of the Table.

ing 1,000 metres (3,280 feet) the latest investigations result in an estimate of some 99,000¹ million tons of coal available in the German Empire. Between 1,000 metres and 1,500 metres (4,920 feet) a further amount of over 64,000 million tons is estimated to exist in the proved coal-fields. These figures indicate resources in Germany which exceed in quantity those of Great Britain.² The very large figures quoted in the Table on p. 325 include the estimated contents at all depths, not only of the coal-fields proved by working or boring, amounting to 280,000 million (metric)

¹ Metric tons. Apparently loss in working has not been allowed for. In dealing with such approximate figures, an exact reduction to English tons serves no purpose.

² Of course, this conclusion depends on the assumption of equal reliability for the estimates of the Committees of the Allerton Commission and those of the German geologists and mining experts whose investigations and arguments serve as the basis of the figures set forth above.

The fact that Jevons could pass lightly over the coal resources of Germany, now known to be so important and extensive, may serve as a warning against too hasty conclusions regarding mineral resources of localities where thorough investigation has not yet taken place. The development of German industry during the last quarter of a century is a fact of exactly that nature which Jevons' whole argument goes to show is to be looked for—one might even say, is inevitable—given the fact of large and accessible coal deposits. The argument of the remainder of the chapter has needed some modification in order to give weight to the additions made to knowledge of German coal resources in the last forty, and especially within the last ten, years. It is no longer possible to proceed on the assumption, reasonably made by Jevons, that the United States is the only country whose coal resources are comparable with our own.

tons, but in assumed extensions of known coal-fields. They are, of necessity, hypothetical in a very high degree, and especially so in relation to the problem of raising coal at a moderate cost.]

Coal exists more or less in most other parts of the world—in India, China, Japan, Labuan, New Zealand, Australia, Brazil, Chili, and Central [and Southern] Africa. Many details concerning the frequent occurrence of coal may be found in R. C. Taylor's *Statistics of Coal*,¹ but they have in reality little bearing upon our inquiry. With the exception of [the coal-fields of Germany and] the great North American fields, [to which may probably be added those of China], none are at all capable of competing in quality or extent with our coal-fields. They will prove very useful in furnishing a supply for local industry and steam navigation. Upon and around each coal-field will grow up, we hope, a prosperous community, enjoying those uses of coal which older nations are discovering ; but the only way in which those coal-fields could interfere with, and reduce the consumption of, our coal would be, either by—

1. Supplying sea-board coal markets which we now supply, or
2. Supporting a system of manufacturing industry capable of competing with ours.

¹ 1st ed., 1848 ; 2nd ed. revised by S. O. Haldeman.

Now, if the comparatively cumbersome and heavy nature of coal be considered, it will be seen that the cost of conveyance is a main element. A small extent of mountainous country, a considerable distance from a port, or a position far from the general current of trade, removes a coal-field from competition. Thus the French Official Report regards the difficulty and cost of conveyance as the great obstacle in the way of the French coal-mines. Otherwise, without being comparable with English fields, they are rich enough for home consumption.¹ "In France the deposits of combustible mineral are numerous, but there is only a small number which are susceptible, either from their extension or the quality of their products, of development upon a great scale. Most of these basins, too, are situated in mountainous countries, difficult of access, where lines of communication have penetrated but slowly and at great cost. This circumstance explains why at present the price of coal at market exceeds, in a very high proportion, the wholesale price at the pit mouth."

An English report expresses a similar opinion. "At St. Etienne, the heart of the French mining district, coal can be extracted as low as in Wales, and the expense of it throughout France is

¹ *Situation de l'Industrie Houillère en 1859*, p. 9.

imputed to the absence of easy lines of carriage and communication, which enable English coal to be sold on the French coast at a profit.”¹

On the other hand, the favourable natural conditions of our mines are thus described by the writers of the French Report :—²

“England is the most favoured country of Europe in the extent and richness of its coal-fields. Its superiority is confirmed by the varied and generally excellent quality of its coal, and by a regularity of the strata very favourable to the working of coal-mines.

“Lastly, as if nature had striven to unite in these coal-fields all the circumstances most conducive to mining and trading in coal, the two richest basins, those of Wales and Newcastle, are intersected by the sea. The coal-owners can load and ship their products in the most economical manner, and thus consign them to any point of the home or continental coasts.

“Over-sea conveyance, too, is the more cheap, because in English commerce the outward voyage may be considered as a voyage in ballast, and the return freight covers the chief part of the expenses.

¹ *Report of the South Shields Committee*, 1843.

² *Situation de l'Industrie Houillère en 1859*, p. 15.

“A like union of favourable conditions does not present itself at any other point of the globe, and constitutes a natural privilege with which no other country can entertain the notion of contending as regards industry founded upon the working and trading in coal. Any attempt at competition of the kind would necessarily be followed by defeat.”

Foreign coal-fields, then, are almost wholly excluded from competition with ours as regards sea-borne coal, because even if there were any coal-fields comparable with ours in intrinsic natural advantages, there would still be wanting the extrinsic advantages of the vast trading system and the mercantile marine of England capable of conveying and distributing the coal. In a great many parts of the world, at Sydney, Cape Breton, at Newcastle in Australia, Labuan, Chili, Asturias in Spain, and on the coast of the Black Sea, there are seams of coal almost abutting on the sea, but the *set* of trade and navigation in the wrong direction long enabled, or rather obliged, us to carry our coals out to these local Newcastles, [and, to some extent, continues to do so.] And if coal situated actually on the sea-board cannot drive our coal away, the high cost of land conveyance completely removes all inland coal-

fields from direct competition with our mines in the general sea-board coal markets of the world.

That French and continental mines generally cannot possibly compete with our coal mines is further shown in the remarks of Mr. R. C. Taylor :—¹

“ It is due to the unrivalled accessibility by sea to the best coal-basins of England, Scotland, and Wales—where coals of many varieties and admirable qualities can be shipped at the very sites where they are mined—that Great Britain has hitherto been able to furnish such enormous and cheap supplies, not only to the home consumers, but nearly to every maritime country in Europe. In this respect she is far more favourably circumstanced than her rival continental producers, France, Belgium, Prussia, and Austria, whose coal-fields lie remote from the sea-shore.

“ From Dunkirk to Bayonne, an extent of 300 leagues of coast, there are but two coal-fields, and those are at some distance from the sea. In regard also to the quality of the coal, France is less fortunate than England ; for with the exception of the basins of Anzin, St. Etienne, and a few others, the collieries of the interior yield but

¹ *Statistics of Coal*, 1st ed., p. 275, quoted by the *Edinburgh Review*, vol. xc., p. 534.

an inferior species of fuel. Both these circumstances combine to render France, to a certain extent, dependent upon Great Britain for the better sorts of coal; and hence the French Government annually make large and increasing contracts for the delivery of English coal at their depôts, for the use of their steam marine on service. . . .

“The manner in which the coal-tracts of Great Britain are distributed, is fortunately such that every coal-field in England and Wales can meet the next adjoining coal-field nearly on a radius of thirty miles, thus forming such a range of deposits, from Scotland to South Wales and Somersetshire, that the whole interior of the country can be supplied with coals, through the railroad system, from several central points.”

So long, then, as the currents of trade and navigation continue in their present general course, there are no coal-fields capable of competing with, and reducing the demand for, our coal in regard to the over-sea coal-trade.¹ The only

¹ The falling off in our exports of coal to India, the Far East, and the Atlantic coast of Central and North America, which is noted in Mr. D. A. Thomas' valuable paper in the *Journal of the Royal Statistical Society* for Sept., 1903, hardly amounts to so marked a contradiction of the statement of the text as to require its elision. In the cases of India and Japan, and also in regard to the United States, Canada, and Australasia, our exports have fallen

other way in which a foreign coal-field could affect the prosperity of our coal-consuming industry would be by nourishing abroad great systems of

off mainly because local production has increased. In the other markets of the Far East and in the West Indies and Central America, the nearer supplies from India, Japan, Australia, and the United States have certainly had the effect of competing with our coal so as to reduce the demand for it. The same is true of the Pacific coast of America. In some of these cases the effect is seen in a lack of expansiveness in the markets concerned, in others in positive reduction in the amount of British coal supplied.

Mr. Thomas' paper shows that the groups of markets which have lagged behind relatively to our entire foreign market are those on the Pacific and Indian Oceans (with the exception of the West Coast of Africa), to which must be added the Atlantic coast of Central and North America. To these markets together, we exported 7,500,000 tons of coal in the quinquennium 1860-64, 12,770,000 in the five years 1880-84, and 10,790,000 in the five years 1900-04. The total exports of these periods were respectively 39, 100, and 220 millions of tons. The relative importance of these markets declined from 18 per cent of our entire foreign market in 1860-64 to 12·5 per cent in 1880-84, and further to little over 4·5 per cent in 1900-04 in spite of the exceptional exports to North America during the anthracite coal strike in the winter of 1902-3, and later to the seat of war in the Far East.

The following Table, the data for which are given in Part XI. of the *Final Report of the Royal Commission on Coal Supplies*, shows how little the development of British exports of coal has as yet been checked by the development of other sources of supply.

NET EXPORTS OF COAL (Thousands of tons)

	1903	1878
United Kingdom	63,802	19,673
Germany	13,307	3,874
United States	4,954	83
Japan	3,313	?
Belgium	2,440	3,684
Australia	2,352	608
British India	287	} Net import
South Africa	131	

Of 28,000,000 tons exported by practically all the coal-exporting countries in 1878, Great Britain supplied 70 per cent. A quarter

manufacturing industry capable of withdrawing from us a part of the custom of the world, which we have enjoyed, as regards coal-made articles, almost to the extent of a monopoly.

If there were plenty of good coal in France, such a system of iron and coal industry might rise upon it as at any rate to deprive us of the custom of French consumers. Strange to say, this result has taken place to some extent. The good order and enlightened commercial policy of the Imperial Government [in the early sixties] had such an extraordinary effect upon French industry, that the produce of coal from the interior French mines advanced at the rate of 6·7 per cent per annum—at nearly double the rate of increase of our consumption of coal. The French iron manufacture advanced in a manner equally surprising, so that instances were not uncommon of English orders for iron goods being executed in France! And it is no doubt owing to this

of a century later, the aggregate export had increased to 90,586,000 tons, but Great Britain still supplied 70 per cent of the aggregate. The British figures include bunker coal supplied to foreign-going ships, while the foreign figures do not treat bunkers uniformly. Nevertheless, the table sufficiently demonstrates the maintenance of its place as a coal-exporting nation by this country. It must be remembered that, in the case of Germany and the United States, export by land accounts for no small part of the entire export of coal. Hence the preponderance of British coal in over-sea trade is even greater than the figures indicate.

advance of French industry in a manner parallel to our own, that the French treaty of commerce had much less remarkable results than was expected. Even the imports of coal into France remained stationary for a time, as seen in the following accounts :—

	Coal raised in France Tons	Coal imported Tons	Coal consumed in France Tons
1860 . .	7,900,000	5,900,000	13,800,000 ¹
1862 . .	9,400,000	5,900,000	15,300,000 ²
[1875 . .	16,957,000	7,004,000	23,961,000
1889 . .	23,852,000	7,798,000	31,650,000
1903 . .	34,218,000	12,224,000	46,442,000]

[The production has about quadrupled since 1860, while the net import has little more than doubled. The recent discoveries of coal in the Department of Meurthe et Moselle may well render France, in even a higher degree than heretofore, self dependent in the matter of coal.] ³

The natural riches and skill of the French are, however, comparatively so much higher in many other branches of industry, that it cannot be

¹ *Situation de l'Industrie Houillère*, p. 7.

² *Journal of Science*, No. 2, pp. 337, 338. The figures of production given in the Report of the 1871 Commission somewhat exceed those quoted above.

³ The figures for the later dates are taken from the *Report of the Commission on Coal Supplies*, part xi, pp. 52, 58, 60, and represent metric tons of 2,204 lbs.

supposed the competition of their coal industry can proceed far, or prove permanent and formidable.

The extraction of coal in Belgium, again, [increased very rapidly up to about 1870, but has recently progressed with markedly decreased rapidity. The following are the figures of production at intervals of ten years :—¹

	Metric tons	Rate of increase per cent in ten years
1830	1,913,000	—
1840	3,590,000	88
1850	5,779,000	61
1860	9,607,000	66
1870	13,458,000	40
1880	16,403,000	22
1890	19,971,000	22
1900	22,531,000	13

In recent years new deposits have been discovered in the North, in the La Campine district. The contents of this new coal-field have been estimated at 13,000 million tons. The newest borings, however, show that it is not everywhere as rich as was hoped, and this figure may prove to be too high. The deposits lie under the mouth of the Scheldt, and hence possess very great importance for Belgian trade. Apart from this new

¹ The figures are from *The Mineral Industry*, Vol. II, p. 220, and official reports. Those for 1840 and subsequent years are the averages of triennial periods 1839-41, 1849-51, etc. They are given in this form so as to represent the course of progress better than can be done by figures for single years.

coal-field,] the Belgian coal-proprietors are afraid that the produce of their mines has nearly reached its maximum. The fact is that the Belgian mines have been worked longer than our Newcastle mines, and have reached still greater depths. They are further advanced towards exhaustion than our own; and as their produce is but one-tenth part of our coal-produce, it would be absurd to suppose that they can support any industry capable of seriously competing with ours.

Germany, by the somewhat inland position of its coal-fields, as well as for other reasons, is [seriously handicapped in relation to the maritime coal-trade of the world, though the extent of its resources in coal has enabled a rapid and formidable development to be effected in industries dependent on coal. Its resources have already been referred to,¹] and no other European country has coal mines worth consideration here.

¹ Pp. 325-6. The production of coal in Germany and Luxemburg has been as follows :—

	Coal Thousands of metric tons	Rate of increase per cent in ten years, or as for ten years	Coal and lignite Thousands of metric tons	Rate of increase per cent in ten years, or as for ten years
1850	5,184	—	(1848) 5,801	—
1860	12,384	138	16,730	142
1870	27,515	123	35,401	112
1880	45,896	67	58,043	64
1890	70,395	53	89,505	54
1900	106,468	52	146,087	63
1904	120,694	37.	169,194	44

The data for coal are taken from Herr Simmersbach's article in *Stahl und Eisen* except for 1904. Those for coal and lignite from

When we turn to North America we meet once more a country capable of comparing in coal resources with our own. [The vast extent of its coal deposits, and the ease with which they yield their mineral wealth, afford the most favourable conditions for the growth of coal-consuming industries,] and the future of England greatly depends, therefore, upon the future of America. The areas of American and British coal-fields have already been compared, and show that the American fields exceed ours in the proportion of nearly 30 to 1.¹

There is reason to suppose that the carboniferous formation was originally spread in one continuous sheet over the whole of Central North America, from the flanks of the Rocky Mountains to the shores of the Atlantic, and from the Gulf of Mexico to Newfoundland. Large portions must have been removed by denudation, [and the following is a summary of the estimated remaining areas in the chief basins, as stated in

Mineral Resources of the United States for 1902. The figures for 1900 and earlier decennial dates are triennial averages. For years earlier than 1880, figures do not cover Alsace-Lorraine.

¹ In vol. i. of *The Mineral Industry*, it is stated that considerations of thinness of seams, and their quality and depth, render it "not likely that over one-sixth of the whole" area covered by coal formations "is available" (see art. *Coal and Coke*, p. 74).

the reports of the Geological Survey, together with the output in 1903 :—¹

	Area Sq. m.	Output, 1903 Tons (2,240 lbs.)
Anthracite	500	66,678,392
Bituminous.		
1. Triassic field	1,070	31,601
2. Appalachian	70,807	165,714,429
3. Northern	11,300	1,221,088
4. Central	58,000	46,545,407
5. Western	94,076	20,689,011
6. Rocky Mountains	100,110	15,161,660
7. Pacific Coast	1,050	3,026,640
Total production		<u>319,068,228</u>

These areas do not include any estimate for the coal-fields of Alaska, where the coal at present known is of poor quality and difficult to mine. It is to be noted that more than one-third of the entire bituminous output, as well as practically the whole anthracite production of the United States, is derived from the mines of Pennsylvania. The coal areas of that State are :—484 sq. m. anthracite, 12,200 sq. m. bituminous. They are thus equal to the

¹ The figures of output are from the *Mineral Resources of the United States* for 1903, pp. 354-5, where the amounts are stated in short tons of 2,000 lbs. The colliery consumption is included.

The 22nd Annual Report of the United States Geological Survey, part iii, contains a detailed account of the coal-fields of the United States, from which the material for the changes in and additions to Jevons' original statement has been derived.

entire coal area of Great Britain. The Pennsylvanian deposits form part of the Appalachian coal-field, which extends from the State of New York on the north to the State of Alabama on the south, having a length north-east and south-west of over 900 miles and a width ranging from 20 to 180 miles, and is, of all the coal-fields of the United States, that which has] the highest economic importance. On the eastward it has been crumpled up into the series of ranges forming the Allegheny Mountains. At the same time the bituminous portion of the coal has been more or less distilled off, producing the anthracite coal of Mauch Chunk and the other Eastern Pennsylvanian mines. The seams of coal, however, retain their bituminous character and their horizontal position on the west of the Allegheny Mountains. "In that less elevated country, the coal-measures are intersected by three great navigable rivers, and are capable of supplying for ages, to the inhabitants of a densely-peopled region, an inexhaustible supply of fuel. These rivers are the Monongahela, the Allegheny, and the Ohio, all of which lay open on their banks the level seams of coal. Looking down the first of these at Brownsville, we have a fine view of the main seam of bituminous coal ten feet thick,

commonly called the Pittsburg seam, breaking out in the steep cliff at the water's edge. . . . The same seam is seen at a distance, on the right bank, and may be followed the whole way to Pittsburg, fifty miles distant. As it is nearly horizontal while the river descends, it crops out at a continually increasing, but never at an inconvenient, height above the Monongahela. Below the great bed of coal at Brownsville is a fire-clay eighteen inches thick; and below this, several beds of limestone, below which again are other coal seams.”¹

[The Pittsburg coal “is the most uniform in quality and thickness and, for a given area, the most valuable coal-bed in the bituminous coal-field of Pennsylvania. . . . It occupies an area in this State about 50 miles in length by 50 miles in breadth, with an average thickness of presumably about six feet. On this basis it is estimated that the Pittsburg coal-bed originally contained more than 10,000,000,000 tons of available coal, and even after sixty years of mining it is probable that the available coal is not reduced below that figure.”² “It is a notable fact, well illustrat-

¹ Lyell, *Manual of Elementary Geology*, 1852, p. 333.

² *22nd Annual Report of the U.S. Geological Survey*, part iii., 1900-1, p. 175.

ing both the relatively recent date of development and the extent of the coal resources of the State, that shafting or deep sloping has as yet been adopted at but few points in all the bituminous area, and that even in pursuit of the most valuable beds mining has not yet been carried beyond a shaft depth of 630 feet. . . . There are no 'deep' mines in the bituminous basins. . . . All but a small percentage of the bituminous coal-mines in Pennsylvania are worked by drift on the out-crop or by gentle slope down the dip of the bed."¹ Of the total production of bituminous coal in the State, about three-fifths are supplied by the Pittsburg bed.]²

We have no extensive seams of coal now which can compare in ease of working with those above described. The "thick coal" of Staffordshire almost within the memory of [the parents of] those now living might be comparable, and four or five centuries ago it is supposed there were seams on the bank of the Tyne, and at Whitehaven, which could be worked by natural drainage, and with the greatest ease. But shallow coal has necessarily almost disappeared in England. The consequence is that we cannot now produce coal,

¹ *22nd Annual Report of the U.S. Geological Survey*, part iii, pp. 194-5.

² *Ibid.*, p. 197.

even with the aid of the best engineering skill, and of abundant trained labour, nearly so cheap as it can be had on the banks of the Ohio. At Pittsburg the best bituminous coal may be had at one-half, or one-third, the general price at European mines, as shown in the following comparative table of prices at the pit:—

	Ca. 1861 ¹				Average ² 1901	
	s.	d.	s.	d.	s.	d.
France	6	0	to	14	0	12 7½
Germany	7	0	„	10	0	9 4½
England	6	0	„	10	0	9 4½
Pennsylvania (anthracite) .	8	0	„	9	0	8 4½
Pittsburg (bituminous) . .	2	0	„	4	0	2s. 0d. to 4 0

Beyond the reach of doubt there is no portion of the earth's surface so naturally fitted for becoming the seat of great industries. "What is the value, it may be asked," in the words of an

¹ Overman, *On the Manufacture of Iron*, p. 102.

² *Coal Tables*, 1902. The cost of mining Pennsylvania anthracite is about \$1.50 per ton, to which must be added taxes and a royalty of 40 to 50 cents for the prepared sizes, and 10 to 12½ cents for small coal (*22nd Annual Report of the U.S. Geological Survey*, pp. 96-100). The cost of actual mining of bituminous coal in Pennsylvania is 40 to 60 cents per ton, running up to 80 or 85 cents in some localities (pp. 199, 200). The Connellsville coal costs only 35 cents per ton to mine. For mining, cleaning, and placing f.o.b. the total cost in the Pittsburg region is stated at from 47½ cents to a dollar. The average value at the pit of all United States coal is given in the *Coal Tables* as 5s. 6½d. It should be remembered that the price of coal in European countries in 1901 was very much above the normal level, while in the United States coal prices were not very much higher than for several years previous. See also note at end of chapter v.

American writer,¹ "of 63,000 square miles of country, which yields coal, iron, oil, and salt, beneath its fertile soil? Here are the elements of strength, heat, light, food, and the giant steam, opened at once to the science, skill, and untiring energy of an enterprising people."

It can excite no surprise that a people of British extraction, endowed with the absolute possession of lands so rich, so extensive, and so easily accessible as those of the United States, should spread and multiply. It is nature in its kindest and most liberal mood that has chiefly contributed to the growth of the United States. And a certain remarkable talent for the application and invention of all practical devices for saving labour and overcoming obstacles is the next chief attribute of the American nation that concerns us here. The moral and political characteristics of that people, and the influence they may exert for good or for evil upon the world, are not here in question.

But why did not such wonderful wealth in coal affect our prosperity long since, if so much depends upon the price of coal? It is because America did not for a long period reach that

¹ Gesner, *Practical Treatise on Coal, Petroleum, etc.*, New York, 1861, p. 30.

state of industrial development in which a great system of manufactures naturally grows up. Great as was the wealth of coal, the wealth of land, comparatively to European countries, was greater still; and agriculture had, as it should have had, the natural preference over manufactures. Nor had America long emerged from that earlier stage of the iron manufacture in which timber is the best fuel. Coal-smelting furnaces in the United States have not existed more than seventy years.¹ And the future relation of American coal to English industry cannot be better indicated than by the words of the very able *Report of the South Shields Committee on Coal Mines*, in the year 1843.

“It is not the want of coal, but of capital and of labour, that allows the more cheaply wrought British mineral to seal up the American mines. *It is within the range of possibility to reverse it.*

“When the expense of working British coal mines leaves no remuneration to the capital and labour employed, when brought into competition with the mines of other countries, then will they

¹ Coal was first successfully used in blast-furnace practice in the U.S. in 1838. In 1855 anthracite coal became more important than charcoal, and remained the chief blast-furnace fuel till, in 1875, coke superseded it as the most important (*Bulletin of the Department of Labour*, May, 1903, p. 446).

be as effectually lost to Britain for purposes of ascendancy, and their produce as exports, as if no longer in physical existence; and her superiority in the mechanical arts and manufactures, *ceteris paribus*, it may well be feared, will be superseded."

[Even in America, however, there are not wanting the signs of approaching exhaustion, which our own fields have manifested for a considerable time. In the anthracite field, in particular, fears are expressed that the maximum production has nearly been reached.¹ The Lackawanna region is expected to be the first to become exhausted. The Lehigh region, it is thought by some, has already passed its maximum production. "The mines in the Wyoming field, which were the most accessible, are being rapidly worked out, and the great reserve is in the Southern or Schuylkill field. In this field the coal lies deeper, and is much more expensive to mine. . . . In the future

¹ Mr. Harris, late President of the Reading Railroad Company, in giving evidence before the U.S. Industrial Commission, expressed a doubt whether the anthracite output would ever reach 60 million tons a year (*Report of the Industrial Commission*, vol. ix, p. 605). This was in 1900, and repeated an estimate of 1896 by Mr. William Griffith. In 1901 the output just exceeded 60,000,000 long tons, and in 1903 and 1904 it reached 66,613,454 and 65,318,490 tons respectively (*Statistical Abstract of the United States*, 1905, p. 492).

the more difficult mines will have to be worked. The improvements in methods of mining and handling coal do not keep pace with the added difficulties arising from the necessity of mining deeper and less satisfactory seams. The price of coal will necessarily advance hereafter, it is maintained, if it is to be mined profitably at all, although the advance will be slow."¹

The region in which anthracite is mined has been so thoroughly explored that estimates of its available coal resources are entitled to respect. The original contents, calculated at 1,900 tons to the foot-acre, amount to an estimated total of 19,507,872,325 tons.²

If the marketable coal be taken at 40 per cent of the coal in the seams,³ the resources available for the market were originally some 7,800,000,000 tons. To the end of 1901 the production had amounted in the aggregate to 1,350,000,000 tons, leaving available 6,450,000,000 tons, or supplies for about a century at the present rate of production. Mr. William Griffith,

¹ *Report of the Industrial Commission*, vol. ix, Review of Evidence, pp. xxxiii-iv.

² Report by Mr. A. D. Smith, Pennsylvania Geological Survey, 1895, *Summary of Final Report*, Vol. 3, part i, p. 2151.

³ Vide *Report of the Anthracite Coal Commission, Bulletin of the Department of Labour*, May, 1903, p. 447.

in a series of articles in the *Bond Record* in 1896, gave an estimate some 25 per cent less than the foregoing.

The resources of the bituminous coal areas of the United States cannot be stated in such definite terms as those of the anthracite fields. The area underlain by coal affords but little indication of the amount of coal available for use. The resources of the Pennsylvania bituminous coal-fields have been estimated at 33,547,200,000 tons,¹ which would make them, relatively to their area, greatly inferior to the British fields in productivity. Nasse's estimate of the aggregate contents of the American coal-fields has already been given.² The Geological Survey's Report affords some further valuable indications of the wealth of mineral concealed in various parts of the country. Of the Eastern Interior Coal-field, which covers most of Illinois, the south-west corner of Indiana, and a small portion of western Kentucky, it is stated that "in Indiana, coal has been found at 20 horizons at least, as many as 17 beds having been struck in a single drilling within a vertical distance of 800 feet. It is probable that the number of beds in Illinois is

¹ *Mineral Resources of the U.S.*, 1886, p. 317. This estimate was made in 1881 by Dr. H. M. Chance.

² P. 325.

fully as great as in Indiana. Most of these are thin, but beds sufficiently thick to be workable occur at eight horizons at least, though, as a rule, not more than three beds are workable at any one point, and usually not more than one, while large areas, amounting to a considerable percentage of the field, are not underlain by workable coal.”¹ As to the quality of the coals in this field, they are “inferior in heating value to eastern coals,” though some of them do “not fall far behind the best eastern coals, and are superior to some of the latter, while they are probably as good as, or better than, most of the coals from the fields farther west.”² . . . “The eastern coals being usually the better, the line separating the two market areas runs nearer the Interior than the Eastern field. . . . The better coal from the Appalachian field practically controls the market along the Ohio and the Mississippi rivers, except for screenings for steam purposes.”³

In the Western Interior Coal-field, covering parts of Iowa, Missouri, and Kansas, the deposits are patchy and irregular. “In some pockets coal 70 feet thick has been found, but its extent is very limited.”⁴ It is usual to find that about

¹ *22nd Annual Report of the U.S. Geological Survey*, part iii, p. 275.

² *Ibid.*, p. 294.

³ *Ibid.*, p. 297.

⁴ *Ibid.*, p. 344.

one-third of the land sought to be developed is, "by reason of thin coal or no coal, not worth further expenditure."¹

Of the total area of the Rocky Mountain coal-field, more than one-half (56,500 sq. m.) covers lignite deposits. For Colorado, "a conservative estimate places the workable area at about 50 per cent of the total area (18,100 sq. m.) . . . occupied by the coal-bearing formations, and the available coal is estimated at 33,897,800,000 tons."² Whether this figure is arrived at after making necessary deductions for coal which cannot be brought to the surface, though in seams of such thickness and satisfactory quality as to be included among the deposits available for working, is not quite clear. Of the Puget Sound district, it is reported that, "in the Green River field, three coal seams are being mined . . . 3 to 6 feet in thickness, at depths varying from 1,000 to 2,800 feet. . . . At Renton, three productive seams are known, the lowest $7\frac{1}{2}$ feet, No. 2 about 8 feet thick. . . . Six miles south-east, two seams, 13 feet and $3\frac{1}{2}$ feet thick, have been found. In the Newcastle area there are four productive seams, from 4 to 12 feet thick, which have been worked to a depth of 2,000 feet. At

¹ *Ibid.*, p. 351.

² *Ibid.*, p. 422.

Issaquah, six beds, $4\frac{1}{2}$ to $15\frac{1}{2}$ feet in thickness,"¹ have been reached.

Such are some of the indications of the extent and wide distribution of the coal resources of the United States. Of some of the bituminous areas, as well as of the Pennsylvania anthracite field, it can be said that, as with ourselves, the best of the coal has already been worked. An example is the Georges Creek district of Maryland, the reputation of which was largely based on the Cumberland coal of the Big or 14-foot bed, a high-grade steam coal. "The Big bed is almost exhausted in the lower Georges Creek district."²

For the present there is no doubt that, in extent and availability, the coal resources of the United States are far greater than those of Great Britain, no very surprising fact in view of the enormously greater area of territory involved. Further investigation may reveal resources capable of supporting the rapid development of recent years for a future of indefinite extent. On the other hand, the possibility presents itself that the duration of the period, when the existing advantages in cheap coal supplies enjoyed by the United States relatively to European coun-

¹ *Ibid.*, pp. 487-9.

² *Ibid.*, p. 213.

tries can be maintained, may be comparatively brief, as time counts in the life of a nation.

The course of the rapid increase in output of coal in the United States is shown in the following table :—¹

	Tons (2,240 lbs.)	Rate of increase per cent in ten years, or as for ten years
1830	1,312,000	—
1840	3,091,000	136
1850	5,683,000	84
1860	14,963,000	163
1870	34,172,000	128
1880	66,674,000	95
1890	139,157,000	109
1900	243,072,000	75
1904	314,283,000	90

In the matter of the competition of the United States in the coal-export trade of the world, it must be remarked that the great advantages offered by the wide distribution of her coal deposits, when industrial development is concerned, are hardly matched by the advantages of situation of her coal-fields in relation to export trade. None of the important deposits of coal is situated on, or close to, the sea, and cheaply as the mineral can be mined, the cost of conveyance to seaports offsets a very large part of the advantage over other

¹ The figures for the years to 1860 are from Mr. Brough's Report to the *Royal Commission on Coal Supplies (Final Report, part xi, p. 41)*. The remaining decennial figures are averages of three consecutive years, and are from the tables in *Mineral Resources of the United States for 1902*.

countries which seems to be shown by the table of comparative values at the pit's mouth.¹

The great Eastern American coal-fields are continued into New Brunswick, Nova Scotia, and Newfoundland, where some part of these extensions are of considerable present, and of still greater prospective, importance. Of Canada's resources the following official summary affords a brief account.²

"The coal areas of Canada are estimated at 97,200 square miles, not including areas known, but as yet undeveloped, in the far north. . . .

"The coal areas of Nova Scotia cover about 635 square miles. They are divided into the Cape Breton, the Pictou, and the Cumberland basins. New Brunswick contains, so far as known, no seams of sufficient magnitude to be worked successfully in competition with the Cumberland mines. The workable thickness of the coal is very great, in Cape Breton a total of 25 to 60 feet, in Pictou at least 70 feet, and in

¹ The coal of the Georges Creek district cost but 67½ cents to a dollar to place f. o. b. at the mines in 1900, and sold, in the early part of that year, previous to the strike, at \$1.05 per ton. The rail freight to Baltimore and Philadelphia was \$1.45 in 1900, and the rate by water was \$1.18 to Baltimore, and \$1.25 to Philadelphia. A large percentage of this coal is devoted to marine purposes (*22nd Annual Report of the Geological Survey*, part iii, pp. 213-4).

² *Statistical Year Book of Canada*, 1903, p. 183.

Cumberland at least 30 feet. If the workable area is reduced one-quarter, say, from 407,400 acres to 300,000 acres, and the average thickness of the workable area put at 25 feet, on the basis of 1,000 tons of coal an acre for every foot of coal, the amount of coal in the measures of Nova Scotia is 7,000,000,000 tons.

“There are no coal measures from New Brunswick westward until the province of Manitoba is reached. The coal areas of Manitoba are roughly estimated at 15,000 square miles. They yield lignites only. . . . The area, extending along the base of the Rocky Mountains, from the international boundary to the vicinity of the Peace River—a distance of 500 miles—underlain by coal measures, is 50,000 square miles.

“The third coal area is that in the Rocky Mountains. Though small, as measured by miles, it contains much coal of the best quality. The small coal area of the Crow’s Nest Pass is very rich.¹ Several seams of anthracite of excellent quality have been found. Those in the Cascades basin have an area of 60 square miles.

¹ Its contents have been estimated at 22,000,000,000 tons. *Final Report of the Royal Commission on Coal Supplies*, part xi, p. 39.

“The fourth area is that of the Pacific Coast. Dr. George M. Dawson gives the following estimate of its extent :—

	Sq. miles
Nanaimo coal basin (approximately correct) . .	200
Comox coal basin (rough approximation)	700
Queen Charlotte's Island (very rough approximation)	800
Tertiary lignite-bearing rocks in different parts of British Columbia south of the 54° parallel of latitude (very rough approximation) . . }	12,000

“Anthracite in 3-feet and 6-feet seams, comparing favourably with that from Pennsylvania, has been found in Queen Charlotte's Island.”

A point of great importance in connection with the coal areas of Canada is the fact that, both in Cape Breton and in Vancouver Island, they are placed very favourably for the shipment of their product. Of Nova Scotia, it is stated in the official *Year Book*¹ that “in the same province the iron-ore, the coal and the flux lie in close contiguity to each other, and are within a comparatively short distance from fine ship harbours, making that province one of the best regions in the world for the seat of iron and steel ship-building on a large scale.” The progress of

¹ *Statistical Year Book of Canada*, 1903, p. 194. The abundance of iron ore in Nova Scotia is a contested question, however.

Canada's coal production is shown in the following :—

	Output Tons (2,240 lbs.)	Rate of increase per cent in ten years, or as for ten years
1870	656,000	—
1880	1,324,000	102
1890	2,754,000	108
1900	5,008,000	82
1904	6,705,000	107

In New South Wales we again encounter coal deposits of large extent, and conveniently placed as regards the shipment of the product to any part of the world. The importance of these deposits to the British Empire, as well as the possibility of building up on them an industry and an export trade which may become serious competitors with those of Great Britain, justify the insertion here of the following account of their resources.¹

“Some years ago the late Mr. C. S. Wilkinson estimated that, within a depth of 4,000 feet from the surface, the New South Wales coal seams, of a thickness exceeding $2\frac{1}{2}$ feet, are capable of pro-

¹ *v. The Mineral Resources of New South Wales*, by Edward F. Pittman, Government Geologist, 1901, pp. 321–22, from which the above is abbreviated. Of the other Australian States, Queensland possesses coal resources estimated at 83,310,000,000 tons, and those of Victoria are estimated at 33,388,000,000 tons, while smaller amounts are known to exist in Tasmania and in West Australia, cf. *The Colliery Guardian* May 9, 1902, p. 996.

ducing 78,198 million tons of coal, allowing one-fifth for loss in working. Subsequently, in 1890, Professor David estimated that the unworked areas of the Palæozoic Coal-fields of New South Wales contained between 130,000 and 150,000 million tons, assuming 4,000 feet to be the limit down to which coal can be profitably worked, and not taking into consideration seams of less than 3 feet in thickness.

“Now, there is a little more known, but much is unexplored, and great uncertainty remains. For the purposes of an approximate estimate, however, we may assume that the Palæozoic Coal-fields underlain by coal within 4,000 feet of depth cover an area of 16,550 square miles. In the most productive areas the coal varies from 20 to 40, 50 and 60 feet of workable coal.

“It is best to base the calculation upon the assumption that a thickness of only 10 feet of workable coal underlies an area of 16,550 square miles. Taking 84 pounds as the weight of a cubic foot of coal, and deducting one-third of the gross weight for loss in working, impurities, etc., this would represent a total quantity of 115,346,880,000 tons of available fuel.”

The value per ton of the output at the pit's mouth fell from an average of nearly 12s. in

1877-79 to about 5*s.* 6*d.* twenty years later, and rose again substantially in 1900 and 1901. The average f. o. b. value of exported coal fell from 14*s.* per ton in 1877-78 to about 7*s.* twenty years later, the output having trebled in the meantime. Australian coal competes with British in most parts of the Pacific Ocean, as already noted.¹ The output of New South Wales has increased as follows :—

	Output Tons (2,240 lbs.)	Rate of increase per cent in ten years, or as for ten years
1860	369,000	—
1870	869,000	136
1880	1,466,000	69
1890	3,061,000	109
1900	5,507,000	80
1903	6,355,000	61

The position of the New South Wales coal-field on the sea-coast, round the port of Sydney, and extending even under the harbour of Sydney itself, gives these deposits a special importance in connection with the question under examination.

The coal-fields of Japan have been of rapidly increasing importance in recent years. The more important coal-fields exceed 4,000 square miles in area, and if to this be added the area of the coal-fields which have not been investigated, a total area of 5,000 square miles may be taken as a fair

¹ Chap. xiii.

estimate. What is known of these deposits indicates that the average thickness of the coal may be taken at 15 feet.¹ These figures indicate an available supply of 48,000,000 foot-acres. If the yield of a foot-acre be taken at 1,000 tons, the supply is estimated at 48,000,000,000 tons. The geographical configuration of Japan gives particular importance to its resources in view of the nearness of the coal-fields to the sea, while the recent industrial development of the nation gives point to an inquiry as to the coal resources available to support the growing industries. The production has grown as follows:—

	Output Tons (2,240 lbs.)	Rate of increase per cent in ten years
1881	925,000	—
1891	3,175,000	243
1901	8,802,000	177

It is hardly necessary to examine in detail the available resources, so far as known, of the numerous countries which contribute in a minor degree to the world's supply of coal.² In some cases the resources are known to be of small extent, inadequate even for the supply of local

¹ v. Report by Mr. Bennett H. Brough prepared for the *Royal Commission on Coal Supplies. Final Report*, part xi, p. 42.

² An excellent *résumé* of information on this subject is contained in the Report, already cited, of Mr. Bennett H. Brough.

needs. In other cases, the estimates which are available as to the extent of coal deposits are not based on such careful and thorough examination as to afford a satisfactory basis for argument based on these estimates. It might be said that this is true, in large degree, of the estimates current as to the coal resources of such regions as North America, Australia, and Japan. The figures which have been cited serve, in the main, rather as indications as to whether or not the countries to which they refer are sufficiently amply endowed with accessible coal to render their competition as sellers of coal, or of goods in the production of which coal is an all-important factor, threatening to the future of our own land, so far as that future depends on development along the lines of industry which have been characteristic of our country for over a century past.

Three countries appear to stand out from the rest in respect of the coal resources with which they are credited, namely, North America, Germany, and China. The least developed at the present moment is China, and the reports which are made from time to time of coal deposits in various parts of the Chinese territory certainly do not lack in sensational features. It

is admitted that foreigners are not readily permitted to gain thorough information as to the extent and richness of Chinese coal-fields, and it may be that the wonderful riches that are reported illustrate the saying, *Omne ignotum pro magnifico*.

The coal-fields of Pechili and Shansi have been recently described by Mr. Noah F. Drake,¹ who gives an estimate of their resources based on an area 500 miles long and 50 miles broad, with 23 feet of average thickness. Deducting one-half for denudation, this gives 350,000,000,000 tons. Another writer says, "all the world's coal-fields appear to be surpassed by the Shansi coal-fields. Over an area of 13,500 square miles there are several almost horizontal seams of anthracite, including a persistent main seam 6 to 9 yards in thickness."² "The Tai'tsan coal basin is a marvellous feature. It is considered, indeed, to be the most extensive and the most favourably situated coal basin in the world. The veins are horizontal and run to a thickness of 16 feet 8 inches. It is estimated that the basin contains 630,000,000,000 tons of

¹ "The Coal-fields of North-Eastern China" in *Transactions of the American Institute of Mining Engineers*, Vol. xxxi, pp. 492-512.

² Report of Mr. Bennett H. Brough to *Royal Commission on Coal Supplies. Final Report*, part xi, p. 42.

anthracite. . . . To the west of the province are more coal-beds nearly as extensive and favourably circumstanced. There is even a third basin, . . . which runs in a N.N.W. direction, may be followed for sixty miles, and its vein of coal has a thickness of 20 feet. At present coal is selling in the neighbourhood at 1s. 4d. to 1s. 6d. per ton, and even 6d. or 3d. per ton is sometimes not refused.”¹

When coal-fields of such phenomenal richness are actively developed, countries in which there no longer remain any large supplies of easily and cheaply mined coal are likely to feel the effect of the resulting severe competition. It may be that the development will not come soon. Yet the longer it is delayed, the further towards exhaustion will the cheaper coals of other lands have progressed. “Taking into consideration the present coal production, Frech, in 1900, expressed the opinion that in 100 to 200 years the coal-fields of Central France, Central Bohemia, the Kingdom of Saxony, the Prussian province of Saxony, and the North of England would be exhausted; in 250 years the other British coal-fields, the Waldenburg-Schatzlar coal-field, and that of the North of

¹ *Engineering*, April 28th, 1905, p. 543.

France; in 600 to 800 years the coal-fields of Saarbrücken, Belgium, Aachen, and Westphalia; and in more than 1,000 years the coal-fields of Upper Silesia."¹ The discussion of the additions made to the knowledge of German coal resources within the last ten years leads Herr Simmersbach to the conclusion that "if we compare the coal resources of European countries with one another, Germany owns a more abundant store of this valuable commodity than all Europe besides. . . . Through the great thickness of the coal measures and the number of the seams of its Eastern and Western coal regions, Germany finds itself in a position, not only to supply the needs of neighbouring countries, which must depend—and in the future in a greater degree than now—on German coal, but, after the exhaustion of the fields of Durham and Northumberland in 200 years, to make good the deficiency in the English export and, 50 years later, after the anticipated working out of the coal-fields of central England, to step into the inheritance of the entire British export trade. The power of Germany will then be by so much the more increased as, on the exhaustion of her coal reserves, the

¹ Report of Mr. B. H. Brough, p. 34.

ascendancy of Britain on the ocean seems threatened, since none of her colonies possess stores of coal answering to the need.”¹

The author cited may set too high a value on the deposits at great depths in the German coal-fields, and appears to somewhat underrate the resources of the British Empire in the final sentence quoted, but his statements serve to emphasise the undoubted fact, that, in the matter of available coal resources, capable of supplying cheap fuel in vast quantities, Great Britain no longer enjoys the solitary pre-eminence which once was her lot. America and Germany in the present, perhaps China in the future, control resources which can rival, and for some purposes surpass, what remains to us of the endowment so generously bestowed by nature on this island.]

[It will be convenient to bring together for comparative purposes the records of the growth of coal production in the chief commercial countries of the world for the last forty years. This is done in the following tables, the first of which states the average output of coal in successive quinquennial periods, whilst the second shows

¹ *Die Steinkohlenvorräte der Erde. Stahl und Eisen*, 1904, p. 1,359.

the average percentage rates of growth in the intervals between these periods¹ (cf. Plate II, facing p. viii).

Period of years	Average yearly production of coal Millions of tons (2,240 lbs.)						Middle year of period
	United States	German Empire	France	Belgium	United Kingdom	Whole World	
1864-68	24'6	28'7	12'0	11'9	100'0	188'3	1866
1869-73	39'8	38'3	14'4	14'1	117'7	237'7	1871
1874-78	49'3	47'8	16'7	14'3	132'2	280'9	1876
1879-83	79'0	61'0	19'3	16'7	151'0	355'6	1881
1884-88	111'4	74'3	20'3	17'8	161'9	423'5	1886
1889-93	148'1	89'8	25'2	19'5	178'0	509'4	1891
1894-98	174'3	110'9	29'1	20'8	195'5	594'4	1896
1899-1903	263'7	147'8	32'2	22'5	224'4	779'5	1901

In the five years to	Rates of increase per cent shown in the preceding table					
	United States	German Empire	France	Belgium	United Kingdom	Whole World
1871	61'7	33'3	20'1	18'8	17'6	26'2
1876	24'0	24'7	15'5	1'1	12'3	18'2
1881	60'2	27'7	15'9	17'1	14'3	26'6
1886	40'9	21'8	5'3	6'3	7'2	19'1
1891	33'0	20'9	24'1	9'4	9'9	20'3
1896	17'7	23'5	15'2	7'0	9'8	16'7
1901	51'3	33'3	10'6	8'2	14'8	31'1
In thirty years to 1901	563	286	123	59	91	228

¹ The data are derived, for the several countries, from the *Mineral Resources of the United States*, and, for the world at large, from *The Mineral Industry*. Though the figures given in this latter publication do not entirely agree with those of the *Colliery Guardian* or of *Engineering*, the differences are not large. The chief source of divergence is in the estimates of production of the minor producing states. The convenient fact that the figures quoted cover the entire forty years, year by year, while the other

A line is added to the second table to show the increase of the production in the period 1899-1903 over that of the period 1869-1873, thirty years earlier. It will be observed that the French output has increased in a greater proportion than that of this country, while the production in Germany has increased at a greater rate than the aggregate production of the world, and the United States output has increased by twice as great a percentage as that of the German Empire.

In the aggregate, this country has contributed more to the world's coal supply, even in the last twenty years, than any other country. In the thirty-five years from 1869 to 1903, the aggregate production, in millions of tons, has been as follows:—

TOTAL OUTPUT OF COAL, 1869-1903
Millions of tons (2,240 lbs.)

United Kingdom	5,803
United States	4,328
German Empire	2,850
France	786
Belgium	629
Entire World	15,910

A study of the table showing the varying rates of increase of coal output in different countries will yield much food for reflection. It fails, however, to demonstrate that the coal production of the United Kingdom is growing only at a steadily diminishing rate. The rate of growth

authorities either do not supply so extensive or so continuous a series, has led to the use of this table in place of the figures supplied to the late Royal Commission. The data for Germany and France include lignite as well as coal proper.

less than formerly, less than in either Germany or the United States, and only about half that of the aggregate production of the world. But we cannot yet foretell, as time would have us believe, the approximate date when our output will become stationary, or begin to decline. The more rapidly it be increased at the present, however, the sooner must that period be reached.]

The following returns for the year 1905 have appeared while the above was in the press (cf. pp. 322 and 399).

		Production in 1905 Tons (2,240 lbs.)	
		Coal	Iron
United Kingdom . . .	236,111,150 . . .		9,592,737
United States			22,992,380
Bituminous ¹	265,809,333		—
Anthracite	67,412,056		—
Germany			10,811,036
Coal	117,796,120		—
Lignite	51,630,200		—
France			3,028,000
Coal	34,779,150		—
Lignite	689,767		—

¹ Including lignite.

CHAPTER XV

OF THE IRON TRADE

SOLON said well to Cræsus, when in ostentation he showed him his gold, "Sir, if any other come that hath better iron than you, he will be master of all this gold."¹ And it will hardly be denied that the retention of our supremacy in the production and working of iron is a critical point of our future history. Most of those works and inventions in which we are pre-eminent depend upon the use of iron in novel modes and magnitudes. Roads, bridges, engines, vessels, are more and more formed of this invaluable metal. And it was well remarked by Wilberforce in opposing an intended tax upon iron that "the possession of iron was one of the great grounds of distinction between civilized and barbarous society; and in the same proportion that this country had improved in manufactures and civilization, the

¹ Bacon.

manufacture of iron had been extended and improved, and found its way by numerous meandering streams into every department of civil life.”¹

As our iron furnaces are a chief source of our power in the present, their voracious consumption of coal is most threatening as regards the future. Though iron is only one of the many products of coal, the making and working of iron demanded in 1865 between one-fourth and one-third of our whole yield of coal [and it demands about one-eighth of the output forty years later]; at the same time the iron trade offers a wide field for a future increase of consumption. We have seen that for a century [to about 1870] our produce of iron increased at a constant rate,² and the pre-eminent usefulness of iron places it beside coal and corn as a material of which there cannot be too much—which itself excites and supports population, offering it the means of constant multiplication.

But it is essentially a suicidal trade in a national point of view. Once already, in an earlier period of iron metallurgy, the iron trade exhausted our resources, and quitted our shores. Its absence contributed to produce that dull and unpro-

¹ *Hansard's Debates*, vol. vii, p. 79.

² See pp. 246-7.

gressive period in the early part of the eighteenth century which is so strongly marked upon our annals.

The former vicissitudes of the iron trade are of a very instructive character. There are two natural periods in the history of the iron manufacture—the charcoal period and the coal period. We require antiquarian writers like Mr. Nichols, Mr. Lower, or Mr. Smiles, to remind us of the very existence of a considerable manufacture of charcoal iron in England in former centuries. It is now utterly a thing of the past.¹

Until the middle of the eighteenth century,

¹ Newland and Backbarrow in Lancashire, Duddon in Cumberland, and Loon in Scotland were the only charcoal furnaces in the United Kingdom when Jevons wrote the above (*Mineral Statistics*, 1863, p. 70). The Backbarrow furnace was in operation as recently as 1902. Mr. Bennett H. Brough, secretary of the Iron and Steel Institute, has kindly supplied the information that all the charcoal furnaces are now shut down. It may be noted that a considerable manufacture of charcoal iron continues in the United States. The annual make increased from 388,677 tons in 1880 to 593,492 tons in 1890, and then decreased to 303,567 tons in 1900. In proportion to the whole pig-iron output of the United States it was 11·5 per cent in 1880, 6·7 per cent in 1890, and only 2·1 per cent in 1900 (see *Reports of Twelfth Census*, vol. x, p. 32). Prior to 1838 practically all the iron made in the United States was charcoal iron, and for nearly fifty years, from 1799 to 1844, charcoal iron ruled the market and was the standard of price (*The Mineral Industry for 1893*). In Germany and France, up to about the middle of the nineteenth century, charcoal iron was the chief product (S. S. Jeans in *British Industries*, p. 6).

however, iron was always made with charcoal, and a wooded country was necessarily its seat. Coal, or cole, was then the common name for charcoal, pit-coal being distinguished as sea-coal. The *collier* or *collyer* was the labourer who cut the timber, stacked it in heaps, *charked* it, and conveyed the coal on pack-horses to the *iron bloomary* and forge, situated in some neighbouring valley, where a stream of water gave motion to the bellows and the tilt-hammer.

The ore or *mine* was also brought by pack-horse from some neighbouring mine or deposit—for there are few geological formations or districts of this country which do not yield iron ore. Often the *mine* used was derived from heaps of old slag or offal, the refuse of still earlier iron works. For, in a previous age, even the use of water-power was unknown, and the furnace was blown by the *foot-blast*, double bellows alternately pressed by a man as he stepped from one to the other. The low heat thus obtained was not capable of half withdrawing the metal from its matrix. The thousands of tons of cinder and slag—"old man," as it is locally called—left by the Romans, for the most part, as the included coins and antiquities prove, on the Forest of Dean, the Weald of Sussex, or the Cleveland

Hills, were long a source of wonder and profit to the manufacturers of a later period.

Here we see a curious instance of the reaction and mutual dependence of the arts. The use of water-power, by giving a blast and heat of greater intensity, raised the iron manufacture to a new efficiency, but it could not enable us to use coal in smelting iron. It was the advance of the art of iron-working, and its special application in the steam-engine, that gave us the blowing-engine, and coal-blast furnace, which contributed in a main degree to our commercial resuscitation and our present strong position.

It was in the seventeenth century that the charcoal iron manufacture most flourished in England, and its chief seat was Sussex. "I have heard," says Norden in his *Surveyor's Dialogue*, "that there are, or recently were in Sussex neere 140 hammers and furnaces for iron." And Camden says of Sussex,¹ "Full of iron-mines it is in sundry places, where, for the making and founding thereof, there be furnaces on every side, and a huge deal of wood is yearly burnt; to which purpose divers brooks in many places are brought to run into one channel, and sundry meadows

¹ Quoted by M. A. Lower. *Contributions to Literature*, 1854, p. 120.

turned into pools and waters, that they may be of power sufficient to drive hammer-mills, which beating upon the iron, resound all over the places adjoining."

The increase of the trade threatened to denude England of the forests which were considered an ornament to the country, as well as essential to its security, as providing the oak timber for our navy. Poets and statesmen agreed in condemning the encroachments of the ironmasters.

"These iron times breed none that mind posterity"—

says Drayton. And George Withers in 1634¹ speaks of—

"The havoc and the spoyle,
Which, even within the measure of my days,
Is made through every quarter of this Isle—
In woods and groves which were this kingdom's praise."

Stowe at the same period clearly describes the growing scarcity of wood-fuel, the falsification of previous anticipations, and the necessity felt for resorting more and more to coal.

"Such hath bene the plenty of wood in England for all uses that *within man's memory it was held impossible to have any want of wood in England, but contrary to former imaginations* such hath bene the great expense of timber for

¹ Quoted by Smiles. *Lives of the Engineers*, vol. i, p. 292.

navigation ; with infinite increase of building of houses, with the great expense of wood to make household furniture, casks, and other vessels not to be numbered, and of carts, waggons, and coaches ; besides the extreme waste of wood in making iron, burning of bricks and tiles," etc.

"At this present, through the great consuming of wood as aforesaid, there is so great a scarcity of wood throughout the whole kingdom, that not only the city of London, all haven towns, and in very many parts within the land, the inhabitants in general are constrained to make their fires of sea-coal, or pit-coal, even in the chambers of honourable personages ; and through necessity, which is the mother of all arts, they have of very late years devised the making of iron, the making of all sorts of glass, burning of bricks, with sea-coal or pit-coal. Within thirty years last, the nice dames of London would not come into any house, or room, where sea-coals were burned, nor willingly eat of the meat that was either sod or roasted with sea-coal fire." ¹

Norden says, "He that well observes it and hath knowne the welds of Sussex, Surrey, and Kent, the grand nursery of those kind of trees, especially oke and beech, shall find an alteration

¹ *Stowe's Annals*, 1632, p. 1025.

within lesse than thirty years, as may well strike a feare, lest few yeares more, as pestilent as the former, will leave few goode trees standing in these welds. Such a heat issueth out of the many forges, and furnaces, for the making of yron, and out of the glasse kilnes, as hath devoured many famous woods within the welds.”¹

Evelyn in his Diary, deploring the fall of a fine oak, expresses “a deep execration of iron mills, and I had almost sayd ironmasters too.”

It was against those “voracious iron-works” that statutes of the 1st and 27th years of Elizabeth were directed, to prevent the destruction of timber trees which were necessary to maintain the wooden walls and maritime power of England. But in spite of statutes the waste went on. Postlethwayt, writing in 1766, says,² “The waste and destruction that has been of the woods in Warwick, Stafford, Worcester, Hereford, Monmouth, Gloucester, Glamorgan, Pembroke, Shropshire, and Sussex, by the iron-works, is not to be imagined. The scarcity of wood is thereby already grown so great, that where cord wood has been sold at five or six shillings per cord. within these few years it is now risen to upwards of

¹ *Surveyor's Dialogue*, p. 175.

² *Commercial Dictionary*, Art. *Coal*.

twelve or fourteen shillings, and in some places is all consumed. And if some care is not taken to preserve our timber from these consuming furnaces, we shall certainly soon stand in need of oak to supply the royal navy, and also shipping for the use of the merchants, to the great discouragement of shipbuilding and navigation, upon which the safety and figure of these kingdoms, as a maritime power, depend."

Now, I particularly beg attention to the curious fact that, in the course of the seventeenth century, the iron manufacture to some extent migrated to Ireland. The woods of that country were full of timber when those of England were nearly exhausted. *The trade at once followed the fuel in spite of a want of ore in Ireland.* As appears in tables of Irish exports, and in Sir F. Brewster's *New Essays on Trade*,¹ of the year 1702, Ireland became an iron exporting country. Sir William Temple says,² "Iron seems to me the manufacture that of all others ought the least to be encouraged in *Ireland*; or if it be, which requires the most restriction to certain places and rules. For I do not remember to have heard

¹ See pp. 94, etc.

² Essay upon the Advancement of Trade in Ireland, Works, 1720, vol. i, p. 119. This essay was first published in 1673. Some native ore was smelted in Ireland, though part was imported.

that there is any ore in Ireland, at least I am sure that the greatest part is fetched from England; so that all this country affords of its own growth towards this manufacture, is but the wood, which has met but with too great consumptions already in most parts of this kingdom, and needs not this to destroy what is left. So that Iron-works ought to be confined to certain places, where either the woods continue vast, and make the country savage; or where they are not at all fit for timber, or likely to grow to it; or where there is no conveyance for timber to places of vent, so as to quit the cost of the carriage."

Postlethwayt alludes to the migration of the manufacture and the necessary result. "It is generally allowed that within about these seventy years, Ireland was better stored with oak-timber than England; but several gentlemen from hence, as well as those residing there, set up iron-works, which in a few years swept away the wood to that degree, that they have had even a scarcity of small stuff to produce bark for their tanning, nor scarce timber for their common and necessary uses."

When Ireland was in a condition to compete with England in a given manufacture, no artificial encouragement was needed. Frequent attempts on the other hand were made to gain a

supply of iron from our American plantations. "Certainly," as Evelyn remarked, "the goodly rivers and forests of the other world would much better become our iron and saw-mills, than these exhausted countries, and we prove gainers by the timely removal." But, perhaps from the want of labour, American iron could not compete with Continental iron.

England had for a length of time made and used much iron. "The Forest of Deane," says Yarranton, "is, as to the iron, to be compared to the sheep's back as to the woollen; nothing being of more advantage to England than these two are." And the Commanders of the Spanish Armada are said to have had especial orders to destroy the Forest of Dean, as being a main source of England's strength. And though coal could not yet be used in the smelting-furnace, it had long been chiefly used in the finery, the chafery, and the blacksmith's hearth. A great portion of the coal and culm that had for centuries been exported to France, and the coasts of the Northern Sea, was used in the smithy. And it was undoubtedly the abundance of coal that reared from early times the ironworking arts at Sheffield, Dudley, and Birmingham.

When our home production of iron was rapidly

failing, there was a considerable demand for foreign iron in England. Hewitt, in his *Statistics of the Iron Trade*,¹ after expressing his surprise that in 1740 the total produce of England was only 17,350 tons, made in 59 furnaces, adds his conviction that the total production of Europe at the time did not exceed 100,000 tons, of which 60,000 were made in the forest countries of Sweden, Norway, and Russia. One-half of this was imported into England. The consumption of iron in England, he thinks, was 15lbs. per head of the population; while in Europe, on the average, it did not exceed 2lbs. Of the iron we used, four-fifths were considered to be imported from one country or another. Joshua Gee speaks of our market as "the most considerable in Europe for the vast consumption of iron," and represents the Swedes, Danes, and Russians as striving to gain our market.² Our production of iron by the middle of the century was believed to have declined to one-tenth part of its former amount, and the high cost of foreign iron formed the main check upon the progress of those arts which were to be so great. By this time the substitution of coal for charcoal had become a

¹ *Statistics and Geography of the Production of Iron*: New York, 1856, p. 7.

² *Trade and Navigation of Great Britain*, 1738, p. 104.

necessity. Postlethwayt, in a pamphlet possessed by the Statistical Society,¹ describes the condition of the iron trade in 1747, remarking that "England not being so woody a country as either Sweden or Russia, we do not abound, nor ever shall, with a sufficiency of wood-coal;" and that as cordwood was doubled, or trebled in price, *six* or *eight* times dearer than pit-coal, and very dear compared with its price in foreign iron-making countries, it was no wonder home-made iron decreased. This scarcity of wood was really due, of course, to the superior profits to be derived from using the land as pasture. Norden allowed this a century before: "The cleansing of many of these welde grounds hath redounded rather to the benefite than to the hurte of the countrey: for where woods did growe in superfluous abundance there was lacke of pasture for kine, and of arable land for corne."

And Houghton had acutely anticipated the subsequent course of things by suggesting that it would be profitable to cut down all wood near navigable waters where coal could be had, of which he remarked *we had enough*.²

¹ *Considerations on the making of Bar Iron with Pit or Sea Coal Fire*, 1747.

² *Houghton's Collection of Letters for the Improvement of Husbandry and Trade*, 1727-1728, vol. iv, p. 259.

To make iron with pit-coal was the great problem, the practical solution of which was all-important to the nation.

It was no new notion. From the early part of the seventeenth century it had been the object of eager experiments, and the cause of ruin to many of the experimenters. The history of the establishment of our great iron trade has been described in the works of Mr. Smiles, Dr. Percy, and others, but it possesses points of interest which we cannot pass over.

Simon Sturtevant, a German metallurgist, about 1612, was the first to take out a patent for making iron with pit-coal. His specification of the invention, entitled *A Treatise of Metallica*, is an eccentric but clever production. In the practical part of his work he seems to have had less success than in the literary; and others who followed up his notions—mostly Dutchmen and Germans, such as Rovenson, Jorden, Franche, and Sir Phillibert Vernalt—had no more success.

The following verses of the year 1633 quaintly allude to such attempts :—

“ The yron mills are excellent for that ;
I have a patent draune to that effect ;
If they goe up, downe goe the goodly trees.
I’ll make them search the earth to find new fire.”¹

¹ *The Costlie Whore*, quoted by Percy, *Metallurgy of Iron and Steel*, p. 144.

It was Dud Dudley, a natural son of Lord Dudley, of Dudley Castle, manager of his father's iron forges in the neighbourhood, who, in 1621, first succeeded in smelting iron with coal. According to his own account in his *Metallum Martis*, he made considerable quantities of pit-coal iron at Cradley, Pensnet, Himley, and Sedgley. But various disasters and troubles, the jealousy of other ironmasters, and the civil strife of the time, frustrated all his undertakings, and left him a ruined man. His history may be read in his own work or in Mr. Smiles' *Industrial Biography*.

Dudley's invention, it would seem probable, depended upon *charking* or coking the coal, in a manner analogous to the making of wood charcoal. The coke thus prepared was comparatively free from sulphur, and more readily gave a strong heat. Dudley was thus able, according to his own account, to make five or seven tons of iron a week, selling his pig-iron at £4 per ton and his bar-iron at £12, while charcoal iron cost in pigs £6 or £7, and in bars £15 or £18. He relied for commercial success upon the cheapness of his iron compared with its fair quality, and he expresses clearly the true inducing cause and purpose of his invention,

"knowing that if there could be any use made of the small-coales that are of little use, then would they be drawn out of the Pits, which coles produceth oftentimes great prejudice unto the owners of the works and the work itself, and also unto the colliers."¹

The almost gratuitous use of fuel thus alluded to obviously led to Dudley's remarkable efforts towards our great manufacture. After Dudley's misfortunes his invention was not followed up. The want of wood was not yet severely felt, and the owners of woodland country and iron forges, of course, considered their interest in the charcoal iron manufacture as one to be protected. When Dr. Plot wrote his curious *Natural History of Staffordshire*, the making of pit-coal iron was a matter of unfortunate history, and he speaks of a certain German, Dr. Blewstone, as making "the last effort in that country to smelt iron ore with pit-coal."²

Thus the matter rested for half a century. The iron trade, which Andrew Yarranton, about this time, truly designated the keystone of England's industrial prosperity, was checked by the high and rising price of the metal; and the

¹ *Metallum Martis*, London, 1665, p. 8.

² Smiles' *Industrial Biography*, p. 77.

efforts made to get iron from Ireland or the Transatlantic Plantations had but a slight or temporary success.

It was Abraham Darby who revived the forgotten method of smelting with pit-coal. The earliest adventurers in the process, we have seen, were Germans, and it is curious that the success of the Darby family was founded upon foreign experience. The eldest Abraham Darby went over to Holland in 1706, and learnt the method of casting hollow iron pots, or Hilton ware, as it was then called. Bringing over skilled Dutch workmen, he took out a patent to protect his newly-acquired process, and then, in 1709, started the celebrated Coalbrookdale Works in Shropshire. At first the oak and hazel woods furnished fuel, but the supply presently proving insufficient for the growing trade, it became customary to mix coke and brays, or small coke, with the charge of fuel. Eventually, when an increased blast was obtained, coke took the place of charcoal entirely.

There is much uncertainty and discrepancy concerning the history of the Coalbrookdale Works. Scrivenor, in his *History of the Iron Trade*, represents pit-coal as used in 1713. Dr. Percy, on the other hand, describes the younger

Abraham Darby as first employing raw coal in the smelting furnace between the years 1730 and 1735.

In his first successful experiment he is said to have watched the filling of his furnace for six days and nights uninterruptedly, falling into a deep sleep when he saw the molten iron running forth. The success of the work was probably secured by the erection of a water-wheel of twenty-four feet diameter, capable of giving a powerful blast. But water was scarce, and a fire-engine, or old atmospheric steam-engine, was set up to pump back the water from the lower to the upper mill-pond. Here is one of those significant instances which teach us the power of coal and the interdependence of the arts. Employed in this engine as a source of motive power, it enabled coal to be also used in the smelting-furnace. And this is typical of the iron trade, as it is of other trades to the present day ; for our iron industry in all its developments is as dependent on coal for motive power as for fuel in the furnace.

In December, 1756, we find the works "at the top pinnacle of prosperity, twenty or twenty-two tons per week, and sold off as fast as made, at profit enough." And from this time and from

this success arose England's material power. To this invention, says McCulloch, "this country owes more perhaps than to any one else."¹

The subsequent history of the iron trade is best to be read in the growth of its produce. Already in 1788 the produce had risen to 68,300 tons, and the increase has since proceeded [till about 1870], as we have seen, in a nearly constant rate of multiplication.²

The chief difficulty experienced in the extension of the trade was the want of motive power. Thus Mr. J. Cookson introduced the coal iron manufacture into the Newcastle district, the blast being worked by a water-wheel on Chester Burn. But "frequent interruption, for want of water to drive their wheel, led at length to the furnace being 'gobbed,' and ultimately abandoned, about the close of the last [eighteenth] century."³

Roebuck originated the great iron trade of Scotland, and his success was due to the command of a good blast.

"Dr. Roebuck was one of the first to employ coal in iron-smelting on a large scale, and for

¹ *Literature of Political Economy*, p. 238.

² Chapter xi.

³ *Report of the British Association*, 1863, p. 738.

that purpose he required the aid of the most powerful blowing apparatus that could be procured. Mr. Smeaton succeeded in contriving and fixing for him, about the year 1768, a highly effective machine of this kind, driven by a water-wheel."¹ This contrivance is said to have been the blowing cylinder now used.²

Wilkinson was another great promoter of the iron manufacture, and his success arose from applying the steam-engine directly to work the blast-engine of his furnace near Bilston in Staffordshire.³

Cort's improvements in the puddling, faggotting, and rolling of iron blooms followed. The extensive use of such improvements depends upon the use of coal as the only fuel sufficiently abundant for the puddling, or reheating furnaces, and to supply the enormous power required in rolling iron bars of large size.

The discovery of the hot-blast process by Mr. Neilson is the next great step,⁴ and one of the most surprising instances of economy in the history of the arts. Ironmasters had previously adhered to the mistaken notion that a *very cool*

¹ Smiles' *Engineers*, vol. ii, p. 61.

² Percy's *Metallurgy, Iron*, p. 889.

³ *History of Wednesbury*, p. 116.

⁴ The date of the patent is 1828.

blast was essential to making good iron, and some even tried the use of ice in cooling the air of the blast. But when a blast of air, hot enough to melt lead, was used instead, the consumption of coal per ton of cast iron made was reduced *from seven tons to two, or two and a half tons.*¹ But was this enormous saving equivalent to a decrease of consumption? The produce of pig iron in Scotland increased as follows:—

Year	Tons
1820	20,000
1830	37,500
1839	200,000
1851	775,000
1863	1,160,000

Now, if we compare the consumption of coal in 1830 and 1863, we find—

$$\begin{array}{rcl} 37,500 \times 7 \text{ tons} & = & 262,500 \text{ tons of coal.} \\ 1,160,000 \times 2 \text{ tons} & = & 2,320,000 \quad \text{,,} \end{array}$$

Or the consumption of coal was increased eight-fold, not to speak of the consumption of coal in puddling or working the iron, or in the machine industry which cheap iron promotes.²

¹ Mushet, *Papers on Iron and Steel*, 1840, gives the consumption of coal in July, 1797, as nine and a half tons of coal for one ton of iron. In 1810 about five tons were used in Staffordshire, according to the same writer; in 1840 about three or three and a half (*Report B of Coal Commission of 1871*, p. 97).

² In reference to the effect of successive economies of fuel on the consumption of coal in the iron and steel industries, cf. p. 142, footnote.

A subsequent step of economy has been the utilisation of the waste gases of the blast-furnace in heating the blast, or the boilers of the steam-engines which drive the blast-engine. This improvement, however, was adopted extensively on the Continent, and in the United States, before it was introduced here in 1845. Now it is applied in all our iron-producing centres with perfect success.

In 1855 there was introduced one of the most ingenious improvements of the iron manufacture, that of Mr. Bessemer, [a process remarkable in the economy of fuel it effects, the molten iron being raised to the high temperature needed by the heat developed in the consumption of the impurities it is desired to remove. By the processes previously adopted about three and a half tons of coke were needed for the conversion of a ton of pig iron into steel. Bessemer's process reduced the consumption to about three hundred-weight of coke, required for fusing the metal preparatory to treatment by the blast. For some years,] indeed, the process was but half completed, because the stream of air forced through the molten cast iron was found to remove only the carbon and the silicon, leaving the injurious elements, sulphur and phosphorus, nearly un-

touched.¹ It is, therefore, necessary to use, in the making of Bessemer steel, ores which are free from impurities, the comparative scarcity of which caused the price of the steel for a time to remain high. [But this defect in the original process was in due time overcome by the modifications introduced about 1878 by Gilchrist and Thomas, which enable pig iron containing too much phosphorus for Bessemer steel-making to be converted, nevertheless, into excellent steel.] This invention, or series of inventions, has been one of those modes of economy which, in reducing the cost of a most valuable material, lead to an indefinite demand. [The labours of Bessemer, Siemens, Thomas, and Gilchrist have effected] one of the greatest advances in the arts ever achieved. Such are the wonderful qualities of steel that, if it be cheap enough, its uses are almost infinite. Our engines, machines, vessels, railroads, conveyances, furniture can all be made of it, with an immense improvement in strength, durability, and lightness. [The displacement of iron by steel which followed the cheapened methods of steel-making] was like a repetition of that substitution of iron for wood, in mill work, which Brindley and Smeaton and Rennie brought about.

¹ Percy's *Metallurgy of Iron and Steel*, p. 817.

And by still further multiplying the value of our coal and iron resources, it would have accelerated alike our present growth and the future exhaustion of our resources, [but for the fact that the new processes were applied with even greater advantage in other countries than in our own. The Gilchrist-Thomas process has enabled Germany to develop an iron industry more than adequate to meet the enlarged demand for steel, in that country, which followed the cheapening of its production. The ores of Lothringen and Luxemburg, of little value formerly in competition with those of Great Britain, have afforded an abundance of material for a production of steel as great as our own. In the United States, too, the enormous demand for steel has been met from the resources of the country itself, thus relieving our coal-fields from one source of exhaustion at an accelerated rate.]

When we reflect upon the conditions of our great production of iron, we shall see them to consist, apart from the ingenuity and perseverance which gave us the inventions, in the following :—

1. Cheapness and excellence of fuel.
2. Proximity of fuel, ores, and fluxes.

Of the first little need here be said. It will be

remembered that the first success of Dudley was obtained in the neighbourhood of the "Thick coal," where up to the end of the eighteenth century coal was a "drug"; and almost the same may be said of Coalbrookdale, where the final success was attained. And now, whether in South Wales, Scotland, Yorkshire, Staffordshire, or Northumberland, the iron manufacture most flourishes where suitable coal is to be had at the lowest rate.

As regards the second condition, it has been the constant reflection of English writers that the co-existence of the materials of the iron manufacture was not undesigned. "The occurrence of this most useful of metals, in immediate connexion with the fuel requisite for its reduction, and the limestone which facilitates that reduction, is an instance of arrangement so happily suited to the purposes of human industry, that it can hardly be considered as recurring unnecessarily to final causes, if we conceive that this distribution of the rude materials of the earth was determined with a view to the convenience of its inhabitants." In South Wales, Staffordshire, and elsewhere, there are often found in conjunction the coal, ironstone, limestone flux, as well as the refractory clay and

gritstone necessary for the construction of the furnaces. The fact, however, is that this is rapidly becoming an imaginary condition of our trade. The exhaustion of the ironstone seams in some places, the cost of working them in others, the increased facilities of transport by rail, new discoveries of superior ore, are rendering our iron-works more and more dependent on distant supplies of ore. Scrivenor says: "The great superiority of our iron manufacture has generally been considered (independently of the excellent quality of the coal) to consist in having all the materials necessary to the manufacture found on, or immediately in the neighbourhood of, the very spot where the furnaces are erected. South Staffordshire, *as it was*, will serve to illustrate this point—abundance of good coal—amongst other seams that of the tenyard—excellent ironstone and limestone; this last from Dudley; celebrated for its beautiful fossil slabs; but now limestone is brought from the vale of Llangollen, and the ironmasters are looking to Northamptonshire and other places to assist them with the required supply of ironstone. Is not this, as regards South Staffordshire, *the beginning of an end?*

"This scarcity of materials is certainly most

beneficial to districts where, from the want of coal, it was never contemplated having any share in the manufacture of iron; but it alters the general character of the circumstances under which we have been accustomed to view our superiority, and casts the first shadow upon the iron trade.”¹

Blackwell, in his lecture on the Iron Resources of Britain, although asserting that “in no other countries does this proximity of ore and fuel exist to the same extent as in England,”² describes how the facilities of transport are developing a new system. The iron trade, he says,

¹ Scrivenor on the *Iron Trade*, p. 301. The course of events, in reference to ore supply, in Staffordshire, during the last half-century, has been peculiar. In 1855, the ore raised was about 2,500,000 tons, which was more than enough to provide the material for the iron output of 855,500 tons in that year. By 1865 the iron output had increased to 898,890 tons, while the ore raised was but 1,484,900 tons, or sufficient for about 520,000 tons of iron, assuming average iron contents of 35 per cent. About 1870, or shortly after, about half the ore supply of the county was imported. An increase of ore raised, and a falling off in the make of iron, brought about a reversal of the current. By 1884 the make of pig iron, 575,900 tons, was less than the iron equivalent of the ore raised, 1,873,700 tons, this reversed relation dating from about 1880. The current has once more been reversed since that time, and in 1902 the make of pig iron in the county, 574,894 tons, required the use of 1,534,464 tons of ore, while only 815,379 tons were raised in Staffordshire in that year. (Cf. *Memorandum presented to the Royal Commission on the Depression of Trade and Industry*, by Sir Lowthian Bell, and the *Mineral Statistics* for 1902.)

² Page 150.

fosters itself by its own creation, the railroad. It is by this that the new-discovered, or rather the re-discovered, ores in the oolitic formation, stretching obliquely across England, are made available, saving the North of England and the South Staffordshire iron-works from stoppage under the competition of the Scotch blackband works. Of South Staffordshire he says : "Hitherto the second most important iron district in the kingdom, it could no longer have maintained its ground against other localities had it not been for this discovery. South Wales had its cheap and good coals, its blackbands, and its supplies of sea-borne hæmatites, as well as its own argillaceous ironstones ; Scotland its beds of blackbands ; and the North of England its oolitic ores ; but up to the present time South Staffordshire had only its argillaceous ironstones, always the most expensive to raise, with such admixture of hæmatite and North Staffordshire stone as the great cost of carriage would permit." ¹

It is even possible that recourse will some day be had to the Wealden ores, used in the old charcoal iron-works of Sussex, and which are both rich and plentiful, though too distant from coal for present use.

¹ Blackwell, p. 165.

It is an all-important fact of this subject, that the ore is carried to the fuel, not the fuel to the ore. This was the case when the pack-horse conveyed ore to the forges situated among the wood lands which supplied the charcoal. When timber-fuel was abundant in Ireland, ore was sent thither from England. In the still earlier times of the foot-blast the smelting hearth was shifted about the hills to the parts most abounding in timber, as may be inferred from heaps of scoria scattered here and there up to the very summit of the hills. And it is the case now, with all our superior means of transport and diminished consumption of fuel. The same fact is found elsewhere.

“Prussia is rich in iron ores, but they seldom occur along with the coal. In former times, the blast-furnaces were built where wood abounded and water power was available; but in later times, as the use of coal and coke became more and more general, it was found that the coal-basins were the fittest localities for the erection of works, as it was more easy and economical to take the ore to the fuel than the fuel to the ore.”¹

¹ Percy's *Metallurgy of Iron*, p. 564. The rule that the ore is carried to the fuel rather than the fuel to the ore still applies

Let us now consider the position and prospects of the English iron manufacture, comparatively to those of other countries, [both a generation ago, and at the present time.] The following were the amounts of pig iron produced by the three chief iron-making nations in 1862 :—

	Tons
Great Britain	3,943,469
France	1,073,300
United States	703,270

If the produce of all other countries were added, it would still be found, no doubt, that *our produce exceeded that of the rest of the world*, in spite of the rapid progress of the manufacture in France and America in the years immediately preceding the date in question. Not long before *our exports of iron were scarcely inferior to the gross produce of the rest of the world*.¹ This was not

generally. Ores from Lothringen and Luxemburg are smelted on the Ruhr coal-field. But the rule is far from universal, for coke is taken from the Ruhr to Lothringen, for the purpose of smelting the ore at the mines. The reduction in the amount of coke needed to make a ton of iron has made such a procedure feasible. Nearly $1\frac{1}{4}$ tons of coke must be brought to the ore for each ton of iron produced, but about 3 tons of ore need to be taken to the coal-field per ton of iron produced when ores of the grade of those of Lothringen are employed. In the United States the Lake Superior region supplies ores for smelting in the Pittsburg district, a thousand miles distant (cf. p. 401 and pp. 408-9 footnote).

¹ Truran on the *Iron Manufacture of Great Britain*, pp. iii, iv. According to the estimate of the pig-iron production of the world given in *Engineering* (April 8th, 1904), the British iron production exceeded that of the rest of the world in 1860 and in 1870, though

due to the quality of our iron. On the contrary, our cheap iron was some of the worst made anywhere. If we compare European iron-producing countries as to the quality and quantity of produce, the following were the orders, the higher place denoting the higher quality or quantity :¹—

Quality of iron	Quantity of iron
Sweden	England
Belgium	France
Prussia	Austria
Austria	Prussia
France	Sweden
England	Belgium

The inferiority of our iron was due to the sulphur, phosphorus, or other impurities of our fuel and ore. It was on this account that steel, even in Mr. Bessemer's process, had to be made from Swedish iron or other choice metal. And the exceptionally fine and high-priced English iron made by the Low Moor and Bowling Companies was chiefly due to the quality of the coal used.

by a narrow margin at the latter date. The estimates of *The Mineral Industry* (vol. i.) for each year, beginning with 1865, show the British output as being in excess of that of the rest of the world in 1865 and again in 1871, but not in any other year. For 1870 this latter estimate of the world's production exceeds that of *Engineering* by 160,000 tons in a total of about 12,000,000 tons. Till the very end of the seventies, the British production did not fall far short of that of all other countries together. A quick change of this relation came about coincidently with the introduction of the Gilchrist-Thomas process.

¹ *Canada at the Universal Exhibition of 1855*, p. 296.

[While, in 1862, Great Britain smelted one-half of the iron product of the whole world, in 1904 the share of this country in the world's output was but one-fifth of the whole, the make of pig iron in the principal iron-producing countries in that year being :—

	Tons (of 2,240 lbs.)
United States	16,497,033
Germany and Luxemburg . . .	9,941,556
Great Britain	8,562,658
France	2,951,575
Russia	2,902,410
Austria-Hungary ¹	1,362,055
Belgium	1,288,355

the world's product being estimated at about 45,000,000 tons. For the second year in succession, Great Britain has taken third place as a producer of iron. The United States first took the lead in 1890, and has maintained it since, except in the years 1894 and 1896, when the British output slightly exceeded that of the United States. The greatest yearly output of the latter country was in 1903, when it slightly exceeded 18,000,000 tons; but between the end of June, 1904, and the same date in 1905, the output exceeded 19,250,000 tons.² Since 1880 the pig iron production of the world has grown to two-and-a-half times its amount at that date. Belgium

¹ Hungarian figures for 1903, Austrian for 1904.

² For latest figures see p. 367.

has doubled its output, Germany has nearly quadrupled its production, the United States output has increased to not far short of fivefold, while that of France has increased by over 70 per cent. Meanwhile, the addition to the output of Great Britain, even using the output of 1899, the largest on record, for comparison, has been increased by but little over 20 per cent.

As already mentioned, one great influence operating to favour the increase in the output in the neighbouring Continental countries is found in the application of the Gilchrist-Thomas process for making basic steel from phosphoric ores. This has rendered available vast stores of mineral previously unworkable, and the extent to which this has affected the iron and steel industry of Germany in particular is shown by the fact that, of the 10,104,941 metric tons of iron produced in that country in 1904, no less than 6,300,047 tons were Thomas pig.¹ In 1902 the world's steel production is estimated to have been 33,350,000 tons, of which 14,902,000 tons were basic steel, from a quality of pig which could not have been profitably used by the original Bessemer or Siemens processes.² The great increase in con-

¹ *Engineering*, Feb. 10th, 1905.

² *Trans. American Society of Mechanical Engineers*, 1904.

sumption of iron and steel in Germany, Belgium, and France has been able to be met from resources near at hand, so that this country has not felt the increase of demand represented by the increase in the world's consumption of iron.

In the United States, the establishment of satisfactory means of communication has brought vast deposits of rich and easily-mined ore within effective reach of the great centres of iron production. Of the 35,500,000 tons of iron ore mined in 1902, all but 8,000,000 tons were supplied by the Lake Superior region.¹ The ores of this region are not only rich in iron, but of great purity, many of them being admirably adapted for the production of steel by the Bessemer process. Nearly half the supply from the Lake Superior region in 1902 came from the latest developed of the five ranges, namely, the Mesabi range, the first shipment from which was made in 1892. These ores are conveyed 50 miles by rail, then 800 miles by water, and then a further 160 miles by rail to the furnaces. The organisation of the means of transport has been so perfected that, in spite of the distance of 1,000 miles between the mine and the furnace, the ore can be laid down at the

¹ *Mineral Resources of the United States*, 1902.

furnace at a cost which, combined with the cheapness of coal in the Pittsburg district, and the excellent quality of the coal from which the celebrated Connellsville coke is produced, enables that district to rank as far the most important iron and steel-producing region in the United States.¹ In Alabama, the ore and the coal are obtained in the near neighbourhood of one another. Yet the pig-iron production of Pennsylvania in 1902 was 45·5 per cent of that of the United States, while Alabama ranked fourth among the States, with less than one-fifth Pennsylvania's output. Proximity of ore and fuel is no longer of the same importance as it was in the earlier days of the railroad and the steamship.

The progress of industry during the past quarter of a century has thus favoured the iron and steel industry of Germany and of the United States more than that of Great Britain. What is the outlook for the future ?

So far as it depends on ore supplies, the information supplied by Mr. J. S. Jeans to the Cham-

¹ The prices at lower lake ports, fixed by the Lake Superior Ore Association in 1902, were on the basis of \$4.50 per long ton (2,240 lbs.) for old range ores, guaranteed 63 per cent metallic iron, 0·045 per cent phosphorus; old range non-Bessemer ore, guaranteed 60 per cent iron, was on the basis of \$3.60. The corresponding prices of Mesabi ores were \$4.00 and \$3.20 respectively (cf. *Engineering*, June 10th, 1904, p. 827).

ertain Tariff Commission is of a somewhat reassuring character. Referring to British ores, it states that "the total available supplies have not only not been nearly exhausted, but we have as yet done little more than touch their fringe. It may be true that the best ironstone is not overabundant. It does not follow that the inferior grades cannot be utilised under other conditions. The shale ironstone cannot be worked so cheaply as the mineral now and hitherto produced. But, even so, it is presumed that when our best ore is gone, we shall be competing with other countries that are more or less in a similar position. It is certain that neither the United States nor Germany, at the end of twenty-five years from now, will any longer have virgin supplies, so far as our present knowledge enables us to make a forecast."¹ And again: "An important question is the character, as well as the quantity, of the ores that remain. In the older iron-producing countries the virgin supplies have been so far exhausted that the cost of the remainder, per unit of iron, has naturally tended to increase. This remark applies to the United States and Germany as well as to Great Britain. Hence our competitive position is not perhaps likely to become relatively less

¹ *Report of the Tariff Commission*, vol. i, § 973.

favourable. It is conceivable that it may even become more so.

“Hitherto the country that has depended mainly on home ores has probably been in the best position. This remark has certainly applied to the three countries dealt with. But is it not possible that in the future the country that has the best command of foreign supplies will rule? The position that I hold tends to bring under my notice much knowledge of such foreign supplies. The great iron-making countries are sure to find their home ore become dearer from year to year. Their foreign supplies need not necessarily increase in price. There is hardly any outside country that may not become tributary to our demands.”¹ At present, about one-third of the ore supply of Great Britain, representing nearly 40 per cent of the iron production, is obtained from abroad.²]

¹ *Report of the Tariff Commission*, vol. i, §§ 980, 981. The same writer, in his *Report to the British Iron Trade Association*, says: “So far as Europe is concerned the only competitive countries at present have no advantages over Great Britain. Indeed, most of them are less favourably situated, and all of them, like Great Britain, are compelled to import larger or smaller supplies from year to year, in order to supplement their own resources,” cf. *Journal of the Iron and Steel Institute*, No. ii, 1900, p. 589.

² One further point of interest may be mentioned. Up to 1878, the British home consumption of iron exceeded the exports of iron and manufactures of iron estimated in the equivalent of pig iron. From 1879 to 1893 the export exceeded the home consumption, the

The vast [and, until about 1882 rapid] extension of our manufacture has been due to *cheapness*, and this is the point of all importance in the great mass of cases—in bridges, rails, ships, heavy framework, pipes, fences, etc. *The use of iron is altogether boundless, provided it can be had cheap enough.* As Dr. Percy remarked, in spite of the marvellous advancement of the iron trade [at that time], “yet it may be safely affirmed that the uses of iron will be vastly more extended than at present, and that there is no just ground for apprehension lest there should be over-produce of this precious metal. Even the railway system is in a state of rapid growth, and the time will come, when every habitable part of the earth’s surface will be reticulated with iron or steel roads.”

Of the greatly increased supplies of iron required in the future general progress of nations, we shall continue for many years to supply a large part, and to enjoy the wealth and influence which it gives us. But this cheapness depends upon raising coal from our mines and running it

former having increased and the latter decreased, broadly speaking. Beginning with 1894, the domestic consumption has, except in 1896 and 1897, again exceeded the export, and this less from a falling off in exports than from a growth in domestic consumption, cf. Table 52, *Report of the Tariff Commission*, vol. i, § 195.

into our furnaces at a very low price. Now low prices cannot hold very long with a consumption of coal growing as it has been shown to grow. Were there no other demands upon the South Wales and Scotch coal-fields than that of the iron trade, yet this is of so unlimited an extent that sooner or later the voracious iron furnaces will exhaust our seams as they exhausted our woods. And the result must be a new migration of our great trade.

It is impossible there should be two opinions as to the future seat of the iron trade. The abundance and purity of both fuel and ore in the United States, with the commercial enterprise of American manufacturers, put the question beyond doubt.

The American iron manufacture was retarded by two chief causes:—

1. The fact that the coal, ore, and flux are not in such close conjunction as in England.
2. The high rate of wages in the United States.

The first obstacle has now disappeared. The Americans, of all people in the world, are the most forward in driving canals, river navigations, and railways where profit can be made. And

while the materials of the iron manufacture have been wedded together in the States, our iron-masters, as we have seen, are seeking their materials at greater distances. The very railway system, which is said to have saved the North of England and the South Staffordshire iron-works from a scarcity of materials, has enabled the Americans to overcome their great obstacle, and thus one advantage of the English manufacturer becomes illusory.

[“In the past era of Britain’s unquestioned manufacturing supremacy, it was an axiom that, as an engineering nation, we were secure because iron ore, coal, and limestone not only existed in abundance with us, but that ours was the only country in which they were found in close proximity. Latter-day discoveries have shown that even this geological advantage is not confined to our shores; but that is of less importance since so large a part of the ore used for steel manufacture is transported great distances.

“The ores of the Lake Superior district are smelted in Pennsylvania, Ohio, Illinois, Michigan, Wisconsin, New York, New Jersey, Virginia, Kentucky, and Missouri. The Wyoming and New Mexico ores are taken to furnaces in Colorado, whilst the magnetites of Lake Champlain are

sent to the Pennsylvania Iron and Steel works." ¹

In Alabama, the Virginias and Tennessee, ore is raised in the near neighbourhood of the furnaces, but it is of lower grade than the Lake Superior ores, and expectations based on the nearness of ore supplies to the fuel have not been fully realised. The efficiency of modern means of transport in the United States has gone far to neutralise the disadvantage of long distances separating ore and fuel.²]

The high rate of wages in a new country like the States is a true and natural obstacle to the progress of a manufacture, but as we shall see in the next chapter, [and as the experience of the last quarter of the nineteenth century has demonstrated,] it is one which time can overcome.

If the Americans have obstacles to overcome, they have advantages in cheap and good mineral fuel, which cannot be over-estimated. The bituminous coal of Pennsylvania and Ohio is got almost for the mere price of quarrying, as coal

¹ *Engineering*, June 10, 1904, p. 827.

² The conditions which determine the most advantageous situation for an industry include easy access to the market for its product. This, as well as the grade of the ores used, has influenced the relative growth of the iron industries of Pennsylvania and Alabama. "It is one of the surprises of American industry," writes Professor Taussig, "that iron manufacturing on a huge

used to be got in Staffordshire, and it has served as the foundation there, as it did here, of a great iron-working industry. Pittsburg is the American Sheffield and Wolverhampton.

scale should be undertaken at . . . points, distant alike from ore and from coal, and having no natural advantages whatever. The coke is moved hundreds of miles by rail from Pennsylvania, and meets the ore, which has travelled no less a distance from Lake Superior. Ease of access to the western market gives these sites an advantage, or at least goes to offset the disadvantage of the longer railway haul of the fuel. . . . But the coal region itself,—western Pennsylvania and the adjacent parts of Ohio—remain the heart and centre of the iron industry.” (*The Iron Industry in the United States, Quarterly Journal of Economics*, Feb. 1900, p. 154.)

The distribution of iron-smelting in western Germany is similarly affected by considerations relating to the marketing of the product, as well as by those relating to supplies of ore and fuel (cf. p. 397).

CHAPTER XVI

THE PROBLEM OF THE TRADING BODIES

THE position of this country in future years will not be rightly appreciated if we confine our attention near home. Without foreign commerce, but with our coal, it is possible we might have done much that we have done, but we could never have supported such masses of busy population, enjoyed such a variety of foreign products, or reared such a great system of industry. We should have been a happy, ingenious, self-dependent people, but not numerous nor rich, and neither endowed with our present world-wide influence nor subjected to its dangers and responsibilities.

But as we are, unfettered commerce, vindicated by our political economists, and founded on the material basis of our coal resources, has made the several quarters of the globe our willing tributaries. "Though England," it has been

truly said, "were one vast rock, where not an acre of corn had ever waved, still those four hundred millions of men, whose labour is represented by the machinery of the country, would extort an abundance of corn from all the surrounding States."¹ The plains of North America and Russia are our corn-fields; Chicago and Odessa our granaries; Canada and the Baltic are our timber-forests; Australasia contains our sheep-farms, and in Argentina and on the western prairies of North America are our herds of oxen; Peru sends her silver, and the gold of South Africa and Australia flows to London; the Hindus and the Chinese grow tea for us, and our coffee, sugar, and spice plantations are in all the Indies. Spain and France are our vineyards, and the Mediterranean our fruit-garden; and our cotton-grounds, which for long have occupied the Southern United States, are now being extended everywhere in the warm regions of the earth.

But great as is our own system, it is not the whole. Commerce is undoubtedly making its way by its own subtle force, and is uniting the

¹ H. Fairbairn, *Political Economy of Railroads*, p. 113.

The horse-power of the machinery of the country is, of course, far greater now than at that time.

parts of the globe into a web of interchanges, in which the peculiar riches of each are made useful to all. The sum of human happiness is thus being surely increased, but we should be hasty in assuming that the growth of general commerce ensures for this island everlasting riches and industrial supremacy.

We ought not to forget that the enjoyments of a commercial country are not without probable drawbacks. We are no longer independent. The rise and decadence of other trading nations is no longer a matter of indifference to us. Our profits depend upon comparative, not absolute, riches, and as an individual nation we may find harm in foreign wealth.

And our anxiety must be indefinitely increased in reflecting that, *while other countries mostly subsist upon the annual and ceaseless income of the harvest, we are drawing more and more upon a capital which yields no annual interest, but once turned to light and heat and motive power, is gone for ever into space.*

So far indeed as trade is dependent on legislation and social and political conditions, its future must be almost wholly uncertain and beyond the reach of reasoning. The development of history cannot be predicted, for in the "still and mental

parts" of a single unborn individual may reside the forces which are to move the world. But industry and riches must have a material basis, and it is in this respect their future course comes somewhat within the grasp of science. The principles of economy have been so far investigated by our own writers that with given material conditions the tendency of trade may often be certainly inferred. And if we may assume that the spirit of commercial freedom will spread and suffer no serious relapse, it is quite possible to foresee the necessary course of trade.

Taking commerce as the free growth of the instincts of gain, we find it resolved into a case of complex attractions and perturbations, as between several gravitating bodies. Trade between two bodies is a case of simple attraction, each naturally attracting and buying the articles which are made *with greater comparative facility and cheapness* by the other, paying with its own *comparatively cheaper products*. There is or should be no competition between them; each State should develop the kinds of industry and sources of wealth opposite to those of the other State. Free interchange of products then raises the economy of labour to its highest pitch.

In proportion, too, as the circumstances or industries of two States are more diverse will trade between them be more to the advantage of each. Two countries whose circumstances are exactly alike can have no motive to trade with each other. Prices will bear the same proportions in each, and thus will leave no margin of profit on exchange, even to pay the freight. And this result will hold, too, even if one country were naturally richer in every way than another, provided it were in every particular equally richer. Thus, if a man with a given amount of labour could raise both twice as much corn and twice as much wool in Australia as in England, we could have no trade with Australia in these articles. But if the same labour could raise twice as much wool but only just as much corn there as here, profit will evidently be gained on the exchange of wool and corn. To the writings of Ricardo, and especially of John Stuart Mill,¹

¹ *Principles of Political Economy*, book iii, chap. xvii.; or, *Essays on some unsettled Questions of Political Economy*. Essay i.

The subject "Of the Competition of different Countries in the same Market" is treated by J. S. Mill. *Principles*, book iii, chap. xxv.

For discussion of some disputed points in the theory of the subject, reference may be made to Jevons' *Theory of Political Economy*, chap. iv, pp. 141-6; to Bastable's *Theory of International Trade*, Appendix C; and to Professor Edgeworth's articles in, the *Economic Journal*, vol. iv, on the *Theory of International Values*.

we are indebted for the discovery and distinct explanation of these principles.

When three States trade with each other, the problem is one of some complexity. A State possessing any peculiar kind of riches may profit and confer profit by trade with each of the other two, and the highest advantage will arise when each devotes its labour exclusively to kinds of industry in which it has comparatively the greatest facilities, or natural riches. If two of the States, however, are of similar circumstances, they cannot trade with each other, but only each of them with the third. And the total trade will have to be shared between the two similar States in some proportion to their absolute capacities of production. For if one had a larger share than this, its powers would be harder pushed and prices somewhat raised, which would at once cause trade to flow more towards the other similar State. If one of these similar States were to grow in absolute powers of production, it must take a greater share of the trade with the third State and positively abstract a portion of the trade between the other two, to the injury, not of the third, but of the second similar State.

The question is now sufficiently complex to

illustrate our actual position. In reality the countries with which we trade present a problem of almost infinite complexity, but for simplicity we may form a few great groups according to similarities of condition. Five groups may be made to comprehend all countries with which we have relations of importance to our present subject.¹

1. Great Britain, capable for the present of indefinitely producing all products depending on the use of coal.

2. Continental Europe, capable of an indefinite production of artistic, luxurious, or semi-tropical products, but debarred by comparative want of coal from competition with us.

¹ The argument presented in the remainder of this chapter has been left as Jevons framed it, with but trivial verbal changes here and there for the most part. The reader should bear in mind that it relates to the situation forty years ago. Some of the changes which are foreseen in it, and expected to occur within a century, are already in evidence, though less than half that interval has elapsed since it was written.

In reference to the position of Germany, as well as with regard to the industrial development of the United States, serious modifications of the grouping of countries which follows must have been made had the chapter had the advantage of revision by its author at the present time. To attempt to divine what those alterations might have been seemed a task so full of risk that it were better abandoned. The general argument can be applied to the existing situation by the reflecting reader, without the aid of a recasting of a chapter which is reckoned among the classical literature of economics.

3. Tropical, Eastern, and other regions, capable of supplying food and raw materials, but of climate and other natural conditions wholly different from those of Great Britain.

4. Australasian, African, and American colonies, capable of an immense production of raw materials, but endowed with no considerable coal resources.

5. The United States of North America, capable of an immense production of corn and raw materials, but also possessing coal deposits many times as great as our own.

At present Great Britain carries on a growing trade with all the other four bodies. The older nations of Europe, indeed, check the trade by restrictions upon the repeal of which we cannot certainly count. Our trade with Western Europe, too, is of a different character from that we enjoy elsewhere, because as the ancient seat of the arts, and endowed with considerable mineral riches, we find there our own superiors in many finer kinds of manufacture. With respect to France and Western Europe, then, we are mainly producers or traders in raw materials. Towards the Tropical, Eastern, Colonial, and American bodies, in fact to the world generally, we are manufacturers, seeking materials to operate, or food to

live upon, and giving in exchange the products of our machine labour.

Suppose trade to spread according to that spirit of progress which seems almost the established order of things. For many years to come our relations will remain of the same kind as at present. Europe will receive more and more crude iron, coal,¹ metals, and other materials, returning food, or elegant articles, while other parts of the world will take more finished products and return their appropriate raw materials. Wherever we trade it will be upon coal, or its more or less refined products. There is no saying that we may not thus progress for the greater part of a century, allowing our manufacturing population to quadruple itself, and our industry to multiply itself many times.

Let us now consider the changes that are going on within the several trading bodies. In Great Britain the agricultural population is about stationary, and its offspring has to find employment in the towns, or else to migrate. So familiar, too, is emigration becoming to us, so

¹ A feature of our coal exports which is provocative of much anxious comment is the large amount supplied to Europe. Of the 46,255,547 tons of coal exported in 1904, no less than 36,514,017 tons were sent to various European countries.

great are the facilities and foreign attractions to it, and so congenial is it to the British character to seek independence and adventure across the seas, that a continuous exodus of our population is already a necessity. Our emigrants either reside as agents and merchants in foreign ports and countries where they powerfully stimulate trade with England, or they settle in the colonies and States of which they increase the productive powers. And we must not forget that the kindred nations of Germany are suffering an exodus almost comparable to our own, and are similarly contributing to the growth of our colonies and the United States.

Supposing protective and restrictive tendencies not to gain ground, we shall continue to grow on the one side as a great manufacturing body, while the colonies and most foreign States will find a source of wealth and advantage in supplying us with raw materials and developing the kinds of industry for which their facilities are almost boundless as compared with ours.

But the growth of production cannot go on *ad infinitum*; natural limits will ultimately be reached on the side both of the agricultural and of the manufacturing country, even if no political

events intervene to check the trade. Suppose some event to occur and prevent our growing population from meeting a corresponding increase of subsistence. From established habits of prosperity and early marriage we shall continue to grow with a certain inertia, but the rising generation will not find the comfort and early independence they were brought up to expect. They will turn to emigration as a congenial resource, and apply their labour to stimulate trade and the production of raw materials in many parts of the world. The corresponding demand for our manufactures will then tend to support or revive the progress of industry at home, and maintain the long existing rate of multiplication.

It is by a process of this sort that the recent emigration,¹ incited to a great extent by the gold discoveries, has contributed to the late extraordinary increase of wealth. It has encouraged our population to adopt new habits of early marriage. And in America, Australia, Africa, Asia, and the Pacific Archipelago there are open lands and undeveloped natural resources which still admit of a vast extension and continuance of the same process.

¹ The emigration of the fifties.

Not to speak of the maritime nations, especially the Spanish and the Dutch, who preceded us in extensive colonisation, the custom of planting out colonies with us dates back three centuries, to the time of Queen Elizabeth. As early as 1681 an English writer¹ clearly explained that *plantations* were not an exhausting drain upon the mother country, but rather "a wheel to set most of our other trades agoing."

"The plantations," he said, "do not depopulate, but rather increase, or improve our people," and they "have increast the profitable employments, not only by building of ships, carrying out our manufactures and products thither, but also by returning theirs hither to supply ourselves, and also a great part of the rest of the world."

When we look either to the trade the colonies carry on with us, to the internal happiness they enjoy, or the benefits which they promise to the world in the future, it is impossible to overvalue the Anglo-Saxon spirit of colonisation.² But when we follow out a policy of free colonisation to its

¹ John Houghton. *Collection of Letters for the Improvement of Husbandry and Trade*. London, 1681, pp. 35, 36.

² See the admirable lecture of Prof. J. E. Cairnes to the Dublin Young Men's Christian Association "On Colonization and Colonial Government," Oct. 26, 1864 ; in the volume of *Political Essays*.

necessary ultimate result, the prospect is more pleasing to a citizen of the world than to a citizen of this small kingdom. For free and voluntary emigration enables and induces our home population to go on multiplying at high rates, otherwise impossible. Not only, then, have we a growing population, but a growing margin also, who, even in times of the highest prosperity, must seek abroad the subsistence not to be had at home. The longer our prosperity continues unslackened, the more necessary a free outlet will become. But the moment to be apprehended is when the first general check to our prosperity and growth at home is encountered. Then the larger part of the rising generation will find themselves superfluous, and must either leave the country in a vast body, or remain here to create painful pressure and poverty. A less active people than the English might endure the latter alternative, and sink by degrees into the stationary condition which characterised some Continental nations, and England herself in the early part of the eighteenth century. But we may well refuse to look forward to such a change here, so painful must be the disappointment of the best hopes which must accompany it. Nor could we feel sure that our popular institutions

could pass unharmed through a period of general pressure and want of employment among a vast artisan population.¹

The alternative, I say, is wholesale emigration. "The only immediate remedy," says Mr. Senior,² "for an actual excess in one class of the population, is the ancient and approved one, *coloniam deducere*. . . . It is a remedy preparatory to the adoption and necessary to the safety of every other." We have seen in the chapter on Population how our agricultural districts in 1811-31 passed through a period of pauperism and excess of population due to an unwarranted growth of population. The gravest fears for our social soundness were excited, and the evil was only overcome by extensive migration into our towns and colonies. The Scotch Highlands, and more lately Ireland, have presented still more striking instances of the choice between pressure at home

¹ A realisation of the distress due to the causes here indicated may perhaps be found in the depression of the eighties, though its early occurrence is distinctly contrary to the anticipations expressed by Jevons. It was certainly accompanied by a greatly reduced rate of increase of coal production, and by active emigration. Perhaps it may be assigned to other causes than the development here contemplated, and we may regard the experience of that time as a foretaste of what is to be looked for later on, if the industrial development of the country continue on existing lines.

² *Three Lectures on Wages*. Preface, p. v.

and migration abroad. It is only a question of time when our whole population, including that of our present most progressive towns, will be placed in the same dilemma, and the result must be a vast and continuous exodus.

But now comes the most serious point of all. *After a certain period emigration will begin to have a very different effect upon the destinies of this country from that it now exercises.* Instead of extending across the seas an agricultural system in harmonious union with our own manufacturing system, it will develop, or rather complete, abroad systems of iron and coal industry in direct competition with ours. The process will be of a two-sided nature.

It is well known that in spreading over a new country, settlers are naturally apt to exhaust the virgin soil they get so cheap, regardless of manures and agricultural arts by which its fertility might be maintained. Upon a process of this kind the able argument of Prof. Cairnes in his *Slave Power* is founded; but exhaustive agriculture and migration are the necessary results, in any country or social system, of a boundless supply of rich lands. It must pay better to take the cream off the land when the farmer can freely select new farms of untouched

richness. A gradual inland migration is the result, and so rapidly has this gone on in the United States towards the West, that already the settlers in the [States of Washington, Idaho, Montana, and Wyoming ¹] are on the verge of deserts that never can be cultivated. And we cannot but acquiesce in the apparently extravagant estimates of American writers concerning the future growth of their population. So long as there is security for life and property left, people will multiply over lands so rich that, as an American orator said, "if you tickle them with a hoe, they will laugh with a harvest."

To appreciate the growth of the American people we need only look upon the results of the American census.

¹ The region described by Jevons as "Minnesota, Washington, and Nebraska territories" is now covered by the States of North and South Dakota, Nebraska, Wyoming, Montana, Idaho, and Washington. The territory of Minnesota became part of the territory of Dakota in 1861, and the designations of 1860 appear to have been those of which Jevons made use. The first three States are classed as semi-arid, the other four as arid. Of course the division between semi-arid and arid regions does not conform precisely to political boundaries. The utilisation of considerable areas by means of irrigation yet leaves it generally true, so far as may be foreseen, that the deserts can never be cultivated. (Cf. *The Territorial Expansion of the United States* in the *Monthly Summary of Commerce and Finance*, May, 1904, p. 4326, and *Report of the Twelfth Census*, vol. vi, pp. 820-867.)

POPULATION OF THE UNITED STATES¹

Year	Population	Numerical increase	Rate per cent of increase
1790	3,929,214		
1800	5,308,483	1,379,269	35
1810	7,239,881	1,931,398	36
1820	9,638,453	2,398,572	33
1830	12,866,020	3,227,567	33
1840	17,069,453	4,203,433	33
1850	23,191,876	6,122,423	36
1860	31,443,321	8,251,445	36
1870	38,558,371	7,115,050	29
1880	50,155,783	11,597,412	30
1890	62,947,714	12,791,931	26
1900	76,085,794	13,138,080	21

If we compare the above with the corresponding results for our population,² it will be seen that we have scarcely anything here to equal the rate of American increase in constancy or amount. The general rate of growth in America during the first sixty years of the nineteenth century was double our highest rate (18 per cent) for the country as a whole, and equal to the rate of progress of Glamorgan in the

¹ Cf. *Twelfth Census of the United States*, vol. i, p. xx. The figures relate to the continental United States, not including Alaska.

² Chapter x.

thirty years preceding 1861, or of our manufacturing towns at their period of most rapid increase.

The very emigration which checked the rapidity of our growth has contributed to maintain that of America, and nothing is more probable in political matters than that its population will continue to grow both by internal multiplication and by vast and ceaseless increments from Europe. With such a growth of population, agriculture must soon be carried to its first limits. Within a century the choicest lands will have been taken up,¹ and the second and third rate lands must be settled, or the old exhausted lands revived by more diligent culture. Agriculture will begin to lose its extremely easy and profitable character in the States.

On the other hand, coal, yet to be had at the mere cost of quarrying, will offer more and more tempting employment comparatively to agriculture. In other words, labour, no longer drawn away by the superior attractions of agriculture,

¹ Already, within less than half a century, the choicest lands have been taken up for the most part. The opening up of the Canadian West provides attractions to those who are drawn to an agricultural life, so that, so far as North America as a whole is concerned, the profits of agriculture still afford a strong counter-attraction to the wages of manufacturing industry, and population moves freely across the international boundary line.

will become abundant in manufacture, and at last a sound system of metallurgical industry will grow up on the banks of the Ohio, capable of almost indefinite extension.¹

It is this decadence of agriculture joined to the rise of a manufacturing system which most distinctly threatens our commercial position. Corn will be growing dearer in the States, while coal and iron are growing dearer here. The industrial conditions of England and the States will thus approximate to equilibrium, and the advantages of trade will diminish. We shall neither buy corn from them, nor sell iron articles to them. And at the same time America will tend to supplant us in the European market for iron and other crude materials, and in all parts of the world in the market for textile and useful manufactured articles in general.

Then, if not before, the continuous multiplication of our home population and industry will receive a check, and a definitive choice of whole-sale emigration or a change of habits will be

¹ The development of the iron and steel industry in the Pittsburg district has more than realised the anticipations justly entertained by Jevons. In a quarter of a century from the time at which he wrote, the United States had taken the first place among the nations of the world as a producer of iron and steel.

In reference to the events of the present, the succeeding paragraph in the text has very great significance.

presented to us. And it must be further observed that by the time in question our consumption of coal will certainly be several times as great as at present.¹ Our total available stores of coal divided by the annual consumption will give a proportionately shorter period of even stationary duration. And while our colonial states will be growing in the vigour of youth, receiving our whole offspring, and establishing new currents of trade far from our shores, our strength will tend to fail continuously.

Of course at the worst we shall not be devoid of many resources. Our position, "anchored by the side of Europe," and close to the terrestrial centre of the globe, gives us a claim to the carrying and trading business of the world, which previously belonged to our close neighbours the Dutch. And our manufactures, though they must diminish in size and importance, may improve in finish and artistic merit. Our work

¹ If we are to regard the development of manufacturing industry in the United States as the sign that the time here referred to by Jevons has already arrived, its early arrival results in the fact that our coal consumption is much less than he expected it would be when the events he indicated should occur. The early industrial maturity of the United States illustrates the difficulties of forecasting economic events. The situation contemplated for Great Britain may yet be far distant.

will be that of the trinket and the watch rather than that of the herculean engine—handiwork rather than machine work. We shall probably approximate to the manufacturing condition of Western Europe, and the extreme elegance of our earthenware, glass, and many small manufactures raises the hope that we may attain a high rank in artistic manufactures.

But excellence in such smaller matters can ill compensate for the loss of our supremacy in the elements of engineering and maritime success. When navigation and the construction of a fleet is a pure question of coal mining and iron metallurgy, it is hard to see how we can insure that invincibility on the seas which is essential to the safety of an insular nation dependent on commerce for its very bread.

The rate of our progress and exhaustion must depend greatly upon the legislation of colonies and foreign States. Should France revert to a less enlightened commercial policy; should Europe maintain or extend a prohibitory system; should the Northern States succeed in erecting a permanent Morrill tariff for the benefit of Pennsylvanian manufacturers; and should the tendency of all our colonies towards Protection increase, the progress of trade may indeed be

vastly retarded. Under these circumstances the present rapid rate of our growth may soon be somewhat checked. The introduction of railways, the repeal of the Corn Laws, the sudden settlement of our Australian colonies, may prove exceptional events. Then, after a period of somewhat painful depression, we may fall into a lower rate of progress, that can be maintained for a lengthened period, passing out of sight.

But on the whole Free Trade is likely to extend itself on the Continent. Our colonies, after a brief experience, may see through their mistaken and highly prejudicial views; and the Americans will hardly succeed in their apparent object of rendering their continent a self-contained Chinese-like empire, unknown to European trade and intercourse.¹ And in other parts of the world—Africa, Asia, and South America—there

¹ That the expectations of the Free-traders of his time, which Jevons shared, and to which he here gives expression, have not been fulfilled, is a familiar fact, the reasons for which need not be discussed here. A return to high Protection in the United States, and an unmistakable tendency in our leading colonies to follow in the same path, are also facts not in agreement with Jevons' hopes. Though there are some indications of a change of policy by the United States in the not distant future, the outlook is too uncertain to justify a definite forecast in that sense.

The correspondence of the history of the last twenty-five or thirty years with the possible sequence of events sketched in the preceding paragraph of the text is worth particular notice.

is sure to be a general, and perhaps a very great, opening for future trade.

It may reasonably be questioned whether a great and continuous increase of our industry is desirable from a national point of view. But for those colonies and countries which trade with us it is an unalloyed benefit. Corn would be a drug in North America, animal products in South America, and wool in Australia, but for the market we offer ; and were not political economy a rather rare and difficult study, the inhabitants of the States, and of our colonies generally, would be aware that the development of the pastoral and agricultural powers of a new country is the first and most appropriate source of riches. It is the very profits thus gained that render wages high, and labour, as it is said, too scarce for manufactures to exist. To receive the products of a mature system of labour, like that of England, in return for the raw products of the soil, is the true mode of creating a rich and populous colony. When the soil is fully occupied it will be time to think of imitating and competing with older countries.

But manufacturers are always the first, as Adam Smith and Sir Robert Peel remarked, to desire artificial restrictions. Colonial manufac-

turers constantly aver that the overflowing pauper population of the old world enables it to undersell the productions of a colony. And they seize upon a paragraph in Mr. Mill's *Political Economy*,¹ in which that eminent writer cautiously recommends Protection as a convenient mode of giving a first impulse to a branch of manufacture. Mr. Mill can hardly know the evil which his words are working, misapplied and distorted in meaning as they are for interested purposes.

It is, indeed, a reproach constantly hurled upon England, even by her own offspring, that she only removed her restrictions—her navigation laws, her prohibition of the export of machinery, and of the import of continental manufactures—when they were no longer necessary. It is, however, quite doubtful whether we derived any real benefit from the navigation laws; there is no doubt that the other restrictions were a great injury to our progress, and in no way assisted the rise of our arts. The attempted strict exclusion of continental manufactures greatly conduced to our stationary condition in the first half of the eighteenth century, and I am wholly

¹ *Principles, etc.*; book v, chap. x; third edition, vol. ii, pp. 507, 508.

unable to see how it in the least forwarded those great inventions in metallurgy and mechanism which did cause our rise. Yet we continually meet in foreign authors such remarks as these: "The requisite skill and development of the mineral resources have been obtained by a century of experience, when *foreign competition was religiously excluded by prohibitory duties*, until England could make iron cheaper than all the world, and since then domestic competition has cheapened the processes, and reduced the cost to the lowest practicable limit."

The falsity of the statement as regards the point in view is apparent. From the very same writer I have already quoted the statement that *about the middle of the eighteenth century England imported four-fifths of the iron she consumed*.¹ The high price of iron had long retarded, not forwarded, the progress of the engine, the railway, and the mechanical works generally by which alone our manufacturing system could be adequately developed.

Our growth has been nourished by freedom, not by restrictions; and if kindred colonies and nations and foreign States wish to raise the

¹ P. 379 *supra*.

world into the earliest and highest state of wealth, they will push trade to its utmost without jealousy of the immediate wealth it confers upon us, in virtue of our coal resources and our well-developed skill.

Any attempt on the part of foreign nations to cripple the development of our trade injures them far more than us. The Morrill tariff¹ almost wholly recoils upon the nation which submits to it. The effect upon us is seen in a temporary and inconsiderable check to one or two of our branches of industry. Its effect upon America is to cut it off from intercourse with the rest of the civilized world, to destroy its maritime influence, and to arrest, as far as human interference can arrest, the development of a great State. No doubt it enables a manufacturing interest to grow half a century or more before its time; but just so much as one interest is forcibly promoted so much are other interests forcibly held back. And no system of industry thus requiring the unnatural stimulus of government protection can compete with foreign systems

¹ If read as applying to 1905, Dingley tariff must be read instead of Morrill tariff, both here and wherever reference to the latter occurs.

stimulated by natural circumstances. When manufacture is naturally more profitable in America than in Britain we shall be supplanted, and not before then. The advent of that period can be hastened only by freedom of industry and trade, not by legislative devices.

CHAPTER XVII

OF TAXES AND THE NATIONAL DEBT

A FEW pages may be given to considering the policy of imposing duties and restrictions with a view to limit the consumption of our fuel.

The prohibition of the export of coal is the first step which naturally suggests itself, and it has often been advocated. Dr. Buckland, when asked, before the Committee on the Coal Trade of 1830, his opinion of the policy of allowing exportation, answered: "It is permitting foreigners to consume the vitals of our own prosperity. I consider coals the stamina upon which the manufacturing prosperity of the country primarily depends; and I think it our duty not to spare one ounce of coals to any person but ourselves."

The imposition of a more or less heavy duty on the export of coal is certainly the way we should commence a prohibitory system. Such a

duty might be imposed for any of the following purposes :—

1st. To raise revenue.

2nd. To cripple the competing manufactures of other nations.

3rd. To discourage exportation, and thus spare our stores of coal

It is plain that the first purpose is more or less inconsistent with the other two.

I can see no general reasons against levying revenue by an export duty. Sir R. Peel adopted as a principle of English finance, "that with respect to exports there shall be no duty leviable. I am unwilling to make any exception to this principle."¹ And to the present day the rule has, I believe, been upheld without exception. Yet there are no principles of economic science, so far as I know, bearing against export duties that do not equally bear against import duties. There are only the general arguments against any restrictions on commercial intercourse. In fact, Sir R. Peel had himself previously said, when proposing the coal-tax of 1842 : "I must say I cannot conceive any more legitimate object of duty than coal exported to foreign countries.

¹ *Hansard's Debates*, third series, vol. lxxvii, p. 478.

I speak of a reasonable and just duty, and I say that a tax levied on an article produced in this country—an element of manufactures—necessary to manufactures—contributing by its export to increase the competition with our own manufactures—I think that a tax on such an article is a perfectly legitimate source of revenue.”¹

Lord Overstone, too, asserted in his speech on the Commercial Treaty with France—a speech distinguished by his usual clearness and soundness of thought—that an export duty on a commodity of peculiar value and limited supply, like coal, may be an advantageous and legitimate source of revenue.

Instances of export duties of a similar kind are not wanting, but they are rather unfortunate instances. The Spaniards taxed Peruvian gold; the Sicilian Government, sulphur; Russia, its products of tallow, hemp, and flax. In India we raise a large revenue of the kind on opium, and the Slave States proposed an impost on cotton. Too high a duty, indeed, is apt to draw out foreign competition, and ruin at once the trade and revenue, as the sulphur trade of Italy was for a time ruined. But we do not fear competition with Newcastle coal; we rather desire

¹ *Hansard's Debates*, third series, vol. lxi, p. 448.

to avoid foreign competition to buy it, and there seems accordingly to be no abstract objection to a duty on coal exported.

But I think that Lord Overstone, in advocating such a duty as a source of revenue, must have overlooked that peculiar relation of coal to our shipping interest which I have endeavoured to explain in chapter xiii. The fact is, that such a tax would be paid by ourselves as entirely as the tax on dogs or men-servants, with the further disadvantage that *we should pay it through and to the discouragement of our navigation. It would be equivalent to a duty on outward tonnage.*

For as our coals, in nearly every part of the world, meet and compete with inferior native coals or other fuel, the freight and price have to be lowered until the competition is successful. If a 4s. coal duty were imposed, our shipowners would receive about 4s. less freight to most places,¹

¹ The figure of 4s. has been left as in the earlier editions, in spite of the fact that, at the lower range of freights prevalent now, as compared with forty years ago, a deduction of four shillings from freight rates would convert a profit into a large loss in the majority of cases. In fact, the deduction of 4s. could not be made generally at the present time. The arguments placed before the recent Royal Commission tended to show that shipowners had felt severely the burden of the tax of 1s. per ton imposed in 1901.

If he could have revised his book to-day, Jevons would probably have altered the discussion of a hypothetical tax and its results into a consideration of the actual tax and its consequences. The reader is left to apply Jevons' principles to current facts for himself.

which consumers would ultimately pay in the shape of increased inward freights and prices of foreign articles. At the same time it must be allowed that the reduction of outward freights would stimulate the exportation of any other heavy commodities like bricks, cement, earthenware, slates, flag-stones, paving-stones, salt, pig iron, etc., which could be found profitably to take the place of coal as ballast. On the whole it may be said that there are even more reasons against a tax on coal *as a source of revenue* than might be urged concerning most taxes. It would be paid out of our own pockets as much as the income-tax, and would act besides as a restriction on commerce and a burden on navigation.

To impose a duty on coals to injure continental manufactures in the sea-board towns, is a purpose that no English statesman in the present day would avow. It was on the contrary argued by Mr. Gladstone and others, in carrying the Commercial Treaty with France (of 1860) through the House of Commons, that a large manufacturing interest on the French coasts, dependent on English coal, would be an excellent guarantee for the peace and extended intercourse we so ardently desire with that country.

There only remains the question of a partially

or completely prohibitory duty on the simple and legitimate ground of self-defence, to save our posterity, if possible, from the misery and danger that a failure of our coal mines would bring upon them. If, indeed, we are again to resort to restrictions on trade, it is not apparent why we repealed the Corn Laws, which might have been far more efficient in preventing the exhaustion of our coal mines than any measures we are now likely to adopt. Nor is it quite apparent why we should stop the export of coal and not that of pig iron, every ton of which represents the consumption of about two tons of coal. The question of a prohibitory tax is but a part of the general question whether we do wisely in allowing a suicidal development of trade, and this question will be again referred to in my concluding remarks.

It is hardly necessary to discuss a duty on all coal raised from the pit's mouth. Such a duty of 2s. per ton was proposed by Pitt in 1784, at the beginning of his great financial career. But it was on the express ground that sea-borne coal was already burdened with duties of long standing, and that equalisation of burdens was desirable. He intended, too, to exempt manufacturers from the impost as far as possible. But

only a week after proposing the tax Mr. Pitt said, with the candour that distinguished his greatness, "From the information he had been able to collect upon the subject, he found men's minds so adverse to the tax, and that it would be necessary to make such a variety of exceptions and regulations in order to prevent it from having an injurious effect on one or other of our manufactures, that he thought it more expedient to abandon the tax."¹

The character of a general tax on coal was truly stated by Robert Bald. "It would unnerve the very sinews of our trade, and be a death-blow to our flourishing manufactories. Were our determined enemy set in council, to deliberate upon a plan to wound us in a vital point as a nation, the advising the imposing of this tax would be the most successful he could possibly suggest." And again he says truly, "A small tax on the ton of coal would be a heavy tax on the ton of iron. The whole of our mining concerns depend as to their prosperity upon the abundance and cheapness of fuel, and if the price be increased by means of taxes the utility of the steam-engine will be greatly abridged."²

¹ Hansard's *Parliamentary History*, vol. xxiv, p. 1215.

² *On the Scotch Coal Trade*, p. 197.

Lord Kames, Sir J. Sinclair, and Adam Smith were the most distinguished of the many writers who deplored the mischief wrought by the old taxes on sea-borne coal, in retarding the progress of towns and country places, where cheap coal might otherwise have been enjoyed. But it is impossible to describe adequately the all-pervading bane that a general tax on coal would be. A rise in the price of coal, whether from taxation or scarcity, must levy open and insidious contributions upon us in a manner with which no other tax whatever can compare. Sydney Smith described how a man in former days was taxed at every step from the cradle to the coffin. But through coals we shall be taxed in everything and at every moment. Our food will be taxed as it crosses the ocean, as it is landed by steam upon the wharf, as it is drawn away by the locomotive, as the corn is ground and the bread mixed and kneaded and baked by steam, and the meat is boiled and roasted by the kitchen fire. The bricks and mortar, the iron joists, the timber that is carried and sawn and planed by steam, will be taxed. The water that is pumped into our houses, and the sewage that is pumped away, and the gas that lights us in and out, will be taxed. Not an article of furniture or ornament,

not a thread of our clothes, not a carriage we drive in, nor a pair of shoes we walk in, but is partly made by coal and will be taxed with it.

And most things will be taxed over and over again at each stage of manufacture. Materials will be burthened in the cost of steam-carriage, and the want of outward coal-freight—in their steam conveyance here—in the machinery that is to manufacture them—the engine to drive the machinery. At every step some tool, some substance, some operation will suffer in cost from the use of taxed coal.

A general coal-tax, too, would be subject to practical difficulties. Coals differ so much in kind and quality and size, that a uniform tax would be prohibitory of the use of small or inferior coals, and great quantities would be lost and burnt upon the waste heaps. An *ad valorem* duty, or one graduated to the size of the coal, would entail endless trouble and fraud.

On coals for domestic use a tax would in theory be very desirable ; but it would entail a change of national habits among a people who look upon a cheerful fireside as one of the most pleasant things in life. It was really a tax on domestic consumption that Pitt proposed, for he intended to exempt all factories largely consuming coal.

But to discriminate the coal used for different purposes would be a difficult or impossible task for the Inland Revenue department.

A tax on coal-gas in domestic consumption might be most readily collected from the inspection of the Gas Companies' books, and would be a beneficial tax in some ways.

Little need be said of other possible modes of legislating with a view to saving coal. To oblige manufacturers to discard old wasteful engines and furnaces would be a wholly unjustifiable interference. It would destroy much property that is now profitable, and render necessary the investment of other capital now profitably engaged elsewhere. And in the building of new engines and furnaces individuals alone can judge properly what forms are most suitable for their purposes, and they are sure not to forget the profit to be derived from a reduced consumption of fuel.

We could hardly prohibit the burning of duff and slack coal on the colliery heaps, seeing that if not lighted they will take fire by spontaneous combustion of the pyrites. To prohibit the screening of coal, again, would deprive many manufacturers of the cheap small coal which is essential to their business. And to attempt to

enforce economical modes of mining and working coal, would be to interfere by legislation in the most uncertain of enterprises, where no rules can be laid down, but the individual circumstances of each pit determine its mode of working.

Nothing is more easy than to suggest that the Legislature should interfere to check the waste of coal so much wanted by posterity. But when we examine the several possible modes of interference it will be found that they all break the principles of industrial freedom, to the recognition of which, since the time of Adam Smith, we attribute so much of our success. Equal objections can be urged against interference with internal industry, or external commerce. To tax home industry would strike more at the root of our industry ; a coal export duty would be less burdensome, but it would lay us open to the imputation of perfidy. The greater part of the world would regard any approach to a new restrictive system as the appropriate sequel to that cunning and successful course of commercial manœuvre which they consider we have pursued since the time of Cromwell. It would seem that we have placed ourselves in a painful dilemma ; we must either retract the professions

we have made to the world and the principles we have so recently adopted, or else we must submit to see our material resources exhausted in a shorter period than could have been thought possible.

The only suggestion I can make towards compensating posterity for our present lavish use of cheap coal is one that it requires some boldness to make.¹ I mean the reduction or paying off of the National Debt. It has long, indeed, become a fashion to talk of this as a chimerical notion. And on various pretexts, but really from "the ignorant impatience of taxation," we go on enduring this vast gap in the capital of the country.

An annual appropriation towards the reduction of the debt would serve the three purposes of adding to the productive capital of the country, of slightly checking our present too rapid progress, and of lessening the future difficulties of the country.

If commenced without delay, and continued with perseverance, the vast debt, now nearly eight hundred millions sterling, might be easily reduced to inconsiderable dimensions

¹ Happily, this proposal no longer calls for exceptional boldness on the part of those who put it forward.

within that period now before us, which we must believe to comprise England's climax of prosperity.¹

A most suitable and unobjectionable mode of effecting the payment presents itself. It is well known that the legacy and succession duties are of a very improvident nature, because they yearly convert a portion of the property of the country into income, and expend it, instead of expending the annual interest only.² The country, to the extent of about one-twentieth of its revenue,³ acts

¹ The course of reduction of the National Debt since Jevons wrote, down to the Boer War, is traced in the following table, which also shows the amount of the increase due to the expenditure in South Africa. The method of reduction has not been that advocated by Jevons in the subsequent paragraphs, but these paragraphs embody points which make it worth while retaining them unaltered. The need of pressing forward with the redemption of the National Debt is more urgent to-day than forty years ago, though the wealth of the nation is greater and the debt somewhat less.

NATIONAL DEBT OF THE UNITED KINGDOM
(Funded and Unfunded)

March 31st	£	March 31st	£
1864	819,677,852	1889	698,430,571
1869	802,922,363	1894	666,154,294
1874	776,017,783	1899	627,562,595
1879	775,646,147	1904	794,498,100
1884	746,423,964	1905	796,736,491

² J. S. Mill, *Principles of Political Economy*, 3rd ed., vol. ii, p. 455.

³ Since the revision of the succession duties by the late Sir W. Harcourt, they have represented a larger fraction of the total national revenue. It is not so certain as is assumed in the text that succession duties operate to reduce capital or restrain its increase. In part they, like other taxes (*cf.* p. 452), are met out of revenue, and, further, out of revenue which would not have been capitalised were the duties not exacted.

the part of a spendthrift in spending what it ought to invest, and trade upon, and transmit to its descendants for their similar use.

Now this investment would be duly made by transferring the whole proceeds of the duty to the Commissioners for the Reduction of the National Debt, not allowing it to enter into the annual balance sheet of the Chancellor of the Exchequer. Of course it would be useless to do this unless the remaining revenue were maintained at least equal to the expenditure. It would be absurd to pay debts on one hand and contract them on the other, in the manner of the old sinking fund. But such is the growing condition of our revenue, that the appropriation could easily be made, had we the patience to refrain for a very few years from *those constant demands for the remission of taxes which are now become an unreasonable habit*. After a very brief period remission of taxes might again go on, gradually accelerated by the reduction of the annual charge of the debt.

At the present time we enjoy the rising tide of prosperity due to the unprecedented commercial reforms of the last twenty years.¹ Are we wise

¹ The reforms of 1842 and about twenty years following that date are referred to.

in pushing our present enjoyment to the extreme by remitting every penny of taxes we can possibly spare? And would not the present appropriation of the legacy duty to a special purpose ensure us future remissions at a time when they will be grateful and useful in contributing to uphold for a little longer a rate of progress which is now, if anything, too rapid?

It cannot be doubted that before long, if at all, an effort must be made to relieve the country of this burden. Writers of the 18th century entertained most gloomy anticipations concerning the growing debt, and they were only wrong in undervaluing the industrial revolution which was then proceeding. But now we run the risk of being too confident, and losing the grand opportunities we enjoy. It is growing wealth that makes a happy and prosperous country, and, no matter what be the absolute wealth of the country at a future time, it is idle to suppose that a popular government with a stationary revenue would ever impose new taxes to pay off an old debt. It is when a surplus revenue grows of its own accord, as at present, that we can alone expect a successful effort to be made.

As a common pretext against any attempt to repay the National Debt it is said that we had

better remit taxes instead, and "leave the money to fructify in the hands of the people." But this is wholly erroneous. Taxes are, partly at least, paid out of income which would otherwise be unproductively expended; part only is subtracted from the fund of productive capital. But in investing the proceeds of a tax in Consols towards the reduction of the great debt, almost the whole money will be added to the productive capital of the country, and will be placed most certainly in the hands which will make it fructify in trade and industrial enterprises.¹

The present Chancellor of the Exchequer² has already devoted a good many millions of surplus revenue to the reduction of the debt, and has converted several millions more into terminable annuities. What is still better, he has often spoken of the debt in a manner which shows he would like to do more. Could a minister be found strong and bold enough to carry out a

¹ J. S. Mill, *Principles of Political Economy*, Book v, chap. vii, § 3.

² The services of Mr. Gladstone, here referred to, in establishing a policy of debt reduction, deserve the encomiums of the latter part of the paragraph. The appreciation, by the Chancellor of the Exchequer of the year of grace 1905, of the obligation to make a beginning of reduction in the newly-augmented debt, was a feature which won him much commendation. This fact shows a notable and welcome change in public opinion in the last generation.

permanent and large measure towards the same end, he would have an almost unprecedented claim to gratitude and fame. And were the work once taken in hand, the notions that the payment of the debt is impossible, or Utopian, or undesirable, would quickly be dispersed. They are mere fallacies of habit.

In regard to our present subject, we find, in the above proposed measure, a legitimate and practicable mode of giving some compensation to our posterity, who will undoubtedly suffer from an increased price of coal, the worst of taxes.

CHAPTER XVIII

CONCLUDING REFLECTIONS

My work is completed in pointing out the necessary results of our present rapid multiplication when brought into comparison with a fixed amount of material resources. The social and political consequences to ourselves and to the world of the partial exhaustion of our mines are of a far higher degree of uncertainty than the event itself, and cannot be made the subject of argument. But, feeling as we must feel, that they will be of an untoward character, it is impossible to conclude this work without a few remarks upon the truly solemn question—Are we wise in allowing the commerce of this country to rise beyond the point at which it can be long maintained?

To say the simple truth, will it not appear evident, soon after the final adoption of Free-trade principles, that our own resources are just those to which such principles ought to be applied

last and most cautiously? To part in commerce with the surplus yearly interest of the soil may be unquestioned gain ; but to disperse so lavishly the cream of our mineral wealth is to be spend-thrifts of our capital—to part with that which can never be reproduced.

After all, commerce is but the means to an end—the diffusion of civilisation and wealth. To allow commerce to expand until the source of civilisation is exhausted is like killing the goose to get the golden egg. Is the immediate creation of the greatest possible quantity of material wealth to be our only purpose? Have we not hereditary possessions in our just laws, our free and nobly developed constitution, our rich literature and philosophy, incomparably above material wealth, and which we are beyond all things bound to maintain, improve, and hand down in safety to posterity? And do we accomplish this duty in encouraging a growth of industry which must prove unstable, and perhaps involve all things in its fall?

But the more is said on one side of this perplexing question, the more there is to say on the other side. It is easy to urge in reply that we can hardly separate the attributes and performances of a kingdom, and have some results

without the others. The resplendent literary genius of our Elizabethan age might never have been manifested but in a period equally conspicuous for good legislation, industrial progress, and general enterprise. The early Hanoverian period, on the contrary, was as devoid of intellectual nobility as it was stationary in wealth and population. A clear and vigorous mind is to be looked for in a wholesome and vigorous state of the body. *Mens sana in corpore sano.* So in our Victorian age may we not owe indirectly to the lavish expenditure of our material energy far more than we can readily conceive? No part, no function of a nation is independent of the rest, and it is possible that in fearlessly following our instincts of rapid growth we may rear a fabric of varied civilisation, we may develop talents and virtues, and propagate influences which could never have resulted from slow restrained growth however prolonged.

Surely the wish could never rise into the mind of any Englishman that Britain should be stationary and lasting as she was, rather than of growing and world-wide influence as she is. To secure a safe smallness we should have to go back, and strangle in their birth those thoughts and inventions which redeemed us from dulness

and degeneration a century ago. Could we desire that Savery and Newcomen had abandoned their tiresome engines; that Darby had slept before the iron ran forth; that the Duke had broken before Brindley completed his canal; that Watt had kept to his compasses and rules; or that Adam Smith had burnt his manuscript in despair? Such experiments could not succeed, and such writings be published among a free and active people in our circumstances, without leading to the changes that have been. Thence necessarily came the growth of manufactures and of population; thence the inexplicable power with which we fought and saved the Continent; thence the initiation of a Free-trade policy by Pitt; the growth of a middle class; and the rise of a series of statesmen—Canning, Huskisson, Peel, Cobden, and Gladstone—to represent their views and powers.

Our new industry had an obscure and unregarded commencement; it is great already and will be far greater yet before it is less. It is questionable whether a country in any sense free can suffer such a grand movement to begin without suffering it to proceed its own length. One invention, one art, one development of commerce, one amelioration of society, follows another almost

as effect follows cause. And perhaps it is well that our national conduct is not prompted by our narrow wisdom nor our selfish desires. Let us stretch our knowledge and our foresight to the furthest, yet we act by powers and towards ends of which we are scarcely conscious.

In our contributions to the arts, for instance, we have unintentionally done a work that will endure for ever. In whatever part of the world fuel exists, whether wood, or peat, or coal, we have rendered it the possible basis of a new civilisation. In the ancient mythology, fire was a stolen gift from heaven ; but it is our countrymen who have really shown the powers of fire, and conferred a second Promethean gift upon the world. Without undue self-gratulation, we may say in the words of Bacon—" The introduction of new inventions seemeth to be the very chief of all human actions. The benefits of new inventions may extend to all mankind universally, but the good of political achievements can respect but some particular cantons of men ; these latter do not endure above a few ages, the former for ever. Inventions make all men happy without either injury or damage to any one single person. Furthermore, new inventions are, as it were, new erections and imitations of God's own works."

When our main-spring is here run down, our fires burnt out, may we not look for an increasing flame of civilisation elsewhere? Ours are not the only stores of fuel. Britain may contract to her former littleness, and her people be again distinguished for homely and hardy virtues, for a clear intellect and a regard for law, rather than for brilliant accomplishments and indomitable power. But our name and race, our language, history, and literature, our love of freedom and our instincts of self-government, will live in a world-wide sphere. We have already planted the stocks of multiplying nations in most parts of the earth, and, in spite of some discouraging tendencies, it is not to be doubted that they will prove a noble offspring.

The alternatives before us are simple. Our empire and race already comprise one-fifth¹ of the world's population; and by our plantation of new States, by our guardianship of the seas, by our penetrating commerce, by the example of our just laws and firm constitution, and above all by the dissemination of our new arts, we stimulate the progress of mankind in a degree not to be measured. If we lavishly and boldly push forward in the creation of our riches, both material

¹ In 1905 fully one-fourth.

and intellectual, it is hard to over-estimate the pitch of beneficial influence to which we may attain in the present. *But the maintenance of such a position is physically impossible. We have to make the momentous choice between brief but true greatness and longer continued mediocrity.*

INDEX

- Ages of emigrants, 229
 Agriculture, changes in, 240-242 ;
 exhaustive, 424
 Agricultural population, 208 ; de-
 crease of, 243 ; implements, 243
 Air-engine, 150
 Alabama iron manufacture, 402,
 408
 Albion mills, 129
 American enterprise, xxxvi, 406
 America, North, coalfields, 338-9 ;
 high wages in, 408
 Anthracite coal, Pennsylvania, 339,
 347
 Appalachian coalfield, 339-40
 Arid region in the United States,
 425
 Arithmetic rate of increase, 247
 Armstrong, Sir Wm., 198 ; address
 to British Association, 3, 32 ;
 Coal Commission of 1871, 147 ;
 hydraulic apparatus, 172, 177
 Atmospheric engine, 119, 143
 Austen Godwin, Mr., quoted, 52
 Australia, coal resources of, 356
 Australian coal competing with
 British, 292, 333
 Babbage quoted, 143, 189
 Bachelors, increase of, 225-6
 Backbarrow charcoal blast-furnace,
 370
 Back-carriage, 292-301
 Bacon, Francis and Roger, 101, 102
 Bacon, on Invention, 458
 Bald, Robert, 16, 105, 443
 Ballast, coal as, 292, 299, 306,
 309 ; freights, 314, 329 ; wharves
 on Tyne, 297
 Balloons, 169
 Banfield on Organisation of Labour,
 241
 Beaumont, inventor of railway, 123
 Belgium, coal production, 336,
 365 ; iron production, 399
 Bessemer steel, 130, 389, 398, 401
 Birmingham, artisans at, 118
 Bituminous coal of Pennsylvania,
 348, 408
 "Blackmine" coal seam, 89
 Blast-furnace, fuel of, 345 ; waste
 gases of, 155, 389
 Bloomary, 245
 Bourne, quoted, xxxv
 Boyd Dawkins, Professor, 53
 Bramah, 173
 Briavoinne, quoted, 119
 Bridgewater, Duke of, 121 ; canal,
 122, 169 ; treatise, 16
 Brindley, 129, 143, 168
 British coal-production, 265, 266,
 365-7 ; Empire, resources of,
 xvii, 364 ; industry, two periods
 of, 234 ; ports, tonnage of, 258,
 301 ; steam-vessels, 254
 Brough, Mr. Bennett H., xv, 352,
 359, 361, 363, 370
 Buckland, Dr., 16, 18, 19, 45, 298,
 437
 Bulwer, Caxtonian essays, 13
 Bunker-coal, viii, 139, 319
 Camden, quoted, 372
 Campbell's Survey, quoted, 110
 Campine, La, coalfields, 336
 Canada, coalfields of, 353-5 ; coal
 production of, 356 ; migration
 to, 227, 427
 Canals, 121
 Cannel coal, xliii

- Cape Breton coal, 330, 353
 Cardiff, price of coal at, 91
 Cargo, preponderance of home-ward, 301, 315
 Caus, Isaac de, 115; Solomon de, 114
 Charcoal iron manufacture, 245, 345, 370-80
 Cheap fuel, its effects, xxxv
 Chemical processes and coal, 134-5
 Cheshire salt mines, 134
 China, coal in, 361
 Clyde, outward cargoes from the, 304
 Coal consumption in the United Kingdom, 192; estimates of coal produced, 264, 267, 268; estimates of coal resources of United Kingdom, 38-9; export duty, 313; exports, value of, 91; exported in 1869 and 1903, 139; importance of, xxxiv, 1; loss in working, 47, 48; produced in the United Kingdom, 265, 266, 365-7; in different countries, 322, 365; raised in France, 335, 365-7; raised in Germany, 337, 365-7; raised in the United States, 339, 352, 365-7; rate of increase of consumption, xiii, xx, 268-9, 280-1, 365; resources of various countries, 320, 323, 325; specific gravity of, 40; under the sea, 39, 49; used in iron-making, 139, 369
 Coalbrookdale coalfield, 26; works, 123, 176, 384; engine at, 129; iron bridge at, 127
 Coal-cutting machine, 66, 76
 Coalfields, Appalachian, 339-40; Belgian, 337; beneath cretaceous formation, 52; Chinese, 361; concealed, 50-55; contents of British, 24, 38; Fifeshire, 16; Flintshire, 26; Forest of Dean, 46, 49; foreign, 323, 325; French, 44, 328, 331; German, 326, 337; Japanese, 359; Lancashire, 44; Newcastle, 17, 42, 46; ninety-fathom dyke, 44-5; New South Wales, 357; North America, 338-9; Nova Scotia, 353; Scotch, 17, 27, 43; Staffordshire, 26; Yorkshire, 49, 50
 Coal miners, numbers of, 277
 Coal ports, freights to, 305, 307
 Coal-tax, impolicy of, 310, 440-5
 Coal-towns, Northern, growth of, 217
 Coal trade reciprocal, 295
 Coasting trade, 295-6; in coal, 296
 Coke, invention of, 382
 Collier, meaning of name, 371
 Collier fleet of Newcastle, 309, 310
 Collieries, number of, 32, 278
 Colliery-consumption of coal, 49
 Colliery, staff of a, 64-5
 Colonisation, 219-21, 421, 423
 Colorado, coal of, 350
 Commercial revolution, 232
 Competition, of foreign coal, 292, 307, 317; in foreign trade, 414
 Compressed air as motive power, 173
 Consumption of coal, 196, 270, 272; in 1869 and in 1903, 139; in past times, 271, 273
 Conybeare and Phillips, *Outlines of Geology*, 37
 Cornish engines, xxxv; duty of, 146; supply of coal, 295
 Corn, imports and exports of, 238; laws, 237, 241, 256; repeal of, 195; trade, 236
 Cort, puddling furnace, 387
 Cost of getting coal, average, 343
 Cotton imports and consumption, 251; trade, 236
 Courtney, Rt. Hon. Leonard, 91
 Cretan laws, xlv
 Crossley, Mr. W. J., on economy of gas engines, 152
 Crow's Nest Pass Coalfield, 354
 Darby, Abraham, 176, 384
 Dawson, Dr. G. M., on coal resources of Canada, 355
 Dee river, power of tides, 179
 Deep mining, limit of, xxxvii, 7, 57, 61-3
 Depth of mines, 58-9, 274; in the United States, 342
 Domestic consumption of coal, 138, 139
 Dover, coal at, 54
 Dowlais ironworks, 165
 Drainage of mines, 68-72, 113

- Drake, Mr. N. F., on Chinese coal resources, 361
- Dudley, Dud., quoted, 81; iron made by, 382
- Dukinfield deep pit, xxxvii, 58, 89
- Dundonald, Earl of, on salt trade, 302
- Duration of Northern coalfield estimates, 18; of coalfields of Europe, 362-3
- Dutch in England, 107; manufactures, 111; manufacture of iron, 381; trade, 109; workmen, 384
- Dynamo-electric machine, 181
- Earthenware trade, 303
- Ebbw Vale ironworks, 248
- Economy of use increases consumption, xxxiv, 141, 142
- Edgeworth, Richard Lovell, 167
- Education, public, xxii, xlviii
- Efficiency of steam-engine, 145-7; of gas-engine, 152
- Electricity, 160, 170
- Electro-magnetic engine, 180
- Emigration, 10, 220, 420; direction of, 227; effects of, 221, 230, 424
- Employment of children in factories, xxii, xlviii
- Energy, 161; developed in burning coal, 137, 186
- English coalfields, 329, 331-2
- Ericsson's engine, 150
- Exhaustion of European coalfields, 362; of our coal mines, xxix
- Export duties, 313; influence on freights, 440; instances of, 135, 139; policy of, 438
- Exports, declared value of, 1801-1905, 255; of coal, 313, 318-9, 418; value per ton, 91; net from various countries, 333; policy of, 312; weight of, 315
- Exports of machinery, prohibition of, 104
- Fairbairn, 128, 411; address to British Association, 131, 153
- Flemings, 109, 111
- Foot-blast, 371
- Forest of Dean, 49, 371, 378
- Forests, source of fuel, 183
- Frech, on duration of coal supplies, 362
- Free trade, 286, 314, 410, 431, 434, 455
- Freight rates, 306-7; effect of export duty on, 440; on coal in the United States, 99; Odessa and Argentina to England, 299
- French coal imports, 314; coal production, 335, 365-7; iron production, 399; manufactures, 111; Treaty of 1860, 5, 182, 439, 441
- Friar's Goose Colliery, 71
- Fuel gas, 151
- Future probable consumption coal, 270, 282
- Garforth, Mr. W. E., on coal-cutting machines, 66
- Gas, 127-8; engine, 151-2; natural, 185; tax on, 446; works, coal used by, 139
- Gee, Joshua, on British iron trade, 379
- Geological map, 45
- Geometrical ratio, growth in, 192-4, 245
- Georges Creek, 351
- German metallurgists, 381; miners, 104
- Germany, coal production of, 337, 365-7; coal resources of, xiv, 326; industrial progress of, xv, 326, 416; iron production of, 367, 399
- Gilchrist-Thomas, basic steel, 390-1, 400
- Gladstone, Rt. Hon. W. E., 288, 441, 452
- Griffith, Mr. Wm., estimate of coal in Pennsylvania, 348
- Grimsby, Port of, 306
- Gunpowder use in blasting, 105
- Hall, T. Y., 19, 299
- Harris, Mr., on anthracite coal output, 346
- Harrison chronometer, 113
- Harvest of wheat, British, 240
- Haswell pit, sinking abandoned, 71
- Hearn's *Phutology*, 168, 197
- Heat, source of, 182; effect of, on working power, 61
- Herring fishery, 109

- Herschel, Sir John, xxxix
Hewitt, *Statistics of Iron Trade*, 379, 434
Hilton ware, 384
Hogge, Ralph, Sussex ironmaster, 107
Holland, John, *History of Fossil Fuel*, 20
Hooson, quoted, 105
Horse-power, coal used per, 138, 145-8; used in factories, 177
Hot-blast iron furnace, 154, 387
Hot springs of Ischia, 189; of Iceland, 189
Houghton, John, quoted, 380, 421
Hull, Edward, xlv, 7, 19, 23-31, 42, 47, 50, 57, 270
Hunt, Mr. Robert, cannel coal supply, xliii; prices of coal in 1860, 87; statistics of output, xlii, 34, 265
Hutton seam, 70, 89
Hydrogen gas, 182
- Ice machine, 136
Iceland, hot springs of, 189
Immigration into the U.S., 227-9
Import-duty on coal, Russian, 299
Imports, official values, 1700-1869, 252-3; real values, 1854-1905, 254; of continental iron, 379; of coal impossible on a large scale, 290, 317; weight of, 315
Inheritances, tax on, 449
Internal combustion engines, 151
International trade, 413
Inventions, 197; Bacon on, 458; conditions of, 112; history of, 100
Ireland, absence of manufactures, 288; devoid of coal, 202; emigration from, 203, 211, 220; former production of iron, 376; policy, 203
Iron, boundless use of, 405; bridges, 127; export of pig, 247; importance, 368; in America, 406; in Scotland, 386, 388; in 1740, 379; in 1862, 397; in 1904, 399; increase of produce, 386, 400; made with pit coal, 381-5; manufacture, conditions of, 391, 408; ore carried to fuel, 396; ore supplies, 403-4; production of, 246, 367; quality of, 398; rails first used, 123; steam vessels, 132; steel substituted for iron, 130, 390; substitution of iron for wood, 129, 390; supply from distance, 393; used in machinery, 128; wrought iron substituted for cast, 129
Iron and steel industries, coal used by, 139, 140, 369
Japan, coal resources, 359; coal production, 359; competition of, with British coal, 292, 333
Jeans, J. S., on iron-ore supplies, 403-4
Jessop, William, 124
Jocteleg, or jack-a-legs knife, 106
Kaltoff, Marquis of Worcester's servant, 116
Kane, Sir Robert, 179, 184
Kelvin, Lord, on fuel supply, 189
- Labelye, Swiss architect, 107
Laird, Sir Wm., on coal export from Liverpool, 305
Lake Superior iron-ore trade, 308, 401, 407
Lanarkshire, exhaustion of coal in, 27
Lancashire, East, coal shipped from, 305; coal from thin seams in, 74
Lardner, Dr., on discovery, 159
Lee, William, inventor of knitting-frame, 103
Legacy duty, 449
Liebig, 142, 163; criticism of Bacon, 102; on electro-magnetic engine, 181; on sulphur production, 135
Lignite produced in Germany, 337
Lincolnshire fens, drainage of, 178
Liverpool, Port of, 257; export trade, 302, 304
Locke, remark on iron, 131
Lombard Street, merchants of, 110
Lombe, Sir Thomas, 112
London, coal imported, 263; population of, 218
Lothringen, iron ores of, 391
Lozé, estimate of coalfields, 323
- McCulloch, 18, 22, 264, 267, 268 386
Machine tools, 130

- Mackworth, Sir Humphrey, 167
 Magnesian limestone, 51
 Malthus, law of population, 194-5
 Manufacturing population, 215
 Maritime enterprise, 108
 Marriage-rate, xxxii, 10, 223-4
 Mathews, Mr. Wm., quoted, 28
 Maximum estimated output of
 anthracite in United States, 346;
 of coal in Great Britain, 31
 Mersey, coal shipped from, 305
 Mesabi iron ores, 401
 Metallurgy, 105
 Meurthe et Moselle, discovery of
 coal in, 335
 Migration into towns, 212
 Mill, J. S., on international trade,
 414; on National Debt, xxxix;
 on Protection, 433
 Mine-workers, classes of, 64-5
 Mineral statistics, 5, 264
 Mining Record Office, xlv, 23, 265
 Monkwearmouth pit, depth of, 57;
 sinking of, xxxvii; temperature
 in, 58
 Morrill tariff, 247, 430, 435
 Mundella, 142, 267
 Murton winning, sinking of, 69
 Nanaimo coal basin, 355
 Nasse, estimates of coal resources,
 324-5
 National Debt, xxii, xxxix, 448-9
 Neilson, discoverer of hot-blast, 387
 New River, London water supply,
 127
 Newcastle coalfield, 17; duration
 of, 18; output of, 18, 19; price
 of coal at, 83-5; Vend of coal
 from, vii, 262
 Newcomen's engine, 119, 143
 New South Wales, coal production,
 358; coal resources, 356
 Norden, *Surveyors' Dialogue*, 372,
 380
 Nova Scotia, coal resources, 354;
 iron-ore in, 355
 Overstone, Lord, on export duty,
 439
 Packhorse conveyance, 292, 303,
 396
 Papin, Denis, 118, 173
 Parties, conflict of, 12, 13
 Pauperism, cost of, 209
 Peat, 184
 Peel, Sir Robert, proposed tax on
 coal, 1842, 299, 438
 Pennsylvania, coal of, 339, 408;
 iron manufacture of, 402
 Percy, Dr., 36, 105, 182, 405
 Permian formation, 52
 Petroleum, 184-5
 Pit coal, 371
 Pitt's proposed tax on coal, 442
 Pittman, E. F., on coal in New
 South Wales, 356
 Pittsburg coal seam, 341; steel
 manufacture, 402, 428
 Platt and Co. of Oldham, 128
 Platte, Hugh, 114
 Population, decrease of agricultural,
 243; of agricultural counties,
 208, 243; of England and Wales,
 205; of manufacturing counties,
 208; of Scotch highlands, 211,
 423; of Scotch manufacturing
 counties, 212; increase of, 192,
 203; law of, 9, 192-5
 Porter, quoted, 133; on the poor-
 rate, 210
 Postlethwayt, quoted, 375, 380
 Potash, supply of, 135
 Potteries, situation of, 304
 Pressure, effects of increase of, in
 steam-engines, 149
 Price of coal at Baltimore, 98; at
 Cardiff, 91, 93; at Newcastle,
 83-5, 290; at Pittsburg, 343; at
 the pit's mouth, 95, 97, 98, 343;
 exported, 91, 95; in different
 countries, 97, 98, 343; in 1860,
 Mr. Hunt, 87; in Manchester,
 1760, 122; in New South Wales,
 357; in Staffordshire, 81, 96;
 reduced by steam-engine, 120
 Price-Williams, Mr. R., on future
 output, x, 279
 Producer-gas, 151
 Progress, when uniform, 191-3
 Production of coal, 1855-1904, 280;
 in various countries, 365
 Prohibition of export, of coal, 312;
 of machinery, 104
 Protection, 433; in colonies, 430
 Proximity of fuel and iron ore, 391,
 397, 401, 408
 Queensland, coal in, 356

- Railways, 122; coal used by, 139;
 converge on coalfields, 125; in-
 fluence on iron manufacture,
 407; rates on return traffic, 294
 Ramsay, Professor, 45
 Rankine, 148
 Rate of progress, 191, 245
 Regenerative furnace, 154
 Rennie, 129, 178
 Resources of British coalfields, 24
 Restrictions on coal trade, 446-7
 Reversal of trades, 134, 286-7
 Rickman on increase of population,
 213
 Roads, 120
 Roebuck, iron trade in Scotland,
 386
 Rogers, Professor, estimate of coal-
 fields, 323; on coal-cutting
 machine, 66
 Rouher, M., quoted, 289
 Royal Commission, coal-cutting
 machines, 66; consumption of
 coal in the past, 271; consump-
 tion of coal per horse-power, 147;
 deduction for loss in working,
 48; effect of pressure on work-
 ing of mines, 62; estimate of
 resources, xv, 24, 38-9; on
 working thin seams, 42, 73, 76;
 petroleum as a fuel, 185; purposes
 for which coal is used, 139; rate
 of increase of output, xiii;
 water-powers available in Great
 Britain, 171; windmills, 165
 Runcorn, coal staiths, 305

 Safety lamp, 67
 Salt trade reversed, 134; of Liver-
 pool, 302
 Sanderson, Dr. J. Burdon, on
 working in hot mine, 61
 Sauerbeck's Index Number com-
 pared with price of coal, 91
 Savery, Thomas, 115, 117, 143,
 175
 Scheldt, coal under mouth of, 336
 Schladebach deep boring, 59
 Scotland, its population and in-
 dustry, 204
 Screening of coal, 86-7, 446
 Scrivenor, *History of Iron Trade*,
 384, 393
 Sea-coal, 371, 374
 Seaport towns, growth of, 214

 Senior on emigration, 423
 Shansi coalfields, 361
 Shipment of coal, 329
 Shipping, tonnage entering and
 clearing, 258; with cargoes and
 in ballast, 301
 Shropshire coal production, 27
 Sicilian tax on sulphur, 135, 439
 Siemens regenerative furnace, 154
 Simmersbach, on coal resources of
 the world, xiv, 325, 363
 Sinclair, Sir John, *Statistical Ac-
 count of Scotland*, 15
 Slitting mill, 107
 Smeaton, 119, 143, 387
 Smelting furnace, birthplace of,
 123
 Smiles, history of invention, 102,
 107, 382
 Sopwith, Mr. T., xliv, xlv, 21,
 265
 South Hetton colliery, 64
 Spinsters, increase of, 225-6
 Staffordshire, potteries, 304; South,
 coalfield, 27, 28; drainage of
 mines, 71; iron manufacture, 77,
 393-5; "thick" coal of, 342;
 price of "thick" coal, 80-1
 Stationary state, xxxi, 232, 429
 Steam colliers, 166; communica-
 tion, 165-6
 Steam-engine, 112, 120; coal con-
 sumed per horse-power, 144;
 effect of improvements in, 153;
 effect on mines, 120; exported,
 119; history of, 143; improve-
 ment of, 144; used to increase
 water-power, 175, 385
 Steam-plough, 153
 Steam-power, cost of, xxxiv; used
 in textile factories, 177
 Steam vessels, and sailing ships,
 133; maintained on British coal,
 316; tonnage of British, 259
 Steel, made at Pittsburg, 409; sub-
 stituted for iron, 130, 390
 Stephenson, George, 17, 67, 126;
 Robert, 132
 Sterling's air-engine, 150
 Stevin, Simon, wind-waggon, 167
 Sturtevant, 103, 381
 Substitution of commodities, 134
 Succession duties, 449
 Sulphur, sources of, 135
 Sun-engine, 190

- Sussex ironworks, 372, 395
 Swansea, copper smelting, 295
 Sydney harbour, coal at, 330, 358
- Tax on coal, 310, 441
 Temperature of mines, 59-61
 Temple, Sir Wm., on iron-making in Ireland, 376
The Trades' Increase, quoted, 109, 309
 Thin seams, working of, 72-6
 Thomas and Gilchrist, steel making, 390, 400
 Thomas, Mr. D. A., on our foreign trade in coal, 314, 332-3
 Tidal mills, 180
 Timber, as fuel, 183; destruction of, 374-8; quantity imported, 250
 Tonnage of British ports, 258, 301
 Trading bodies, problem of, 410
 Transport of coal, 289-90, 328
 Tyndall, Professor, quoted, xl-xlii
- United States, coal exports from, 317; coal production in, 339, 352, 365-7; coal resources of, 338-51; immigration, 229; iron production, 367, 399; population, 426; resources of, 344; steel industry, 428
 Utilisation of waste heat, 155
- Vancouver Island, coal in, 355
 Vend, from Newcastle, vii, 262; limitation of the, 86
 Ventilation of coal mines, 61, 68
 Victoria, coal resources of, 356
- Vivian, H. H., xxiv, xxxvi, xxxvii, 276
- Wages, high in America, 408
 Wales, South, coalfield, 17, 24, 38
 Wallsend coal prices, 88
 Waste gases of blast-furnace, 155, 389
 Waste of coal, 266, 272
 Water, accumulation of, in Permian and New Red Sandstone rocks, 52, 72
 Water, -mills, 129; -power, 119, 171-4; effect on iron-making, 372, 385, 386; -supply of towns, 177; supply-pipes, 127
 Watt, 144, 146, 153, 187
 West Ardsley Colliery, 66
 Welds of Sussex, 371, 374
 Wheat, and coal, exchange of, 308; British harvest of, 240; imports and exports of, 238
 Whitaker, Mr. W., quoted, 53
 Williams, John, 15
 Williamson, Mr., on weight of imports and exports, 315
 Willoughby, Sir Francis, 293
 Windmills, 108, 164-5
 Wind-waggons, 167
 Wooden water pipes, 127
 Wool trade, 235
 Woolf's double cylinder, 144
 Worcester, Marquis of, 115, 116, 174-5
 World's coal production, viii, 365-6; iron production, 399
- Yarranton, 79, 112, 121, 383
 Young, John, millwright, 108

THE END